

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	(50-5) HBK-2	LASALLE	331	13
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

WOVEN WIRE FENCE, 4' 66500105	
LOCATION	(FT)
MARSEILLES	
LT, 112+99 TO LT, 114+03	110
RT, 112+99 TO RT, 113+98	99
LT, 126+10 TO LT, 127+01	91
RAMP C	
RT, 401+07 TO RT, 412+62	1140
RAMP D	
RT, 519+74 TO RT, 522+24	270
TOTALS:	1710

TEMPORARY CONCRETE BARRIER		
LOCATION	TEMPORARY CONCRETE BARRIER (FT) 70400100	RELOCATE TEMPORARY CONCRETE BARRIER (FT) 70400200
MARSEILLES		
RT, 117+50 TO 122+25, STAGE 2A		475
F.A.I. 80		
501+58 TO 526+10, STAGE 1B	2478	
862+68 TO 319+32, STAGE 1B	2044	
LT, 837+15 TO 838+85, STAGE 1B		170
RT, 837+15 TO 838+85, STAGE 1B		170
LT, 843+00 TO 846+35, STAGE 1B		335
RT, 843+00 TO 846+35, STAGE 1B		335
820+28 TO 419+16, STAGE 2B	1891	
2035+54 TO 225+57, STAGE 2B	2328	
TOTALS:	8741	1485

SHOULDER RUMBLE STRIPS 64200105	
LOCATION	(FT)
RAMP A	
RT, 201+72 TO 226+10	2438
LT, 201+19 TO 210+32	913
RAMP B	
RT, 300+00 TO 319+99	1999
LT, 307+52 TO 320+08	1256
RAMP C	
RT, 400+00 TO 419+94	1994
LT, 407+50 TO 420+03	1253
RAMP D	
LT, 501+19 TO 510+72	953
RT, 501+72 TO 526+45	2473
F.A.I. 80	
LT, 810+70 TO 872+30	6282
RT, 810+70 TO 872+30	6401
TOTALS:	25961

STEEL PLATE BEAM GUARDRAIL				
LOCATION	STEEL PLATE BEAM GUARD RAIL, TYPE A (FT) 63000000	TRAFFIC BARRIER TERMINALS		TERMINAL MARKER DIRECT APPLIED (EACH) 78201000
		TYPE 1, SPECIAL (FLARED) (EACH) 63100169	TYPE 6 (EACH) 63100085	
MARSEILLES				
RT, 116+72.5 TO 117+22.5		1		1
LT, 116+73.9 TO 117+23.9		1		1
RT, 117+22.5 TO 118+60.0	137.5			
LT, 117+23.9 TO 118+61.4	137.5			
RT, 118+60.0 TO 119+03.1			1	
LT, 118+61.4 TO 119+04.5			1	
RT, 120+95.6 TO 121+38.8			1	
LT, 120+97.0 TO 121+40.2			1	
RT, 121+38.8 TO 121+88.8	50.0			
RT, 121+88.8 TO 122+38.8		1		1
LT, 121+40.2 TO 122+77.7	137.5			
LT, 122+77.7 TO 123+27.7		1		1
TOTALS:	462.5	4	4	4

POLYUREA TYPE II PAVEMENT MARKINGS										
LOCATION	LINE 4" (WHITE) (FT) 78008310	LINE 4" (YELLOW) (FT) 78008310	LINE 6" (WHITE) (FT) 78008330	LINE 8" (WHITE) (FT) 78008340	LINE 12" (WHITE) (FT) 78008350	LINE 24" (WHITE) (FT) 78008370	LETTERS AND SYMBOLS (WHITE) (SQ FT) 78008300	PERFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 6" (WHITE) (FT) 78003130	RAISED REFLECTIVE PAVEMENT MARKER (EACH) 78100100	RAISED REFLECTIVE PAVEMENT MARKER BRIDGE (EACH) 78100105
MARSEILLES										
101+50 TO 127+00	3479	1546	600				53		83	14
127+00 TO 139+60	2520	1768							30	
RAMP A										
200+00 TO 226+12	2589	941		863	454					
RAMP B										
300+00 TO 320+82	2200	1280		725	443	36	18			
RAMP C										
400+00 TO 420+77	2194	1277		726	393	36	18			
RAMP D										
500+00 TO 526+55	2632	981		866	461					
F.A.I. 80										
807+40 TO 834+00	3834	5320	262	1395				1330	132	
834+00 TO 864+00	5379	6000	181	1398				1500	152	
864+00 TO 875+60	2575	2320	81					580	60	
TOTALS:	27402	21433	1123	5973	1751	72	88	3410	457	14

TEMPORARY PAVEMENT MARKING AND REMOVALS									
LOCATION	TEMPORARY PAVEMENT MARKING						SHORT TERM PAVEMENT MARKING (FT) 70300100	PAVEMENT MARKING REMOVAL (SQ FT) 78300100	WORK ZONE PAVEMENT MARKING REMOVAL (SQ FT) 70301000
	LINE 4" (WHITE) (FT) 70300220	LINE 4" (YELLOW) (FT) 70300220	LINE 6" (WHITE) (FT) 70300240	LINE 8" (WHITE) (FT) 70300250	LINE 12" (WHITE) (FT) 70300260	LINE 24" (WHITE) (FT) 70300280			
MARSEILLES									
101+50 TO 127+00	12163	10613				22	510	4640	7891
127+00 TO 139+60	5579	5579					252	2520	3845
RAMP A									
200+00 TO 226+12	2457	834		122			522	200	1440
RAMP B									
300+00 TO 320+82	1593	538				45	416	200	1009
RAMP C									
400+00 TO 420+77	3197	1999		122		58	415	200	2137
RAMP D									
500+00 TO 526+55	3238	1503					531	200	1846
F.A.I. 80									
807+40 TO 834+00	15396	14640	563	1310	217		1458	6268	12113
834+00 TO 864+00	14317	11755	1249	913	152		1800	6042	10975
864+00 TO 875+60	5980	3980					618	2318	3629
TOTALS:	63920	51441	1811	2467	369	125	6523	22588	44884

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION FAI ROUTE 80 (I-80 AT MARSEILLES INTERCHANGE) SCHEDULE OF QUANTITIES SCALE: NONE DATE: 11/02/07
NAME	DATE	



DRAWN BY: KM
CHECKED BY: SE