

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	(50-5) HBK-2	LASALLE	331	18
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

LOCATION	EARTH EXCAVATION (CU YD) 20200100	EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR SHRINKAGE (25%) (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)	TOPSOIL EXCAVATION AND PLACEMENT (CU YD) 21101505
MARSEILLES					
101+50 TO 139+50	-	-	-	-	-
RAMP A					
200+00 TO 226+10	4005	3004	974	2030	-
RAMP B					
300+00 TO 321+20	-	-	-	-	-
RAMP C					
400+00 TO 421+15	1753	1315	3803	-2488	-
RAMP D					
500+00 TO 526+45	-	-	-	-	-
TOTALS:	5758	4319	4777	-459	0

LOCATION	EARTH EXCAVATION (CU YD) 20200100	TOPSOIL EXCAVATION (CU YD)	EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR SHRINKAGE (25%) (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)	TOPSOIL EXCAVATION AND PLACEMENT (CU YD) 21101505	EXCESS TOPSOIL (CU YD)
MARSEILLES							
101+50 TO 139+50	13964	2714	10473	9566	906	2223	490
TEMP MARSEILLES							
101+50 TO 139+50	491	-	368	593	-225	-	-
RAMP A							
200+00 TO 226+10	4422	1416	3317	4694	-1377	1355	61
TEMP RAMP A							
2001+50 TO 2003+50	677	-	507	1040	-533	-	-
RAMP B							
300+00 TO 321+20	14285	1923	10714	3371	7343	1805	118
TEMP RAMP B							
3010+00 TO 3012+00	236	-	177	172	4	-	-
RAMP C							
400+00 TO 421+15	6889	1966	5167	7191	-2024	1601	365
TEMP RAMP C							
4017+50 TO 4022+00	278	-	208	300	-92	-	-
RAMP D							
500+00 TO 526+45	6307	1632	4730	4159	571	1560.91	71
TEMP RAMP D							
5001+00 TO 5005+50	400	-	300	728	-428	-	-
F.A.I. 80							
810+70 TO 872+30	6365	1825	4774	6365	-1591	1825	-
TOTALS:	54312	11476	40734	38179	2555	10371	1105

STAGE	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)	CUMULATIVE EARTHWORK FURNISHED EXCAVATION 20400800 (CU YD)
PRESTAGE	555	555
1A	-427	128
1B	2000	2128
2A	-3286	-1158
2B	-459	-1617
3	4172	2555
TOTALS:	2555	-1617

LOCATION	EARTH EXCAVATION (CU YD) 20200100	EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR SHRINKAGE (25%) (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)	TOPSOIL EXCAVATION AND PLACEMENT (CU YD) 21101505
MARSEILLES					
101+50 TO 139+50	2507	1880	1593	287	2223
RAMP A					
200+00 TO 226+10	157	118	0	118	1355
TEMP RAMP A					
2001+50 TO 2003+50	677	507	0	507	-
RAMP B					
300+00 TO 321+20	-	-	-	-	-
RAMP C					
400+00 TO 421+15	460	345	32	313	1601
TEMP RAMP C					
4017+50 TO 4022+00	247	185	0	185	-
RAMP D					
500+00 TO 526+45	-	-	-	-	-
F.A.I. 80					
810+70 TO 872+30	5215	3912	1150	2762	1825
TOTALS:	9264	6948	2776	4172	7005

REVISIONS	
NAME	DATE



ILLINOIS DEPARTMENT OF TRANSPORTATION
 FAI ROUTE 80 (I-80 AT MARSEILLES INTERCHANGE)
SCHEDULE OF QUANTITIES
 SCALE: NONE
 DATE: 11/02/07
 DRAWN BY: KM
 CHECKED BY: SE