

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
180	06-111	BUREAU	10	3
FED. ROAD DIST. NO.	ILLINOIS			

SUMMARY OF QUANTITIES

CONSTRUCTION CODE TYPE: SFTY-2A

CODE NO.	ITEM	UNIT	RURAL 100% STATE TOTAL QUANTITY
20400800	FURNISHED EXCAVATION	CU YD	50.6
25101005	HEAVY DUTY EXCELSIOR BLANKET	SQ YD	50
50102400	CONCRETE REMOVAL	CU YD	1.9
50200100	STRUCTURE EXCAVATION	CU YD	50.6
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	200
51205200	TEMPORARY SHEET PILING	SQ FT	752
54003000	CONCRETE BOX CULVERTS	CU YD	1.9
67100100	MOBILIZATION	L SUM	1
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1
X0322121	SHEET WATERPROOFING MEMBRANE SYSTEM	SQ YD	27

Date: 10/30/2007
c:/projects/cmain08/cm316/details.dgn

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
 FAI ROUTE 180 (I-180) SECTION 06-111
 STA. 157+00
 BUREAU COUNTY
 S.N. 06-2000