

SCOPE OF WORK

MILE POST	STR. NUMBER	LANE	GR REMOVAL	SPBGR TYPE A	TBT TYPE 1 SPEC (TANG)	TERM MKS DA	TBT T6	TBT T2	IMP ATTN NON-RE T1 3	FURN EX	CONC STRUCT.	P.CULV. CL "D" TYPE 1, 15"	METAL END SECTIONS, 15"	REBAR EPOXY COATED	REM & REERECT GR	CURB REMOVAL	CLASS SI CONC (MISC)	CONC CURB TYPE B	SCOPE OF WORK
			FOOT	FOOT	FACH	FACH	FACH	FACH	FACH	FACH	CU YD	CU YD	FOOT	FACH	POUNDS	FOOT	FOOT	CU YD	FOOT
50.2	006-0014	EBDL	50		1	1				5					120		4.4	120	1,4,5,10
50.2	006-0014	FBPI	200	300	1	1				5					120		4.4	120	4,5,8,10
50.2	006-0015	WBPI	50		1	1				5					120		4.4	120	1,4,5,10
50.2	006-0015	WBPI	200	300	1	1				5					120		4.4	120	4,5,8,10
50.4	006-0016	EBDL	44		1	1	1			5					30	5	0.2	5	1,2,4,6,10
50.4	006-0016	FBPI	244	300	1	1	1			5					30	5	0.2	5	2,4,6,8,10
50.4	006-0017	WBPI	44		1	1	1			5					30	5	0.2	5	1,2,4,6,10
50.4	006-0017	WBPI	244	300	1	1	1			5					30	5	0.2	5	2,4,6,8,10
	006-0124	ER	44		1	1	1			5					30		1.1	44	1,2,4,5,10
	006-0124	MEDIAN	350						2										7
52.1	006-0124	WR	44				1								30		1.1	44	2,5,10
52.2	NO STRUCTURE	WBPI	50		1	1				5									1,4
54	006-0151	EBDL	44				1								30		1.1	44	2,5,10
54	006-0151	FBPI	200	300	1	1				5					30		1.1	44	1,4,5,10
54	006-0152	WBPI	44				2										1.1	44	1,2,5
54	006-0152	WBPI	200	300	1	1	1			5							1.1	44	1,2,4,5
	006-0116	ER	94		1	1	1			5	1.4			167			1.1	44	
	006-0116	MEDIAN	350						2										7
54.4	006-0116	WR	44				1										1.1	44	2,5
54.9	NO STRUCTURE	EBDL	50		1	1				5									1,4
55.2	NO STRUCTURE	WBPI	50		1	1													1,4
	006-0162	ER																	NO WORK
	006-0162	MEDIAN	400						2		5			675					7,9
56.3	006-0162	WR																	NO WORK
59.9	SIGN TRUSS	MEDIAN	150						2										7,11
	006-0131	ER	138		1	1	2			5							2.2	88	1,2,4,5
	006-0131	MEDIAN	285						2										7
60.3	006-0131	WR	94		1	1	1			5							1.1	44	1,2,4,5
60.5		EBDL	50		1	1				5									
60.5	SIGN TRUSS	MEDIAN	150						2										7,11
	006-0038	ER																	NO WORK
	006-0038	MEDIAN	100						2										7
60.7	006-0038	WR																	NO WORK
	006-0039	ER																	NO WORK
	006-0039	MEDIAN	100						2										7
60.7	006-0039	WR																	NO WORK
61	SIGN TRUSS	MEDIAN	150						2										7,11
61.2	NO STRUCTURE	EBDL	50		1	1													1,4
	006-0127	ER	94		1	1	1			5							1.1	44	1,2,4,5
	006-0127	MEDIAN	360						2										7
62.2	006-0127	WR	94		1	1	1			5							1.1	44	1,2,4,5
62.3	SIGN TRUSS	MEDIAN	300						2										7
	006-0132	ER	44				1										1.1	44	2,5
	006-0132	MEDIAN	200						2										7
63.5	006-0132	WR	94		1	1	1			5							1.1	44	1,2,4,5
65.3	SIGN TRUSS	MEDIAN	150						2										7,11
	006-0129	ER	94		1	1	1			5							1.1	44	1,2,4,5
	006-0129	MEDIAN	290						2										7
66.4	006-0129	WR	88				2										2.2	88	2,5
	006-0133	ER	94		1	1	1			5							1.1	44	1,2,4,5
	006-0133	MEDIAN	400						2										7
67.5	006-0133	WR	94		1	1	1			5							1.1	44	1,2,4,5
72.9	SIGN TRUSS	MEDIAN	200						2	15		75	2						3,7,12
			11911	3000	46	46	56	12	48	225	6.4	150	4	842	1080	80	65.86	2532	

SCOPE OF WORK LEGEND: 1.REM DEFICIENT E.S. AND REPLACE W/TYPE 1 E.S. 2. REM DEFICIENT END SECTION/REPLACE W/TYPE 6 E.S. 3.ADD PIPE CULVERT NEAR PIER FOR DRAINAGE 4. ADD FURNISHED EXCAVATION FOR TBT, T1 (SP) TO MEET STD 630301
 5. PLACE TYPE B CURB UNDER EXIST. OR PROP. T6 END SECT 6. REMOVE 5' FO TAPERED CURB AND PLACE NEW C&G UNDER ALL OF TYPE 6 E.S. 7. REMOVE MEDIAN G.R. AND REPLACE W/IMP. ATTN.
 8. REMOVE TAPERED MEDIAN G.R. REPLACE WITH TANGENT G.R. AND TYPE 1 (SP) TANGENT E.S. 9. ADD CONCRETE TO PIER CAP 10. REMOVE AND RE-ERECT G.R. FOR TYPE B CURB PLACEMENT 11. PLACE PIPE CULVERT AT CENTER PIER FOR DRAINAGE
 12. PLACE EMBANKMENT FOR IMP. ATTN SO THEY WILL BE AT 1:10 SLOPE
 NOTE--EXISTING GR IN BITUMINOUS STABILIZATION FOR 006-0124 EBDL. REMOVE AND INSERT NEW END SECTION THROUGH EXISTING STABLIZATION-COST INCLUDED IN THE PRICE OF TBT, T1 (SP) TANG.
 NOTE- NO CURB TO BE PLACE NEAR STRUCTURES 006-0007,006-0008,006-0009,006-0010,006-0011,006-0012-THESE BRIDGES TO HAVE NEW DECKS WITH APPROACH PAVEMENT WITHIN A YEAR ON A SPERERATE CONTRACT

FILE NAME =	USER NAME = braboypp	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULES			F.A.I RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ca:\projects\ed01208\details.dgn		DRAWN -	REVISED -					80	*	BUREAU	8	5
PLOT SCALE = 58,0000' / IN.		CHECKED -	REVISED -					D3 INTERSTATE SAFETY 2008-2			CONTRACT NO. 66740	
PLOT DATE = Oct 25, 2007 - 01:24:06 PM		DATE -	REVISED -					FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT				
				SCALE: _____ SHEET NO. _____ OF _____ SHEETS STA. _____ TO STA. _____								