

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
318	IRS-1, 2RS-2, 3RS-3;	MARSHALL	28	4
645	(106)RS-5			
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES

1000-2A
80% FED.
20% STATE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY
28100207	STONE RIPRAP, CLASS A4	TON	95
28100228	STONE RIPRAP, CLASS B4 (SPECIAL)	TON	74
28200200	FILTER FABRIC	SY YD	92
40600200	BITUMINOUS MATERIAL (PRIME COAT)	TON	75
40600300	AGGREGATE (PRIME COAT) (MACHINE METHOD)	TON	433
X4067107	POLYMERIZED LEVELING BINDER IL-4.75, N50	TON	4,679
40600895	CONSTRUCTING TEST STRIP	EACH	1
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1,083
40600990	TEMPORARY RAMP	SQ YD	400
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	9,525
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	192
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	97,914
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	45,029
44000400	GUTTER REMOVAL	FOOT	125
44000920	BITUMINOUS CONCRETE SHOULDER REMOVAL	SQ YD	56
44200162	PAVEMENT PATCHING, TYPE IV, 13 INCH	SQ YD	167
44200180	PAVEMENT PATCHING, TYPE II, 15 INCH	SQ YD	600
44200184	PAVEMENT PATCHING, TYPE III, 15 INCH	SQ YD	175
44200186	PAVEMENT PATCHING, TYPE IV, 15 INCH	SQ YD	80
44300900	REFLECTIVE STRIP CRACK CONTROL TREATMENT, SYSTEM A	FOOT	39,595
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	4,064
48203100	HOT-MIX ASPHALT SHOULDERS	TON	3,991
60602600	CONCRETE GUTTER, TYPE A (MODIFIED)	FOOT	125
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	38
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4
67100100	MOBILIZATION	L SUM	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	19,035
70300610	TEMPORARY PAINT PAVEMENT MARKING, LETTERS AND SYMBOLS	SQ FT	65
70300625	TEMPORARY PAINT PAVEMENT MARKING LINE 4"	FOOT	94,436

SUMMARY OF QUANTITIES

1000-2A
80% FED.
20% STATE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY
70300635	TEMPORARY PAINT PAVEMENT MARKING LINE 6"	FOOT	258
70300640	TEMPORARY PAINT PAVEMENT MARKING LINE 8"	FOOT	327
70300645	TEMPORARY PAINT PAVEMENT MARKING LINE 12"	FOOT	818
70300660	TEMPORARY PAINT PAVEMENT MARKING LINE 24"	FOOT	172
* 78005100	EPOXY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	65
* 78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	94,436
* 78005130	EPOXY PAVEMENT MARKING - LINE 6"	FOOT	258
* 78005140	EPOXY PAVEMENT MARKING - LINE 8"	FOOT	327
* 78005150	EPOXY PAVEMENT MARKING - LINE 12"	FOOT	818
* 78005180	EPOXY PAVEMENT MARKING - LINE 24"	FOOT	172
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	530
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	326
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1
X0322729	MATERIAL TRANSFER DEVICE	TON	9,525
X0322752	WORK ZONE PAVEMENT MARKING REMOVAL	FOOT	3,807
X4067108	POLYMERIZED LEVELING BINDER (MACHINE METHOD) IL-4.75, N50 (SPECIAL)	TON	52

10/18/2007
C:\p\projects\127\p\plan\plan.dgn
11:03:18 AM
USER NAME

REVISIED 12/27/07
*SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. HORIZ. DATE

DRAWN BY CHECKED BY