

F.A.P. RATE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
318	1RS-1, 2RS-2, 3RS-3, (106)RS-5	MARSHALL	28	14
645				
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

TEMPORARY RAMP	
LOCATION	SQ YD
IL 29	
STA. 7+98 TO STA. 8+03	13.33
STA. 217+82.33 TO STA. 217+87.33	13.33
STA. 220+67.17 TO STA. 220+72.17	13.33
STA. 359+64.50 TO STA. 359+69.50	13.33
STA. 361+46.50 TO STA. 361+51.50	13.33
STA. 386+29.51 TO STA. 386+34.51	30.28
SIDEROADS	
RT. STA. 19+80 (CHESNUT ST.)	13.08
RT. STA. 30+75 (MAPLE ST.)	16.31
LT. STA. 96+25 (1175 N/1300E)	50.08
RT. STA. 118+60 (1150 N/1275 E)	25.89
RT. STA. 208+00 (1025 N)	29.97
RT. STA. 226+34 (CAMP GROVE RD.)	23.28
RT. STA. 290+32 (1100 E/OLD IL 29)	38.22
RT. STA. 358+50 (THENIUS RD.)	16.11
RT. STA. 375+55 (MAIN ST.)	18.31
RT. STA. 380+88 (NORTH ST.)	17.31
RT. STA. 385+63 (FERRY ST.)	17.58
IL 17W - STA. 24+81 TO STA. 24+86	13.33
IL 17E (BY RAILROAD TRACKS)	23.36
TOTAL	400

STRIP REFLECTIVE CRACK CONTROL TREATMENT, SYSTEM A		
LOCATION	LT/RT	FOOT
IL 29		
STA. 113+00 TO STA. 217+87.33	11' LT	10,487.33
STA. 220+67.17 TO STA. 284+19.50 (BK)	11' LT	6,352.33
STA. 284+23.25 (AH) TO STA. 285+00	11' LT	76.75
STA. 285+00 TO STA. 293+69.70	6' LT	869.70
STA. 351+00 TO STA. 359+69.50	6' LT	869.50
STA. 361+46.50 TO STA. 379+48	11' LT	1,801.50
STA. 385+60 TO STA. 386+34.51	22' LT	74.51
STA. 113+00 TO STA. 217+87.33	11' RT	10,487.33
STA. 220+67.17 TO STA. 284+19.50 (BK)	11' RT	6,352.33
STA. 284+23.25 (AH) TO STA. 285+00	11' RT	76.75
STA. 361+46.50 TO STA. 374+03	11' RT	1,256.50
IL 17W		
STA. 20+30 TO STA. 24+86	9' & VAR, LT	456.00
STA. 20+52 TO STA. 24+86	9' & VAR, RT	434.00
TOTAL		39,595

PAVEMENT PATCHING				
LOCATION	TYPE II (15 INCH)	TYPE III (15 INCH)	TYPE IV (15 INCH)	TYPE IV (13 INCH)
	SQ YD	SQ YD	SQ YD	SQ YD
IL 29				
STA. 40+00 TO STA. 118+60	265.33	76.00	55.00	
STA. 118+60 TO STA. 217+87.33	192.00	67.33	25.00	
STA. 220+67.17 TO STA. 385+00	142.20	31.33		
SIDEROADS				
IL 17W - LT. STA. 532+35 TO STA. 533+60				166.67
TOTAL	600	175	80	167

MOBILIZATION	
LOCATION	L SUM
JOBSITE	1
TOTAL	1

ENGINEER'S FIELD OFFICE, TYPE A	
LOCATION	CAL MO
JOBSITE	4
TOTAL	4

TRAFFIC CONTROL AND PROTECTION		
LOCATION	STD 701306	STD 701336
	L SUM	EACH
JOBSITE	1	1
TOTAL	1	1

FILTER FABRIC	
LOCATION	SQ YDS
IL 29 - S. N. 062-0004	
STA. 219+18	92.00
TOTAL	92

RAILROAD PROTECTIVE LIABILITY INSURANCE	
LOCATION	L SUM
JOBSITE	1
TOTAL	1

CONCRETE GUTTER, TYPE A (MODIFIED)		
LOCATION	LT/RT	FOOT
IL 17W		
STA. 532+35 TO STA. 533+60	LT	125.00
TOTAL		125

STONE RIPRAP, CLASS A4	
LOCATION	TON
IL 29 - S. N. 062-0004	
STA. 219+18	94.95
TOTAL	95

STONE RIPRAP, CLASS B4 (SPECIAL)	
LOCATION	TON
IL 17W	
LT. STA. 533+69	74.08
TOTAL	74

CONSTRUCTING TEST STRIP	
LOCATION	EACH
JOBSITE	1
TOTAL	1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT. HORIZ.
DATE

DRAWN BY
CHECKED BY

PLT DATE = 11/10/2007
FILE NAME = c:\pwworkspace\118198881\dwg
USER NAME = sbr418