

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEET NO.
687	(122V81)-1	McDONOUGH	20
STA. 26+31.00		TO STA. 27+49.00	3
FED. ROAD DIST. NO. 4		ILLINOIS	FED. AID PROJECT

SUMMARY OF QUANTITIES

100% STATE SAFETY - 2A
McDONOUGH

CODE NO.	ITEM	UNIT	RURAL	TOTAL
20200100	EARTH EXCAVATION	CUYD	40	40
20201450	SUB-BASE GRANULAR MATERIAL, TYPE A	CUYD	7.5	7.5
20400800	FURNISHED EXCAVATION	CUYD	34	34
20700420	POUROUS GRANULAR EMBANKMENT, SUBGRADE	CUYD	14.4	14.4
35600716	HOT-MIX ASPHALT BASE COURSE WIDENING, 10"	SQYD	277	277
44001005	HOT-MIX ASPHALT SURFACE REMOVAL	SQYD	22.7	22.7
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	8.6	8.6
42001300	PROTECTIVE COAT	SQYD	23	23
44000920	BITUMINOUS CONCRETE SHOULDER REMOVAL	SQYD	277	277
50300255	CONCRETE SUPERSTRUCTURE	CUYD	2.5	2.5
50400305	DECK BEAMS (17" DEPTH) ↑ PRECAST PRESTRESSED CONCRETE	SQFT	621	621
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	26,970	26,970

REVISIONS	
NAME	DATE
CEJ	06/08/07

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
SCALE: VERT. _____
HORIZ. _____
DATE 06-18-2007
DRAWN BY CEJ
CHECKED BY _____

#DATE# 13-07
 #FILE# \\S:\GEOGRAPHY\STDP\PLUS\SD\4014\Bridges\Report\Contract\Emergency\PCB\BeamReport\68744_SMB05-081711_060807.RR.dgn
 #PAGE# 1
 #REV# 0