

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	72(7,8,9,9-1)LS-1	PEORIA	20	9
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

GRAVEL MULCH		
Location	Depth	M. Ton
Ramp E-1		
Lt. Sta. 20+475 to 20+570	150 mm	35

ENGINEER'S FIELD OFFICE, TYPE A	
Jobsite	10 CAL MO

MOBILIZATION	
Jobsite	1 Lump Sum

TRAFFIC CONTROL AND PROTECTION	
Jobsite	1 Lump Sum

SUPPLEMENTAL WATERING				
Location	No. of Plants	Rate liters/plant	No. of Waterings	Units
Trees	134	38	5	25.46
Shrubs	4,605	11	5	253.275
Vines	422	11	5	23.21
Perennials	1,447 SQM	15 L/SQM	14	303.87
Total				606

CARE OF PLANT MATERIALS			
Location	No. of Plants	No. of Care Cycles	Each
Tree Care	134	2	268
Shrub Care	4,605	2	9,210
Vine Care	422	2	844
Perennial Plant Care	1,447	8	11,575 SQM

Note: Perennial Plant Care will be measured by SQM.

WEED CONTROL, PRE-EMERGENT GRANULAR HERBICIDE				
Location	Appl. Rate (kg/SQM)	Area (SQ M)	No. of Appl.	Kilograms
Perennial Plant Beds	0.01	1,447	3	44

FERTILIZER NUTRIENTS				
Location	Appl. Rate (kg/SQM)	Area (SQ M)	No. of Appl.	Kilograms
Perennial Plant Beds				
Nitrogen Fert. Nutr.	0.01	1,447	1	14
Phosphorus Fert. Nutr.	0.006	1,447	1	9
Potassium Fert. Nutr.	0.004	1,447	1	6

	Totals By Layout Sheet		Totals by Plant Name
	Sheet 3	Sheet 6	
Forbs			
Aster Laevis -Smooth Aster	0	700	700
Aster Novae angliae-New England Aster	670	600	1,270
Baptisia Leucantha - White Indigo	0	350	350
Echinacea Purpurea - Purple Coneflower	770	1,000	1,770
Helianthus Strumosus- Woodland Sunflower	700	900	1,600
Monarda Fistulosa- Wild Bergamont	750	350	1,100
Physostegia Virginiana-Obedient Plant	0	330	330
Rudbeckia Goldstrum- Goldstrum Brown Eyed Susan	0	600	600
Silphium Integrefolium- Rosin Weed	770	500	1,270
Silphium Laciniatum-Compass Plant	700	0	700
Silphium Terebinthinaceum- Prairie Dock	0	1,500	1,500
Solidago Speciosa - Showy Goldenrod	0	380	380
Vernonia Fasticulata- Ironweed	0	485	485
Veronicastrum Virginicum-Culvers Root	0	480	480
Grasses			
Andorpogon Scoparius- Little Bluestem	540	1,030	1,570
Sorghastrum Nutans-Indiangrass	260	0	260
Sporobulus Heterolepsis-Dropseed	1,210	0	1,210
Sub Totals	6,370	9,205	
Grand Total	15,575 = 155.75 Units		

NOTE: PERENNIAL PLANTS TO BE PLANTED IN LARGE GROUPINGS. LAYOUT TO BE DETERMINED BY LANDSCAPE ARCHITECT PRIOR TO PLANTING.

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. ROUTE 74 (I-74)

SCHEDULE OF QUANTITIES

DATE: DRAWN BY: K.K.K.
CHECKED BY: R.J.D.