CONTRACT NO. 70128

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
840	(121,122)RS-3	VERMILION	89	15
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

GUARDRAIL SCHEDULE

LOCATION	63200310 - GUARDRAIL REMOVAL	63000000 - SPBGR, TYPE A	78200450 - MONO-DIRECT. G'RAIL REFLECTORS	63100167 - TBT, TY. 1, SPL. (TANG.)	63100045 - TBT, TY. 2	63000025 - SPBGR ATTACH TO STRUCT.	63000005 - SPBGR, TYPE B	78201000 - TERM. MKR. DIRECT. APPLIED	FILL - (FOR INFO ONLY)	63301210 - REMOVE & RE-ERECT SPBGR, TY. A
	FOOT	FOOT	EACH	EACH	EACH	FOOT	FOOT	EACH	CU YD	FOOT
LT STA. 850+10 - 855+00										490.6
RT STA. 850+12 - 851+00										88.1
RT STA. 851+37 - 855+00										377.5
LT STA. 861+95 - 865+88										492.6
RT STA. 861+98 - 865+88										490.3
RT STA. 944+38.50 - 946+38.50	200.0									
LT STA. 944+46.00 - 945+75.00	162.5									
RT STA. 942+28.50 - 942+78.50				1.0				1.0	11.0	
RT STA. 942+78.50 - 946+78.50		400.0	9.0							
RT STA. 946+78.50 - 947+28.50				1.0				1.0	11.0	
LT STA. 943+16.00 - 943+66.00				1.0				1.0	11.0	
LT STA. 943+66.00 - 945+75.00		212.5	5.0							
LT STA. 945+75.00 - 945+87.50					1.0					
RT STA. 1191+87.00 - 1195+87.50	400.5									
LT STA. 1192+62.50 - 1196+62.50	400.0									
RT STA. 1191+15.625 - 1191+65.625				1.0				1.0	11.0	
RT STA. 1191+65.625 - 1193+90.625		225.0	6.0							
RT STA. 1193+90.625 - 1194+15.625							25.0			
RT STA. 1194+15.625 - 1194+40.625						25.0				
RT STA. 1194+40.625 - 1194+65.625							25.0			
RT STA. 1194+65.625 - 1196+15.625		150.0	4.0							
RT STA. 1196+15.625 - 1196+65.625				1.0				1.0	11.0	
LT STA. 1191+84.375 - 1192+34.375				1.0				1.0	11.0	
LT STA. 1192+34.375 - 1193+84.375		150.0	4.0							
LT STA. 1193+84.375 - 1194+09.375							25.0			
LT STA. 1194+09.375 - 1194+34.375						25.0				
LT STA. 1194+34.375 - 1194+59.375							25.0			
LT STA. 1194+59.375 - 1196+84.75		225.0	6.0							
LT STA. 1196+84.75 - 1197+34.75				1.0				1.0	11.0	
TOTAL	**1163.0**	**1362.5**	**34.0**	**7.0**	**1.0**	**50.0**	**100.0**	**7.0**	**77.0**	**1939.1**
USE	**1163.0**	**1363.0**	**34.0**	**7.0**	**1.0**	**50.0**	**100.0**	**7.0**		**1940.0**

NOTE: FURNISHED EXCAVATION AND SEEDING, CLASS 7 ARE TO BE USED AT THE TBT, TYPE I, SPECIAL (TANGENT) LOCATIONS ONLY.

66700110 - PERMANENT SURVEY MARKERS TO BE ADJUSTED

LOCATION	TYPE	EACH
4.8' LT STA. 866+82.7	VAULT	1.0
5' LT STA. 893+22.7	VAULT	1.0
5' LT STA. 919+51.5	VAULT	1.0
5' LT STA. 945+82.9	VAULT	1.0
5' LT STA. 972+12.9	VAULT	1.0
4.5' LT STA. 998+07.8	VAULT	1.0
5.1' LT STA. 1024+47.8	VAULT	1.0
8.2' LT STA. 1049+34.5	VAULT	1.0
11.67' LT STA. 1075+74.5	VAULT	1.0
11.67' RT STA. 1102+14.5	VAULT	1.0
4.75' RT STA. 1128+54.5	VAULT	1.0
8' RT STA. 1181+34.5	VAULT	1.0
5' RT STA. 1207+69	VAULT	1.0
5.2' RT STA. 1234+04.1	VAULT	1.0
TOTAL		**14.0**

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT. HORIZ.

DATE

DRAWN BY

CHECKED BY

PLOT DATE = 11/19/2007
FILE NAME = c:\projects\d505888 k8\rev_plans\ts.dgn
PLOT SCALE = 42.0000 ' / IN.
USER NAME = cotlwerm