

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
840	(121,122)RS-3	VERMILION	89	16
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

70300100 - SHORT-TERM PAVEMENT MARKING	
LOCATION	FOOT
SKIP-DASH (YELLOW)	
STA. 765+00 - 837+24 (BK)	2167.2
STA. EQ. 837+24 (BK) = 837+20 (AH)	
(AH) STA. 837+20 - 870+00 (BK)	984.0
STA. EQ. 870+00 (BK) = 870+71 (AH)	
(AH) STA. 870+71 - 1280+10	12281.7
TOTAL	15432.9
USE	15433.0

70301000 - WORK ZONE PAVEMENT MARKING REMOVAL	
LOCATION	SQ FT
SKIP-DASH (YELLOW)	
STA. 765+00 - 837+24 (BK)	240.6
STA. EQ. 837+24 (BK) = 837+20 (AH)	
(AH) STA. 837+20 - 870+00 (BK)	109.2
STA. EQ. 870+00 (BK) = 870+71 (AH)	
(AH) STA. 870+71 - 1280+10	1363.3
TOTAL	1713.1
USE	1714.0

78001110 - PAINT PAVEMENT MARKING LINE, 4"			
LOCATION	FOOT	LOCATION	FOOT
SKIP-DASH (YELLOW)		EDGE LINES - SOLID (WHITE)	
STA. 765+00 - 837+24 (BK)	7224.0	IL 49	
STA. EQ. 837+24 (BK) = 837+20 (AH)		LT STA. 1280+10 - 765+00	51510.0
(AH) STA. 837+20 - 870+00 (BK)	3280.0	RT STA. 1280+10 - 765+00	51510.0
STA. EQ. 870+00 (BK) = 870+71 (AH)			
(AH) STA. 870+71 - 1280+10	40939.0	SUB-TOTAL	103020.0
SUB-TOTAL	51443.0		
SPACING = 62948.8 / 40 x 10			
SUB-TOTAL	12860.8		
NO PASSING ZONE - DOUBLE (YELLOW)		NO PASSING ZONE - DOUBLE (YELLOW)	
NORTHBOUND		SOUTHBOUND	
STA. 801+83 - 810+80	897.0	STA. 809+22 - 817+67	845.0
STA. 843+01 - 857+27	1426.0	STA. 852+51 - 864+66	1215.0
STA. 881+55 - 886+83	528.0	STA. 892+11 - 897+92	581.0
STA. 914+29 - 924+85	1056.0	STA. 932+24 - 937+52	528.0
STA. 940+69 - 946+50	581.0	STA. 952+31 - 957+59	528.0
STA. 1088+53 - 1094+87	634.0	STA. 1099+09 - 1105+43	634.0
STA. 1211+55 - 1218+42	687.0	STA. 1222+64 - 1229+51	687.0
STA. 1235+84 - 1243+76	792.0	STA. 1246+93 - 1254+85	792.0
STA. 1252+21 - 1259+07	686.0	STA. 1263+30 - 1270+16	686.0
SUB-TOTAL	7287.0	SUB-TOTAL	6496.0
TOTAL		TOTAL	129663.8
USE		USE	129664.0

RRPM SCHEDULE		
LOCATION	78300200 - RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	78100100 - RAISED REFLECTIVE PAVEMENT MARKERS
	EACH	EACH
STA. 765+00 - 837+24 (IL49)	91.0	91.0
STA. 837+20 - 870+00 (IL49)	41.0	41.0
STA. 870+71 - 1280+10(IL49)	512.0	512.0
STA. EQ. 837+24 (BK) = 837+20 (AH)		
STA. EQ. 870+00 (BK) = 870+71 (AH)		
TOTAL	644.0	644.0

X0301232 - SURVEY MARKER VAULT		
LOCATION	EX. TYPE	EACH
70' RT. STA. 1075+74.5	5/8" PIN	1.0
TOTAL		1.0

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT. _____
HORIZ. _____

DATE _____

DRAWN BY _____
CHECKED BY _____