

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
808	*	DOUGLAS	42	14
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SCHEDULE OF QUANTITIES

SHEET 2 OF 5

(12,Y-15D)ORS-2

40600990 TEMPORARY RAMP

STATION	TO	STATION	LENGTH (FT)	WIDTH (FT)	AREA (SQ YD)
3+33.00		3+38.00	5.00	38.00	21.11
25+90.00		25+95.00	5.00	26.00	14.44
26+03.75		26+08.75	5.00	26.00	14.44
RT. 29+18.00			5.00	22.00	12.22 (MAIN ST.)
LT. 29+18.00			5.00	24.00	13.33 (MAIN ST.)
LT. 39+92.00			5.00	22.00	12.22 (MILL ST.)
LT. 70+18.00			5.00	20.00	11.11 (T.R. 146)
RT. 85+73.00			5.00	30.00	16.67 (LAKEWOOD DR.)
RT. 106+57.00			5.00	24.00	13.33 (1150N)
145+19.74	145+24.74		5.00	26.00	14.44
149+48.36	149+53.36		5.00	26.00	14.44
LT. 173+20.00			5.00	22.00	12.22 (T.R. 25 / 1275N)
RT. 173+30.00			5.00	24.00	13.33 (C.H. 28 / 1275N)
RT. 228+63.00			5.00	26.00	14.44 (ARTHUR AVE.)
RT. 232+24.00			5.00	26.00	14.44 (HAYES AVE.)
RT. 235+86.00			5.00	26.00	14.44 (GARFIELD AVE.)
RT. 239+44.00			5.00	26.00	14.44 (CLEVELAND ST.)
RT. 243+00.00			5.00	26.00	14.44 (MCKINLEY AVE.)
RT. 246+65.00			5.00	26.00	14.44 (LINCOLN AVE.)
RT. 250+24.00			5.00	26.00	14.44 (JACKSON AVE.)
LT. 254+58.00			5.00	42.00	23.33 (RAILROAD ST.)
252+82.33	252+87.33		5.00	34.00	18.89
253+18.00	253+23.00		5.00	34.00	18.89
LT. 255+64.00			5.00	42.00	23.33 (MONROE AVE.)
RT. 255+64.00			5.00	30.00	16.67 (MONROE AVE.)
RT. 259+23.00			5.00	26.00	14.44 (ADAMS ST.)
LT. 259+25.00			5.00	32.00	17.78 (ADAMS ST.)
RT. 262+82.00			5.00	26.00	14.44 (JEFFERSON ST.)
LT. 262+84.00			5.00	26.00	14.44 (JEFFERSON ST.)
RT. 266+45.00			5.00	34.00	18.89 (HARRISON AVE.)
LT. 266+45.00			5.00	34.00	18.89 (HARRISON AVE.)
272+49.90	272+54.90		5.00	28.70	15.94
273+91.48	273+96.48		5.00	28.70	15.94
LT. 287+37.00			5.00	23.00	12.78 (MCCOY AVE.)
297+45.00	297+50.00		5.00	26.00	14.44
TOTAL =					543.47 SQ YD
USE =					544.00 SQ YD

44000500 COMBINATION CURB & GUTTER REMOVAL

STATION	TO	STATION	LENGTH (FT)
RT. 260+76.00		262+18.00	142.0
LT. 265+12.00		265+20.00	8.0
TOTAL =			150.0 FT

60605000 COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24

STATION	TO	STATION	LENGTH (FT)
RT. 260+76.00		262+18.00	142.0
LT. 265+12.00		265+20.00	8.0
TOTAL =			150.0 FT

60260100 INLETS TO BE ADJUSTED

STATION	OFFSET	QUANTITY (EACH)
262+03.00	15.0' RT.	1.0
TOTAL =		1.0 EACH

60255500 MANHOLES TO BE ADJUSTED

STATION	OFFSET	QUANTITY (EACH)
255+45.00	22.0' LT.	1.0
255+85.00	24.0' LT.	1.0
255+98.00	2.0' LT.	1.0
259+12.00	19.0' RT.	1.0
259+25.00	20.0' LT.	1.0
263+00.00	19.0' RT.	1.0
266+14.00	19.0' RT.	1.0
TOTAL =		7.0 EACH

66700110 PERMANENT SURVEY MARKERS TO BE ADJUSTED

STATION	OFFSET	QUANTITY (EACH)
106+63.85	CENTERLINE	1.0
186+42.52	9.00' RT.	1.0
226+35.38	1.90' LT.	1.0
239+73.95	2.80' LT.	1.0
266+44.96	CENTERLINE	1.0
292+99.65	2.40' RT.	1.0
TOTAL =		6.0 EACH

70300100 SHORT TERM PAVEMENT MARKING

STATION	TO	STATION	APPLY AFTER:	QUANTITY (FT)	COLOR
3+33.00		25+95.00	MILLING	232.0	YELLOW
26+03.75		145+24.74	MILLING	1,196.0	YELLOW
149+48.36		252+87.33	MILLING	1,040.0	YELLOW
253+18.00		272+54.90	MILLING	200.0	YELLOW
273+91.48		297+50.00	MILLING	240.0	YELLOW
26+51.25		144+84.74	LEVEL BINDER	1,188.0	YELLOW
149+88.36		224+10.00	LEVEL BINDER	748.0	YELLOW
278+46.00		297+40.00	LEVEL BINDER	196.0	YELLOW
3+33.00		25+95.00	HMA SURFACE	232.0	YELLOW
26+03.75		145+24.74	HMA SURFACE	1,196.0	YELLOW
149+48.36		252+87.33	HMA SURFACE	1,040.0	YELLOW
253+18.00		272+54.90	HMA SURFACE	200.0	YELLOW
273+91.48		297+50.00	HMA SURFACE	240.0	YELLOW
TOTAL =				7,948.0 FT	

70301000 WORK ZONE PAVEMENT MARKING REMOVAL

STATION	TO	STATION	QUANTITY (SQ FT)
3+33.00		25+95.00	77.33
26+03.75		145+24.74	398.67
149+48.36		252+87.33	346.67
253+18.00		272+54.90	66.66
273+91.48		297+50.00	80.00
TOTAL =			969.33 (SQ FT)
USE =			970.00 (SQ FT)

70300210 TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS

STATION	LOCATION	QUANTITY (FT)	COLOR
RT. 22+55.00	RXR CROSSING	61.2	WHITE
LT. 28+35.00	RXR CROSSING	61.2	WHITE
RT. 251+35.00	RXR CROSSING	61.2	WHITE
LT. 254+95.00	RXR CROSSING	61.2	WHITE
RT. 265+43.00	TURN ARROW	15.6	WHITE
RT. 265+77.00	TURN ARROW	15.6	WHITE
LT. 267+14.00	TURN ARROW	15.6	WHITE
LT. 267+74.00	TURN ARROW	15.6	WHITE
RT. 8+96.00	TURN ARROW	15.6	WHITE (HARRISON AVE)
RT. 9+35.00	TURN ARROW	15.6	WHITE (HARRISON AVE)
LT. 10+64.00	TURN ARROW	15.6	WHITE (HARRISON AVE)
LT. 11+06.00	TURN ARROW	15.6	WHITE (HARRISON AVE)
TOTAL =		369.6 FT	
USE =		370.0 FT	

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
 F.A.P. 808 (IL ROUTE 130)
 SECTION (12,Y-15D)ORS-2
 DOUGLAS COUNTY
 Sheet 2 of 5

SCALE: NOT TO SCALE DRAWN BY: B.B.P.
 DATE: 10/04/07 CHECKED BY: G.A.E.