

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
808	*	DOUGLAS	42	20
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

INCIDENTAL HOT-MIX ASPHALT SURFACE SCHEDULE

(SHEET 3 OF 4)

• (12,Y-15D)ORS-2

STATION	DESCRIPTION	INCIDENTAL AREA (SQ FT)	AVERAGE THICKNESS (INCH)	40800050 INCIDENTAL HOT-MIX ASPHALT SURFACING (TON)	40800010 BIT MAT'L PRIME COAT (GALLONS)	40800030 AGGREGATE PRIME COAT (TON)	44000155 HOT-MIX ASPHALT SURFACE REMOVAL 1 1/2" (SQ YD)	44000196 HOT-MIX ASPHALT SURFACE REMOVAL, SPECIAL (SQ YD)	40600982 HOT-MIX ASPHALT SURFACE REMOVAL, BUTT JOINT (SQ YD)	35101400 AGGREGATE BASE COURSE, TYPE B (TON)	40200800 AGGREGATE SURFACE COURSE, TYPE B (TON)	44000200 DRIVEWAY PAVEMENT REMOVAL (SQ YD)	REMARKS
RT. 224+93.00	P. E.												NO WORK
RT. 225+62.00	MBTO												NO WORK
LT. 226+25.00	NEW SIDEROAD												NO WORK
RT. 226+26.00	P. E.												NO WORK
RT. 227+33.00	P. E.												NO WORK
RT. 228+63.00	ARTHUR AVE.	1,280.00	1.50	11.95	14.22	0.28	142.22						RESURFACE TO BACK OF RADIUS
RT. 229+93.00	P. E.												NO WORK
RT. 230+93.00	P. E.												NO WORK
RT. 232+24.00	HAYES AVE.	1,020.00	1.50	9.52	11.33	0.23	113.33						RESURFACE TO BACK OF RADIUS
RT. 233+11.00	P. E.												NO WORK
RT. 234+08.00	P. E.												NO WORK
LT. 234+46.00	C. E.												NO WORK
RT. 234+97.00	P. E.												NO WORK
RT. 235+86.00	GARFIELD AVE.	1,020.00	1.50	9.52	11.33	0.23	113.33						RESURFACE TO BACK OF RADIUS
LT. 235+96.00	C. E.												NO WORK
RT. 236+69.00	P. E.												NO WORK
LT. 236+72.00	C. E.												NO WORK
RT. 239+44.00	CLEVELAND ST.	1,280.00	1.50	11.95	14.22	0.28	142.22						RESURFACE TO BACK OF RADIUS
LT. 239+44.00	C. E.												NO WORK
LT. 241+16.00	C. E.												NO WORK
RT. 241+18.00	P. E.												NO WORK
RT. 241+73.00	P. E.												NO WORK
LT. 242+50.00	C. E.												NO WORK
RT. 243+00.00	MCKINLEY AVE.	950.00	1.50	8.87	10.56	0.21	105.56						RESURFACE TO BACK OF RADIUS
RT. 243+65.00	P. E.												NO WORK
RT. 244+25.00	C. E.												NO WORK
RT. 245+35.00	C. E.												NO WORK
RT. 246+65.00	LINCOLN AVE.	1,020.00	1.50	9.52	11.33	0.23	113.33						RESURFACE TO BACK OF RADIUS
RT. 248+53.00	P. E.												NO WORK
LT. 248+77.00	C. E.												NO WORK
RT. 250+24.00	JACKSON AVE.	1,280.00	1.50	11.95	14.22	0.28	142.22						RESURFACE TO BACK OF RADIUS
LT. 250+24.00	C. E.												NO WORK
RT. 252+00.00	C. E.												NO WORK
LT. 252+13.00	C. E.												NO WORK
LT. 254+58.00	RAILROAD ST.	5,940.00	1.50	55.44	66.00	1.32	660.00						RESURFACE TO BACK OF RADIUS
LT. 254+94.00	C. E.												NO WORK
LT. 255+19.00	C. E.												NO WORK
LT. 255+64.00	MONROE AVE.	1,710.00	1.50	15.96	19.00	0.38	190.00						RESURFACE TO BACK OF RADIUS
RT. 255+64.00	MONROE AVE.	1,020.00	1.50	9.52	11.33	0.23	113.33						RESURFACE TO BACK OF RADIUS
LT. 256+51.00	C. E.												NO WORK
RT. 256+95.00	C. E.												NO WORK
LT. 257+39.00	C. E.												NO WORK
LT. 257+69.00	C. E.												NO WORK
LT. 258+12.00	C. E.												NO WORK
RT. 258+29.00	P. E.												NO WORK
LT. 258+65.00	C. E.												NO WORK
RT. 259+23.00	ADAMS ST.	1,280.00	1.50	11.95	14.22	0.28	142.22						RESURFACE TO BACK OF RADIUS
LT. 259+25.00	ADAMS ST.	1,470.00	1.50	13.72	16.33	0.33	163.33						RESURFACE TO BACK OF RADIUS
LT. 260+00.00	C. E.												NO WORK

PLOT DATE = 10/18/2007
 FILE NAME = c:\projects\0506902\08\70275\text.dgn
 USER NAME = collierdw

INCIDENTAL HOT-MIX ASPHALT SURFACE SCHEDULE

F.A.P. 808 (IL ROUTE 130)
 SECTION (12,Y-15D)ORS-2
 DOUGLAS COUNTY
 Page 3 of 4

SCALE: NOT TO SCALE
DATE: 10/04/07

DRAWN BY: B.B.P.
CHECKED BY: G.A.E.