

## GENERAL NOTES

G.N.-100  
ENGLISH UNITS OF MEASUREMENT SHALL GOVERN OVER AND SUPERSEDE ANY METRIC UNITS SHOWN IN THIS CONTRACT. WHERE INCLUDED, METRIC UNITS ARE FOR INFORMATION ONLY.

G.N.-250C  
TEMPORARY EROSION CONTROL SEEDING AND MULCH, METHOD 2 IS INCLUDED IN THIS CONTRACT TO SEED NEW EARTH SHOULDERS DURING TIME PERIODS WHEN PERMANENT SEEDING IS NOT ALLOWED. SOME OR ALL OF THE TEMPORARY EROSION CONTROL SEEDING AND MULCH WILL BE DELETED IF IT IS POSSIBLE TO PLACE PERMANENT SEEDING ON EARTH SHOULDERS AT THE TIME OF THEIR COMPLETION.

G.N. -406H

### MIXTURE REQUIREMENTS

The following mixture requirements are applicable for this project:

| Location(s):                                | SN 010-0062 & SN 057-0091 | FAP 709 & FAP 315 (US 136) |
|---|---------------------------|----------------------------|
| Mixture Use(s):                             | SURFACE                   | HMA BINDER                 |
| AC/PG:                                      | PG 64-22                  | PG 64-22                   |
| RAP %: (Max)**                              | 15%                       | 25%                        |
| Design Air Voids:                           | 4.0% @ Ndes = 50          | 4.0% @ Ndes = 50           |
| Mixture Composition:<br>(Gradation Mixture) | IL 9.5                    | IL 19.0                    |
| Friction Aggregate:                         | MIX C                     | N.A.                       |

COMMITMENTS:  
THERE ARE NO COMMITMENTS FOR THIS PROJECT.

|   |                             |            |           |   |                      |                          |         |                    |                 |              |                     |                           |
|---|-----------------------------|------------|-----------|---|----------------------|--------------------------|---------|--------------------|-----------------|--------------|---------------------|---------------------------|
| FILE NAME =<br>c:\projects\1504807\158\70669\text.dgn | USER NAME = collierbw       | DESIGNED - | REVISED - | <b>STATE OF ILLINOIS<br/>DEPARTMENT OF TRANSPORTATION</b> | <b>GENERAL NOTES</b> | F.A.<br>RTE.             | SECTION | COUNTY             | TOTAL<br>SHEETS | SHEET<br>NO. |                     |                           |
|   |                             | DRAWN -    | REVISED - |   |                      |                          |         |                    | 26              | 4            |                     |                           |
|   | PLOT SCALE = 40,0000' / IN. | CHECKED -  | REVISED - |   |                      | • 05 BEAM REPLACE 2008-1 |         | CONTRACT NO. 70669 |                 |              |                     |                           |
|   | PLOT DATE = 10/25/2007      | DATE -     | REVISED - |   | SCALE:               | SHEET NO.                | OF      | SHEETS             | STA.            | TO STA.      | FED. ROAD DIST. NO. | ILLINOIS FED. AID PROJECT |