SUMMARY OF QUANTITIES

LOCATION OF WORK:

CONSTRUCTION TYPE CODE:

CODE NO	ITEM	UNIT	TOTAL QUANTITY	CHAMPAIGN COUNTY RURAL ROADWAY / STRUCTURE IMPROVEMENTS FAP 709 (US 136) STA. 1892+87.30 STA. 1893+44.00 100% STATE SFTY-2A	MCLEAN COUNTY RURAL ROADWAY / STRUCTURE IMPROVEMENTS FAP 315 (US 136) STA. 126+32.30 STA. 127+59.22 100% STATE SFTY-2A
20200100	EARTH EXCAVATION	CU YD	120.00	80.00	40.00
25000200	SEEDING, CLASS 2	ACRE	0.25	0.13	0.12
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	14.00	7.00	7.00
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	14.00	7.00	7.00
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	14.00	7.00	7.00
25100115	MULCH, METHOD 2	ACRE	0.25	0.13	0.12
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	15.00	8.00	7.00
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	21.00	11.00	10.00
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	25.00	13.00	12.00
44000156	HOT-MIX ASPHALT SURFACE REMOVAL, 1 3/4"	SQ YD	39.00	20.80	18.20
44004250	PAVED SHOULDER REMOVAL	SQ YD	241.00	0.00	241.00
50102400	CONCRETE REMOVAL	CU YD	12.80	0.00	12.80
50300255	CONCRETE SUPERSTRUCTURE	CU YD	12.80	0.00	12.80
50300300	PROTECTIVE COAT	SQ YD	70.00	0.00	70.00
50400405	PRECAST PRESTRESSED CONCRETE DECK BEAMS (21" DEPTH)	SQ FT	637.00	0.00	637.00
50400505	PRECAST PRESTRESSED CONCRETE DECK BEAMS (27" DEPTH)	SQ FT	833.00	833.00	0.00
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	360.00	0.00	360.00
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	2040.00	0.00	2040.00
58100200	WATERPROOFING MEMBRANE SYSTEM	SQ YD	185.00	115.00	70.00
58300100	PORTLAND CEMENT MORTAR FAIRING COURSE	FOOT	770.00	452.00	318.00
67100100	MOBILIZATION	L SUM	1.00	0.50	0.50
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	2.00	1.00	1.00
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1.00	0.50	0.50
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	2.00	1.00	1.00
70106700	TEMPORARY RUMBLE STRIP	EACH	12.00	6.00	6.00
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1167.00	641.00	526.00
70400100	TEMPORARY CONCRETE BARRIER	FOOT	625.00	287.50	337.50
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	375.00	175.00	200.00
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	3018.00	1440.00	1578.00
78300100	PAVEMENT MARKING REMOVAL	SQ FT	571.00	180.00	391.00
X0320047	REMOVAL OF EXISTING PRECAST PRESTRESSED CONCRETE DECK BEAMS	SQ FT	1493.00	847.00	646.00
X7200201	WIDTH RESTRICTION SIGNING	L SUM	1.00	0.50	0.50
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	21.00	16.00	5.00
Z0002900	BASE COURSE (OPTION)	SQ YD	256.00	256.00	0.00
Z0003100	BASE COURSE (OPTION) NO. 2	SQ YD	241.00	0.00	241.00
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	4.00	2.00	2.00
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	4.00	2.00	2.00

* SPECIALTY ITEM

FILE NAME = c:\projects\d504007 lw81\70669text.dgn	USER NAME = colliersbw	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 40.0000 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 10/25/2007	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

GENERAL NOTES

SCALE: | SHEET NO. OF SHEETS | STA. | TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	*		26	5
	* D5 BEAM REPLACE 2008-1	CONTRACT NO. 70669		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		