CONTRACT NO. 72659

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	SANGAMON	248	6
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* FAI55(I-55), FAI72(I-72), FAP666(I-55 BUS)
** D6 INTERSTATE RS,BR,M CAB 2008

SUMMARY OF QUANTITIES

				ACIM	ACHSIP	ACIM			
				HMA ROADWAY 90% FEDERAL 10% STATE URBAN	CABLE MEDIAN BARRIER 90% FEDERAL 10% STATE URBAN	STRUCTURE 084-0028 NB BL-55 90% FEDERAL 10% STATE URBAN	STRUCTURE 084-0076 WB I-72 90% FEDERAL 10% STATE URBAN	STRUCTURE 084-0077 EB I-72 90% FEDERAL 10% STATE URBAN	STRUCTURE 084-0092 W LAKE SHORE DR 90% FEDERAL 10% STATE URBAN
				CONSTRUCTION TYPE CODE					
CODE NO.	PAY ITEM	UNITS	TOTAL QUANTITY	1000-2A	SFTY-4A	SFTY-2A	SFTY-2A	SFTY-2A	SFTY-2A
55034500	STORM SEWERS, TYPE 1, REINFORCED CONCRETE ELLIPTICAL PIPE, SPAN 38, RISE 24	FOOT	1,192	1,192					
58100200	WATERPROOFING MEMBRANE SYSTEM	SQ YD	1,527					1,027	500
60219000	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	2	2					
60225100	RESTRICTED DEPTH MANHOLES, 4'-DIAMETER, TYPE 8 GRATE	EACH	5	5					
60260100	INLETS TO BE ADJUSTED	EACH	1	1					
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	2	2					
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	4	4					
60500060	REMOVING INLETS	EACH	1	1					
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	5,262.5	5,262.5					
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	9	9					
* 63100070	TRAFFIC BARRIER TERMINAL, TYPE 5	EACH	1	1					
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4					
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	29	29					
63200310	GUARDRAIL REMOVAL	FOOT	4,547.5	4,547.5					
63300575	REMOVE AND RE-ERECT RAIL ELEMENT OF EXISTING GUARD RAIL	FOOT	18,650	18,650					
63400105	GUARD POSTS	EACH	8	8					
63500105	DELINEATORS	EACH	774	774					
64200105	SHOULDER RUMBLE STRIP	FOOT	190,468	190,468					
66400105	CHAIN LINK FENCE, 4'	FOOT	60,118	60,118					
66410300	CHAIN LINK FENCE REMOVAL	FOOT	25,758	25,758					
66502300	WOVEN WIRE FENCE REMOVAL	FOOT	34,360	34,360					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	10	10					
67100100	MOBILIZATION	L SUM	1	1					
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	32	32					
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1	1					
70100815	TRAFFIC CONTROL AND PROTECTION, STANDARD 701446	L SUM	1	1					
70101205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321 (SPECIAL)	EACH	1						1
70101605	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402 (SPECIAL)	EACH	2				1	1	
70103710	TRAFFIC CONTROL FOR RAMPS	L SUM	1	1					
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	15	6	5		2	2	
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1						1
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	67	67					

1 Rev. 1-8-08

* SPECIALTY ITEMS

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

FAI55(I-55), FAI72(I-72), FAP666(I-55 BUS)
SECTION D6 INTERSTATE RS,BR,M CAB 2008
SANGAMON COUNTY

SCALE: DRAWN BY
DATE CHECKED BY

PLOT DATE = Oct-22-2007 08:18:49AM
FILE NAME = c:\Projects\d652582\sht soq.dgn
PLOT SCALE = 100.000 ' / IN.
USER NAME = leagdirr