

F.A.I. RYE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	SANGAMON	248	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
* FA155(I-55), FA172(I-72), FAP666(I-55 BUS)				
** D6 INTERSTATE RS,BR,M CAB 2008				

SUMMARY OF QUANTITIES

CODE NO.	PAY ITEM	UNITS	TOTAL QUANTITY	CONSTRUCTION TYPE CODE					
				I000-2A	SFTY-4A	SFTY-2A	SFTY-2A	SFTY-2A	SFTY-2A
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	56	56					
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	24	24					
20100500	TREE REMOVAL, ACRES	ACRE	19.5	19.5					
20200100	EARTH EXCAVATION	CU YD	175	175					
20200600	EXCAVATING AND GRADING EXISTING SHOULDER	UNIT	228		228				
20400800	FURNISHED EXCAVATION	CU YD	5740	3625	2,115				
21400100	GRADING AND SHAPING DITCHES	FOOT	5,092	5,092					
25000200	SEEDING, CLASS 2	ACRE	30	23	7				
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	2,670	2,068	602				
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	2,670	2,068	602				
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	2,670	2,068	602				
25000700	AGRICULTURAL GROUND LIMESTONE	TON	59.4	46.0	13.4				
25100115	MULCH, METHOD 2	ACRE	23	23					
25100630	EROSION CONTROL BLANKET	SO YD	32,606	100	32,506				
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	5,930	4,592	1,338				
28000300	TEMPORARY DITCH CHECKS	EACH	22	22					
28000500	INLET AND PIPE PROTECTION	EACH	30	30					
28100107	STONE RIPRAP, CLASS A4	SQ YD	1,397	1,397					
28100109	STONE RIPRAP, CLASS A5	SQ YD	33	33					
28200200	FILTER FABRIC	SQ YD	1,430	1,430					
35100100	AGGREGATE BASE COURSE, TYPE A	TON	52	52					
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SO YD	1,143	1,143					
35600724	HOT-MIX ASPHALT BASE COURSE WIDENING, 12"	SO YD	3410			1346	2062		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	193	193					
40600300	AGGREGATE (PRIME COAT)	TON	1,013	1,013					
40600895	CONSTRUCTING TEST STRIP	EACH	3	3					
40600990	TEMPORARY RAMP	SO YD	2,054	2,054					
40603245	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, 1L-19.0, N105	TON	41,051	41,051					
40603305	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N30	TON	19,197	19,197					
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	42						42
40603575	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N105	TON	28,543	28,457				86	
44000152	HOT-MIX ASPHALT SURFACE REMOVAL, 3/4"	SO YD	17,531	17,531					
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SO YD	25,683	25,683					

PLOT DATE = 04-25-2007 08:06:37AM
 FILE NAME = c:\p\projects\628282\shasap.dgn
 PLOT SCALE = 1/8"=1'-0"
 USER NAME = haughlin

Rev.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SUMMARY OF QUANTITIES
 FA155(I-55), FA172(I-72), FAP666(I-55 BUS)
 SECTION D6 INTERSTATE RS,BR,M CAB 2008
 SANGAMON COUNTY
 SCALE: DATE DRAWN BY CHECKED BY