CONTRACT NO. 72659

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	SANGAMON	248	31
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* FAI55(I-55), FAI72(I-72), FAP666(I-55 BUS)
** D6 INTERSTATE RS,BR,M CAB 2008

PAVING SCHEDULE

LOCATION			PAVEMENT WIDTH (FOOT)	OUTSIDE SHOULDER WIDTH (FOOT)	MEDIAN SHOULDER WIDTH (FOOT)	TOTAL AREA (SQ YD)	PAVT AREA (SQ YD)	SHLD AREA (SQ YD)	BIT MATL PR CT (TON)	AGG PR CT (TON)	BINDER DEPTH (INCHES)	SURFACE DEPTH (INCHES)	SHLD SURF DEPTH (INCHES)	BINDER N105 (TON)	SURFACE N105 (TON)	SURF N30 FOR SHLD (TON)
I-72 MAINLINE																
EASTBOUND																
STA 627+00.00	TO	STA 635+79.29 BK	24	10	4	3,712.55	2,344.77	1,367.78	1.41	7.43	2.25	1.50	2.00	295.44	196.96	153.19
STA 634+03.49 AH	TO	STA 646+56.00	24	10	4	5,288.38	3,340.03	1,948.35	2.01	10.58	2.25	1.50	2.00	420.84	280.56	218.22
STA 646+56.00	TO	STA 649+30.00	24	10	4	1,156.89	730.67	426.22	0.44	2.31	2.25	1.50	2.00	92.06	61.38	47.74
STA 649+30.00	TO	STA 652+57.06	24	10	4	1,380.92	872.16	508.76	0.52	2.76	2.25	1.50	2.00	109.89	73.26	56.98
STA 652+57.06	TO	STA 659+20.00	24	0	4	2,062.48	1,767.84	294.64	0.78	4.12	2.25	1.50	2.00	222.75	148.50	33.00
STA 659+20.00	TO	STA 671+02.00	24	10	4	4,990.67	3,152.00	1,838.67	1.90	9.98	2.25	1.50	2.00	397.15	264.77	205.93
STA 671+02.00	TO	STA 673+12.11	24	0	4	653.67	560.29	93.38	0.25	1.31	2.25	1.50	2.00	70.60	47.06	10.46
STA 675+04.78	TO	STA 678+44.00	24	0	4	1,055.35	904.59	150.76	0.40	2.11	2.25	1.50	2.00	113.98	75.99	16.89
STA 678+44.00	TO	STA 684+54.96	24	8	4	2,443.84	1,629.23	814.61	0.93	4.89	2.25	1.50	2.00	205.28	136.86	91.24
STA 688+01.96	TO	STA 689+25.00	24	8	4	492.16	328.11	164.05	0.19	0.98	2.25	1.50	2.00	41.34	27.56	18.37
STA 689+25.00	TO	STA 694+78.00	24	8 TO 16	6	2,580.67	1,474.67	1,106.00	0.98	5.16	2.25	1.50	2.00	185.81	123.87	123.87
STA 694+78.00	TO	STA 695+67.00	24	10	4	375.77	237.33	138.44	0.14	0.75	2.25	1.50	2.00	29.90	19.94	15.51
WESTBOUND																
STA 627+00.00	TO	STA 635+79.29 BK	24	10	4	3,712.55	2,344.77	1,367.78	1.41	7.43	2.25	1.50	2.00	295.44	196.96	153.19
STA 634+03.49 AH	TO	STA 657+60.37	24	10	4	9,951.27	6,285.01	3,666.26	3.78	19.90	2.25	1.50	2.00	791.91	527.94	410.62
STA 657+60.37	TO	STA 673+13.13	24	0	4	4,830.81	4,140.69	690.12	1.84	9.66	2.25	1.50	2.00	521.73	347.82	77.29
STA 675+05.80	TO	STA 677+20.00	24	0	4	666.40	571.20	95.20	0.25	1.33	2.25	1.50	2.00	71.97	47.98	10.66
STA 677+20.00	TO	STA 684+19.00	24	8	4	2,796.00	1,864.00	932.00	1.06	5.59	2.25	1.50	2.00	234.86	156.58	104.38
STA 684+19.00	TO	STA 691+08.25	24	0	4	2,144.33	1,838.00	306.33	0.81	4.29	2.25	1.50	2.00	231.59	154.39	34.31
STA 691+08.25	TO	STA 691+21.00	24	10	4	53.83	34.00	19.83	0.02	0.11	2.25	1.50	2.00	4.28	2.86	2.22
I-55 BUSINESS LOOP																
NORTHBOUND																
STA 27+74.75	TO	STA 29+74.00	24	4	4	708.44	531.33	177.11	0.27	1.42	2.25	1.50	2.00	66.95	44.63	19.84
STA 29+74.00	TO	STA 40+27.62	24	8	4	4,214.48	2,809.65	1,404.83	1.60	8.43	2.25	1.50	2.00	354.02	236.01	157.34
STA 43+03.26	TO	STA 51+83.67	24	8	4	3,521.64	2,347.76	1,173.88	1.34	7.04	2.25	1.50	2.00	295.82	197.21	131.47
STA 51+83.67	TO	STA 58+97.00	24	0	4	2,219.25	1,902.21	317.04	0.84	4.44		2.00	2.00		213.05	35.51
STA 58+97.00	TO	STA 61+29.29	24	8 TO 9	4	942.07	619.44	322.63	0.36	1.88		2.00	2.00		69.38	36.13
STA 61+29.29	TO	STA 61+59.25	24	10	4	126.50	79.89	46.60	0.05	0.25		2.00	2.00		8.95	5.22
STA 61+59.25	TO	STA 62+93.73	24	0	4	418.38	358.61	59.77	0.16	0.84		2.00	2.00		40.16	6.69
STA 62+93.73	TO	STA 63+50.00	24	8	4	225.08	150.05	75.03	0.09	0.45		2.00	2.00		16.81	8.40
SOUTHBOUND																
STA 31+21.67	TO	STA 35+76.00	28 TO 36.9	10	0	2,142.92	1,638.11	504.81	0.81	4.29	2.25	1.50	2.00	206.40	137.60	56.54
STA 35+76.00	TO	STA 41+32.00	24	0	4	1,729.78	1,482.67	247.11	0.66	3.46	2.25	1.50	2.00	186.82	124.54	27.68
STA 41+32.00	TO	STA 49+56.00	24	10	4	3,479.11	2,197.33	1,281.78	1.32	6.96	2.25	1.50	2.00	276.86	184.58	143.56
STA 49+56.00	TO	STA 54+00.00	24	0	4	1,381.33	1,184.00	197.33	0.52	2.76		2.00	2.00		132.61	22.10
STA 54+00.00	TO	STA 54+15.24	24	0	4	47.41	40.64	6.77	0.02	0.09		2.00	2.00		4.55	0.76
STA 54+15.24	TO	STA 61+05.00	24	8	4	2,759.04	1,839.36	919.68	1.05	5.52		2.00	2.00		206.01	103.00
STA 61+05.00	TO	STA 63+50.00	24	0	4	762.22	653.33	108.89	0.29	1.52		2.00	2.00		73.17	12.20
I-55 MAINLINE																
NORTHBOUND																
STA 9+97.00	TO	STA 11+34.00	36	10	4	761.11	548.00	213.11	0.29	1.52	2.25	1.50	2.00	69.05	46.03	23.87
STA 11+34.00	TO	STA 27+77.96	36 TO 58	10	4	11,142.39	8,585.12	2,557.27	4.23	22.28	2.25	1.50	2.00	1,081.73	721.15	286.41
STA 27+77.96	TO	STA 64+66.59	24	10	4	15,574.22	9,836.35	5,737.87	5.92	31.15	2.25	1.50	2.00	1,239.38	826.25	642.64
STA 64+66.59	TO	STA 67+13.00	64 TO 58	10	0	1,943.90	1,670.11	273.79	0.74	3.89	2.25	1.50	2.00	210.43	140.29	30.66
STA 67+13.00	TO	STA 68+50.00	58 TO 51	10	4	1,042.72	829.61	213.11	0.40	2.09	2.25	1.50	2.00	104.53	69.69	23.87
STA 68+50.00	TO	STA 72+75.50	51 TO 36	10	4	2,718.47	2,056.58	661.89	1.03	5.44	2.25	1.50	2.00	259.13	172.75	74.13
STA 72+75.50	TO	STA 92+11.00	36	10	4	10,752.78	7,742.00	3,010.78	4.09	21.51	2.25	1.50	2.00	975.49	650.33	337.21
STA 92+11.00	TO	STA 98+11.00	36 TO 25	10	4	2,966.66	2,033.33	933.33	1.13	5.93	2.25	1.50	2.00	256.20	170.80	104.53
STA 98+11.00	TO	STA 128+87.38 BK	24	10	4	12,989.16	8,203.68	4,785.48	4.94	25.98	2.25	1.50	2.00	1,033.66	689.11	535.97
STA 128+91.29 AH	TO	STA 171+00.60	24	10	4	17,772.65	11,224.83	6,547.82	6.75	35.55	2.25	1.50	2.00	1,414.33	942.89	733.36

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

FAI55(I-55), FAI72(I-72), FAP666(I-55 BUS)
SECTION D6 INTERSTATE RS,BR,M CAB 2008
SANGAMON COUNTY

SCALE: DRAWN BY
DATE CHECKED BY

PLOT DATE = Oct-22-2007 08:15:17AM
FILE NAME = c:\Projects\d652802\shtsch.dgn
PLOT SCALE = 185.8824 / IN.
USER NAME = leughrr1