

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	SANGAMON	248	42

STA.	TO STA.
FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT

- * FA155(I-55), FA172(I-72), FAP666(I-55 BUS)
- ** D6 INTERSTATE RS,BR,M CAB 2008

CLASS A PATCHING SCHEDULE (I-72)

LOCATION	LENGTH DL (FOOT)	LENGTH PL (FOOT)	WIDTH (FOOT)	CL A 11" TY II (SQ YD)	CL A 15" TY II (SQ YD)	SAW CUTS (FOOT)	TIE BARS (EACH)	PATCH REINF (SQ YD)
EASTBOUND I-72								
STA 653+00	6.0		12.0	8.00		60.0		8.00
STA 655+00	6.0		12.0	8.00		60.0		8.00
STA 655+00		6.0	12.0	8.00		60.0		8.00
WESTBOUND I-72								
STA 655+00	6.0		12.0		8.00	60.0		8.00
STA 655+00		6.0	12.0		8.00	60.0		8.00
STA 654+00	6.0		12.0		8.00	60.0		8.00
STA 654+00		6.0	12.0		8.00	60.0		8.00
STA 650+50	6.0		12.0		8.00	60.0		8.00
TOTALS				24.00	40.00	480.0	0	64.00

CLASS B PATCHING SCHEDULE (I-72)

LOCATION	LENGTH DL (FOOT)	LENGTH PL (FOOT)	WIDTH (FOOT)	CL B 15" TY II (SQ YD)	CL B 18" TY II (SQ YD)	CL B 18" TY III (SQ YD)	SAW CUTS (FOOT)	DOWEL BARS (EACH)	TIE BARS (EACH)	PAVT FABRIC (SQ YD)
EASTBOUND I-72										
STA 665+00	6.0		12.0		8.00		48.0	20		
STA 665+00		6.0	12.0		8.00		48.0	20		
STA 666+66	6.0		12.0		8.00		48.0	20		
STA 669+10	8.0		12.0		10.67		52.0	20		
STA 669+10		8.0	12.0		10.67		52.0	20		
WESTBOUND I-72										
STA 697+50	6.0		12.0	8.00			48.0	20		
STA 697+50		6.0	12.0	8.00			48.0	20		
STA 683+00		6.0	12.0	8.00			48.0	20		
STA 680+10	6.0		12.0	8.00			48.0	20		
STA 680+10		6.0	12.0	8.00			48.0	20		
STA 678+00	7.0		12.0	9.33			50.0	20		
STA 678+00		7.0	12.0	9.33			50.0	20		
STA 669+70	6.0		12.0		8.00		48.0	20		
STA 669+70		6.0	12.0		8.00		48.0	20		
STA 668+20	18.0		12.0			24.00	72.0	20		24.00
STA 668+20		18.0	12.0			24.00	72.0	20		24.00
STA 665+20	8.0		12.0		10.67		52.0	20		
STA 665+20		8.0	12.0		10.67		52.0	20		
STA 664+40	6.0		12.0		8.00		48.0	20		
STA 664+50		6.0	12.0		8.00		48.0	20		
STA 656+40	8.0		12.0		10.67		52.0	20		
STA 656+40		8.0	12.0		10.67		52.0	20		
TOTALS				58.66	120.02	48.00	1,132.0	440	0	48.00

PLOT DATE = 06/22/2007 08:15:26AM
 FILE NAME = c:\p\projects\652282\shsch.dgn
 PLOT SCALE = 1/8"=1'-0" / IN.
 USER NAME = laughlin-1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF QUANTITIES
 FA155(I-55), FA172(I-72), FAP666(I-55 BUS)
 SECTION D6 INTERSTATE RS,BR,M CAB 2008
 SANGAMON COUNTY

SCALE: _____ DRAWN BY _____
 DATE _____ CHECKED BY _____