

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	SANGAMON	248	44
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
* FA155(I-55), FA172(I-72), FAP666(I-55 BUS)				
** D6 INTERSTATE RS,BR,M CAB 2008				

CLASS B PATCHING SCHEDULE (I-55)

LOCATION	DL (FOOT)	LENGTH ML (FOOT)	PL (FOOT)	WIDTH (FOOT)	CL B 16" TY II (SQ YD)	CL B 16" TY III (SQ YD)	CL B 16" TY IV (SQ YD)	SAW CUTS (FOOT)	DOWEL BARS (EACH)	TIE BARS (EACH)	PAVT FABRIC (SQ YD)
NORTHBOUND I-55											
STA 238+00			6.0	12.0	8.00			48.0	20		
STA 240+00	18.0			12.0		24.00		72.0	20		24.00
STA 247+00	7.0			12.0	9.33			50.0	20		
STA 247+60	15.0			12.0		20.00		66.0	20		20.00
STA 284+50	19.0			12.0			25.33	74.0	20		25.33
STA 286+20	20.0			12.0			26.67	76.0	20	10.0	26.67
STA 289+00	10.0			12.0	13.33			56.0	20		
STA 290+00	8.0			12.0	10.67			52.0	20		
STA 294+00	10.0			12.0	13.33			56.0	20		
STA 294+00			10.0	12.0	13.33			56.0	20		
STA 296+50	15.0			12.0		20.00		66.0	20		20.00
STA 304+00	12.0			12.0		16.00		60.0	20		16.00
STA 306+00	12.0			12.0		16.00		60.0	20		16.00
STA 308+00			12.0	12.0		16.00		60.0	20		16.00
STA 309+00	12.0			12.0		16.00		60.0	20		16.00
STA 309+00			12.0	12.0		16.00		60.0	20		16.00
STA 325+00	15.0			12.0		20.00		66.0	20		20.00
STA 325+00			10.0	12.0	13.33			56.0	20		
STA 329+00	25.0			12.0			33.33	86.0	20	13.0	33.33
STA 329+00			25.0	12.0			33.33	86.0	20	13.0	33.33
STA 333+50	7.0			12.0	9.33			50.0	20		
STA 333+50			7.0	12.0	9.33			50.0	20		
STA 334+00	6.0			12.0	8.00			48.0	20		
STA 334+00			6.0	12.0	8.00			48.0	20		
STA 340+33	10.0			12.0	13.33			56.0	20		
STA 340+33			7.0	12.0	9.33			50.0	20		
STA 352+00	14.0			12.0		18.67		64.0	20		18.67
STA 353+20	6.0			12.0	8.00			48.0	20		
STA 355+00	13.0			12.0		17.33		62.0	20		17.33
SOUTHBOUND I-55											
STA 350+00	12.0			12.0		16.00		60.0	20		16.00
STA 348+00	14.0			12.0		18.67		64.0	20		18.67
STA 341+10	12.0			12.0		16.00		60.0	20		16.00
STA 333+00	6.0			12.0	8.00			48.0	20		
STA 333+00			6.0	12.0	8.00			48.0	20		
STA 332+00	12.0			12.0		16.00		60.0	20		16.00
STA 332+00			7.0	12.0	9.33			50.0	20		
STA 327+60	16.0			12.0		21.33		68.0	20		21.33
STA 319+99	6.0			12.0	8.00			48.0	20		
STA 318+30	7.0			12.0	9.33			50.0	20		
STA 311+50	15.0			12.0		20.00		66.0	20		20.00
STA 308+00	15.0			12.0		20.00		66.0	20		20.00
STA 306+50	7.0			12.0	9.33			50.0	20		
STA 305+90	6.0			12.0	8.00			48.0	20		
STA 305+00	13.0			12.0		17.33		62.0	20		17.33
STA 305+10			6.0	12.0	8.00			48.0	20		
STA 302+00	7.0			12.0	9.33			50.0	20		
STA 297+00	8.0			12.0	10.67			52.0	20		
STA 296+00	8.0			12.0	10.67			52.0	20		
STA 292+00	6.0			12.0	8.00			48.0	20		
STA 292+00			6.0	12.0	8.00			48.0	20		
STA 282+00	6.0			12.0	8.00			48.0	20		
STA 282+00			6.0	12.0	8.00			48.0	20		
STA 282+00	8.0			12.0	10.67			52.0	20		
STA 282+00			6.0	12.0	8.00			48.0	20		
STA 276+50			6.0	12.0	8.00			48.0	20		
STA 254+00	18.0			12.0		24.00		72.0	20		24.00

PLOT DATE = 06/22/2007 08:15:30AM
 FILE NAME = c:\p\projects\4652882\shsch.dgn
 PLOT SCALE = 1/8"=1'-0" / IN.
 USER NAME = laughlin-1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF QUANTITIES
 FA155(I-55), FA172(I-72), FAP666(I-55 BUS)
 SECTION D6 INTERSTATE RS,BR,M CAB 2008
 SANGAMON COUNTY
 SCALE: _____ DRAWN BY _____
 DATE _____ CHECKED BY _____