

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	SANGAMON	248	47
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
* FA155(I-55), FA172(I-72), FAP666(I-55 BUS) ** D6 INTERSTATE RS,BR,M CAB 2008				

CLASS B PATCHING SCHEDULE (SIXTH ST INTERCHANGE RAMPS)																			
LOCATION		LENGTH (FOOT)	WIDTH (FOOT)	CL B 11" TY I (SQ YD)	CL B 11" TY II (SQ YD)	CL B 11" TY IV (SQ YD)	CL B 13" TY I (SQ YD)	CL B 13" TY II (SQ YD)	CL B 13" TY III (SQ YD)	CL B 13" TY IV (SQ YD)	CL B 15" TY I (SQ YD)	CL B 15" TY II (SQ YD)	CL B 15" TY III (SQ YD)	CL B 15" TY IV (SQ YD)	SAW CUTS (FOOT)	DOWEL BARS (EACH)	TIE BARS (EACH)	PAVT FABRIC (SQ YD)	
RAMP A																			
STA 4+00	LEFT	6.0	9.0					6.00							39.0	16	3		
STA 4+00	RIGHT	6.0	7.0				4.67								33.0	16	3		
STA 23+50	LEFT	6.0	9.0		6.00										39.0	16	3		
STA 23+50	RIGHT	6.0	7.0	4.67											33.0	16	3		
STA 28+00	LEFT	50.0	9.0			50.00									127.0	16	25	50.00	
STA 28+00	RIGHT	50.0	7.0			38.89									121.0	16	25	38.89	
RAMP B																			
STA 4+00	LEFT	8.0	9.0					8.00							43.0	16	4		
STA 4+00	RIGHT	8.0	7.0					6.22							37.0	16	4		
STA 6+50	LEFT	15.0	9.0						15.00						57.0	16	8	15.00	
STA 6+50	RIGHT	15.0	7.0					11.67							51.0	16	8		
STA 10+50	LEFT	6.0	9.0					6.00							39.0	16	3		
STA 10+50	RIGHT	6.0	7.0				4.67								33.0	16	3		
STA 15+40	LEFT	8.0	9.0					8.00							43.0	16	4		
STA 15+40	RIGHT	8.0	7.0					6.22							37.0	16	4		
STA 19+50	LEFT	60.0	9.0							60.00					147.0	16	30	60.00	
STA 19+50	RIGHT	60.0	7.0							46.67					141.0	16	30	46.67	
RAMP C																			
STA 0+70	LEFT	30.0	9.0											30.00	87.0	16	15	30.00	
STA 0+70	RIGHT	30.0	7.0										23.33	81.0	16	15	23.33		
STA 5+75	LEFT	6.0	9.0								6.00			39.0	16	3			
STA 5+75	RIGHT	6.0	7.0							4.67				33.0	16	3			
STA 10+00	LEFT	11.0	9.0								11.00			49.0	16	6			
STA 10+00	RIGHT	11.0	7.0								8.56			43.0	16	6			
STA 10+50	LEFT	6.0	9.0								6.00			39.0	16	3			
STA 10+50	RIGHT	6.0	7.0							4.67				33.0	16	3			
RAMP D																			
STA 6+00	LEFT	7.0	9.0								7.00			41.0	16	4			
STA 6+00	RIGHT	7.0	7.0								5.44			35.0	16	4			
STA 15+05	LEFT	8.0	9.0								8.00			43.0	16	4			
STA 15+05	RIGHT	8.0	7.0								6.22			37.0	16	4			
STA 17+50	LEFT	6.0	9.0								6.00			39.0	16	3			
STA 17+50	RIGHT	6.0	7.0							4.67				33.0	16	3			
STA 18+00	LEFT	6.0	9.0								6.00			39.0	16	3			
STA 18+00	RIGHT	6.0	7.0							4.67				33.0	16	3			
SW LOOP RAMP																			
STA 0+50	LEFT	6.0	9.0					6.00						39.0	16	3			
STA 0+50	RIGHT	6.0	7.0				4.67							33.0	16	3			
STA 7+50	LEFT	8.0	9.0		8.00									43.0	16	4			
STA 7+50	RIGHT	8.0	7.0		6.22									37.0	16	4			
STA 14+75	LEFT	6.0	9.0		6.00									39.0	16	3			
STA 14+75	RIGHT	6.0	7.0	4.67										33.0	16	3			
STA 16+50	LEFT	6.0	9.0		6.00									39.0	16	3			
STA 16+50	RIGHT	6.0	7.0	4.67										33.0	16	3			
NE RAMP																			
19+00	LEFT	30.0	9.0							30.00				87.0	16	15	30.00		
19+00	RIGHT	30.0	7.0						23.33					81.0	16	15	23.33		
TOTALS					14.01	32.22	88.89	14.01	58.11	38.33	136.67	18.68	70.22	23.33	30.00	2188.0	672	298	317.22

PLOT DATE = 06/22/2007 08:19:31AM
 FILE NAME = c:\p\projects\652882\shsch.dgn
 PLOT SCALE = 1/8"=1'-0" / IN.
 USER NAME = laughlin-1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF QUANTITIES
 FA155(I-55), FA172(I-72), FAP666(I-55 BUS)
 SECTION D6 INTERSTATE RS,BR,M CAB 2008
 SANGAMON COUNTY
 SCALE: _____ DRAWN BY _____
 DATE _____ CHECKED BY _____