

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	SANGAMON	248	50
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
* FA155(I-55), FA172(I-72), FAP666(I-55 BUS) ** D6 INTERSTATE RS,BR,M CAB 2008				

PATCHING SUMMARY

	CL A 11" TY II (SQ YD)	CL A 15" TY II (SQ YD)	CL B 11" TY I (SQ YD)	CL B 11" TY II (SQ YD)	CL B 11" TY IV (SQ YD)	CL B 13" TY I (SQ YD)	CL B 13" TY II (SQ YD)	CL B 13" TY III (SQ YD)	CL B 13" TY IV (SQ YD)	CL B 15" TY I (SQ YD)	CL B 15" TY II (SQ YD)	CL B 15" TY III (SQ YD)	CL B 15" TY IV (SQ YD)	CL B 16" TY II (SQ YD)	CL B 16" TY III (SQ YD)	CL B 16" TY IV (SQ YD)	CL B 18" TY II (SQ YD)	CL B 18" TY III (SQ YD)	PAVT PATCH 13" TY II (SQ YD)	PAVT PATCH 13" TY IV (SQ YD)	PATCH REINF (SQ YD)	SAW CUTS (FOOT)	DOWEL BARS (EACH)	TIE BARS (EACH)	PAVT FABRIC (SQ YD)
I-72 CL A	24.00	40.00																			64.00	480.0		0	
I-55														1,124.00	700.00	314.66						9,220.0	3,340	101	1,014.66
I-72 CL B									0.00	58.66	0.00	0.00					120.02	48.00				1,132.0	440	0	48.00
BL-55 CL B						0.00	208.00	40.00	0.00													960.0	380	0	40.00
6th ramps			14.01	32.22	88.89	14.01	58.11	38.33	136.67	18.68	70.22	23.33	30.00									2,188.0	672	298	317.22
Stev Ramps						23.35	70.88	0.00	0.00													596.0	256	40	0.00
So Gr Ramps						18.68	38.22	35.56	0.00													496.0	192	38	35.56
Clear Lk Ramps						42.03	180.19	35.56	0.00													1,492.0	608	150	35.56
BL-55 PP																			59.99	133.33					
TOTALS	24.00	40.00	14.01	32.22	88.89	98.07	555.40	149.45	136.67	18.68	128.88	23.33	30.00	1,124.00	700.00	314.66	120.02	48.00	59.99	133.33	64.00	16,564.0	5,888	627	1,491.00

SEEDING SUMMARY

LOCATION	LENGTH (FOOT)	WIDTH (FOOT)	SEEDING CLASS 2 (ACRE)	MULCH METH 2 (ACRE)	TEMP EROS CONTROL SEEDING (POUND)	EROSION CONTROL BLANKET (SQ YD)	NITR FERT NUTR (POUND)	PHOS FERT NUTR (POUND)	POTASS FERT NUTR (POUND)	AGR GROUND LIME (TON)
FROM GRADING & SHAPING SCHEDULE			2.21	2.17	442	100	199	199	199	4.4
FROM CABLE BARRIER SCHEDULE			6.69		1,338	32,506	602	602	602	13.4
FROM FENCE SCHEDULE			19.39	19.39	3,878		1,745	1,745	1,745	38.8
I-55 EMERGENCY MEDIAN X-OVER 15+55	50	25	0.03	0.03	6		3	3	3	0.1
I-72 X-OVER DE-GRADING 627+90	100	50	0.11	0.11	22		10	10	10	0.2
I-72 EMERGENCY MEDIAN X-OVER 640+55	100	50	0.11	0.11	22		10	10	10	0.2
STEVENSON DRIVE: RAMP A/B	40	35	0.03	0.03	6		3	3	3	0.1
SOUTH GRAND: RAMP B STORM SEWER	1,192	40	1.09	1.09	218		98	98	98	2.2
TOTALS			29.66	22.93	5,932	32,606	2,670	2,670	2,670	59.4

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
 FA155(I-55), FA172(I-72), FAP666(I-55 BUS)
 SECTION D6 INTERSTATE RS,BR,M CAB 2008
 SANGAMON COUNTY

SCALE: _____ DRAWN BY _____
 DATE _____ CHECKED BY _____