

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	SANGAMON	248	52

STA. TO STA.
 FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT
 * FA155(I-55), FA172(I-72), FAP666(I-55 BUS)
 ** D6 INTERSTATE RS,BR,M CAB 2008

DRAINAGE SCHEDULE - REMOVAL AND ADJUSTMENT ITEMS

LOCATION	PIPE CULV REM	REM INLETS	END SECT TO BE REMOVED	INLET TO BE ADJ	FR & GR TO BE ADJ	FR & LID TO BE ADJ	REM AND RELAY END SECT
(FOOT)	(EACH)	(EACH)	(EACH)	(EACH)	(EACH)	(EACH)	(EACH)
I-55 MAINLINE							
1 STA 15+55	MED						
2 STA 39+80	SB RT		1				
13 STA 82+55	SB LT		1				
17 STA 105+90	MED			1			
18 STA 116+41	MED	1					
20 STA 126+40	NB RT					1	
21 STA 127+10	SB LT					1	
22 STA 128+00	NB RT					1	
23 STA 128+70	SB LT					1	
26 STA 159+00	NB RT						
79 STA 342+00	SB LT		1				
I-72 MAINLINE							
92 STA 667+90	WB LT				1		
94 STA 687+50	WB LT				1		1
BL-55							
86 STA 52+24	NB RT						
SIXTH ST INTERCHANGE							
NE RAMP							
95 STA 5+30	RT						
96 STA 10+40	LT						1
SOUTH GRAND INTERCHANGE							
RAMP A							
51 STA 4+00	RT		1				
52 STA 4+72	RT		1				
TOTAL		1	5	1	2	4	2

DRAINAGE SCHEDULE - PIPE CULVERTS, STORM SEWER

LOCATION	PIPE CULV CL D, TY 1, 12"	P CULV CULV TY 1, RCCP 24"	PIPE CULV RCCP 30"	PIPE CULV RCCP 36"	SS TY 1 RC EP SPAN 38 RISE 24
(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)
I-55 MAINLINE					
1 STA 15+55	MED				
I-72 MAINLINE					
103 STA 640+00	EB	8.0	60.0		
83 STA 640+55	MED	82.0			
85 STA 654+90	EB LT		4.0		
84 STA 662+00	WB LT		4.0		
50 STA 662+00	EB RT		4.0		
SIXTH ST INTERCHANGE					
NE RAMP					
95 STA 5+30	RT	26.0			
96 STA 10+40	LT			8.0	
SOUTH GRAND INTERCHANGE					
RAMP B					
STA 15+10 TO 27+02					1, 192.0
TOTAL		52.0	116.0	72.0	8.0
					1, 192.0

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
 FA155(I-55), FA172(I-72), FAP666(I-55 BUS)
 SECTION D6 INTERSTATE RS,BR,M CAB 2008
 SANGAMON COUNTY

SCALE: DATE: DRAWN BY: CHECKED BY: