

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	SANGAMON	248	53
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
* FA155(I-55), FA172(I-72), FAP666(I-55 BUS)				
** D6 INTERSTATE RS,BR,M CAB 2008				

DRAINAGE SCHEDULE - END SECTIONS & GRATES

LOCATION	PRC FL END SECT 30"	GR FOR CONC FL END SECT 30"	PRC FL END SECT 36"	GR FOR CONC FL END SECT 36"	PRC FL END SECT 42"	GR FOR CONC FL END SECT 42"	PRC FL END SECT 30"
	(EACH)	(EACH)	(EACH)	(EACH)	(EACH)	(EACH)	(EACH)
I-55 MAINLINE							
2 STA 39+80 SB RT	1	1					
13 STA 82+55 SB LT					1	1	
79 STA 342+00 SB LT	1	1					
I-72 MAINLINE							
85 STA 654+90 EB LT	1	1					
84 STA 662+00 WB LT	1	1					
50 STA 662+00 EB RT	1	1					
SOUTH GRAND INTERCHANGE							
RAMP A							
51 STA 4+00 RT			1	1			
52 STA 4+72 RT			1	1			
RAMP B							
54 STA 15+00 RT							1
TOTAL	5	5	2	2	1	1	1

DRAINAGE SCHEDULE - INLETS & MANHOLES

LOCATION	MH 4' DIA TY 8 GRATE	RD MH 4' DIA TY 8 GRATE	RD MH 9' DIA TY 1 FR CL LID	INLET BOX STD 542526	FL INLET BOX STD 542546
	(EACH)	(EACH)	(EACH)	(EACH)	(EACH)
I-55 MAINLINE					
18 STA 116+41 MED					1
I-72 MAINLINE					
103 STA 640+00 EB			1	1	
SOUTH GRAND INTERCHANGE					
RAMP B					
STA 17+50		1			
STA 18+50		1			
STA 19+50		1			
STA 21+00		1			
STA 22+50	1				
STA 24+50		1			
STA 27+02	1				
TOTAL	2	5	1	1	1

DRAINAGE SCHEDULE - RIPRAP ITEMS

LOCATION	STONE RIPRAP CL A4	STONE RIPRAP CL A5	FILTER FABRIC
	(SQ YD)	(SQ YD)	(SQ YD)
I-55 MAINLINE			
17 STA 105+90 NB RT	25.0		25.0
19 STA 124+38 SB LT	20.0		20.0
25 STA 141+70 NB RT	25.0		25.0
26 STA 159+00 NB RT	55.6		55.6
32 STA 175+00 NB RT	16.0		16.0
39 STA 201+14 NB RT		25.0	25.0
41 STA 211+00 NB RT	25.0		25.0
99 STA 274+29 SB LT		8.0	8.0
65 STA 287+56 SB LT	43.2		43.2
68 STA 311+70 NB RT	25.0		25.0
68 STA 311+70 SB LT	16.0		16.0
81 STA 354+10 NB RT	16.0		16.0
I-72 MAINLINE			
50 STA 662+00 EB RT	25.0		25.0
STEVENSON DR INTERCHANGE			
RAMP C			
37 STA 6+00 RT	16.0		16.0
RAMP D			
STA 5+00 RT	277.8		277.8
SOUTH GRAND INTERCHANGE			
RAMP A			
STA 3+95 TO STA 4+75	88.9		88.9
STA 4+60 TO STA 6+00	155.6		155.6
RAMP B			
54 STA 15+00 RT	66.7		66.7
RAMP C			
53 STA 6+50 LT	33.3		33.3
57 STA 15+35 RT	16.0		16.0
RAMP D			
58 STA 7+25 LT	22.2		22.2
CLEAR LAKE INTERCHANGE			
RAMP E			
76 STA 11+00 LT	60.0		60.0
STA 12+20 TO STA 15+80	368.9		368.9
TOTAL	1,397.2	33.0	1,430.2

PLOT DATE = 08/15/2007 08:15:35AM
 FILE NAME = c:\p\projects\652882\shsch.dgn
 PLOT SCALE = 1/8"=1'-0" / IN.
 USER NAME = laughlin-1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
 FA155(I-55), FA172(I-72), FAP666(I-55 BUS)
 SECTION D6 INTERSTATE RS,BR,M CAB 2008
 SANGAMON COUNTY
 SCALE: _____ DRAWN BY _____
 DATE _____ CHECKED BY _____