

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	SANGAMON	248	58
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
* FA155(I-55), FA172(I-72), FAP666(I-55 BUS) ** D6 INTERSTATE RS,BR,M CAB 2008				

GUARDRAIL SCHEDULE

LOCATION	GR REM (FOOT)	R & R SPBGR (FOOT)	SPBGR TYPE A (FOOT)	TRAFFIC BARRIER TERMINAL				TERM MK DA (EACH)	GR MARK (EACH)		
				TY 1 SP (T) (EACH)	TY 2 (EACH)	TY 5 (EACH)	TY 6 (EACH)				
CLEAR LAKE INTERCHANGE											
RAMP F											
66 RT STA 11+75	TO	STA 12+25	50.0					1			
RT STA 12+25	TO	STA 17+25	500.0	500.0					8		
RT STA 17+25	TO	STA 17+38	12.5					1			
<b>TOTALS</b>			4,547.5	18,650.0	5,262.5	29	9	1	4	29	376

GUARD POSTS	QUANTITY
LOCATION	EACH
I-72 MAINLINE	
MEDIAN	
STA 627+85	8
<b>TOTAL</b>	<b>8</b>

HIGH TENSION CABLE MEDIAN BARRIER ITEMS SCHEDULE

LOCATION	SHLD WIDTH (FOOT)	SEED/EROS BLANK WIDTH (FOOT)	HTC MED BAR (FOOT)	MED BAR TERM (EACH)	CABLE GUARD MARKER (EACH)	EXCAV & GRADE SHLD (UNIT)	HMA SHLD 4" (SQ YD)	SEEDING CL 2 (ACRE)	EROS BLANK (SQ YD)		
										I-55 MAINLINE	
RT STA 14+81.00	TO	STA 15+11.00	6.0	12.0		0.30	20.00	0.01	40.00		
RT STA 15+11.00	TO	STA 15+61.00	6.0	12.0	1	0.50	33.33	0.01	66.67		
RT STA 15+61.00	TO	STA 23+83.00	6.0	12.0	822	21	8.22	548.00	1,096.00		
RT STA 23+83.00	TO	STA 24+33.00	6.0	12.0	1	0.50	33.33	0.01	66.67		
LT STA 93+50.00	TO	STA 94+00.00	6.0	20.0	1	0.50	33.33	0.02	111.11		
LT STA 94+00.00	TO	STA 116+46.00	6.0	20.0	2,246	56	22.46	1,497.33	4,991.11		
LT STA 116+46.00	TO	STA 116+96.00	6.0	20.0	1	0.50	33.33	0.02	111.11		
LT STA 116+96.00	TO	STA 117+26.00	6.0	20.0		0.30	20.00	0.01	66.67		
LT STA 117+26.00	TO	STA 117+92.00	6.0	12.0		0.30	20.00	0.01	40.00		
RT STA 117+92.00	TO	STA 118+42.00	6.0	12.0	1	0.50	33.33	0.01	66.67		
RT STA 118+42.00	TO	STA 128+87.38 BK	6.0	12.0	1,045	26	10.45	696.92	1,393.84		
RT STA 128+87.38 BK	TO	STA 233+44.43 BK	6.0	12.0	10,453	261	104.53	6,968.76	13,937.52		
RT STA 233+44.43 BK	TO	STA 249+54.00	6.0	12.0	1,601	40	16.01	1,067.53	2,135.07		
RT STA 249+54.00	TO	STA 250+04.00	6.0	12.0	1	0.50	33.33	0.01	66.67		
RT STA 286+04.00	TO	STA 286+54.00	6.0	12.0	1	0.50	33.33	0.01	66.67		
RT STA 286+54.00	TO	STA 347+92.00	6.0	12.0	6,138	153	61.38	4,092.00	8,184.00		
RT STA 347+92.00	TO	STA 348+42.00	6.0	12.0	1	0.50	33.33	0.01	66.67		
<b>TOTAL</b>					22,305	8	565	227.95	15,197.18	6.69	32,506.45

PIPE UNDERDRAIN OUTLET EXTENSION SPECIAL

LOCATION	QUANTITY
(EACH)	
I-55 MAINLINE	
RT STA 14+81.00 TO STA 24+33.00	2
LT STA 93+50.00 TO STA 116+96.00	5
RT STA 117+92.00 TO STA 128+87.38 BK	2
RT STA 128+91.29 AH TO STA 233+44.43 BK	21
RT STA 233+52.70 AH TO STA 250+04.00	3
RT STA 286+04.00 TO STA 348+42.00	12
SOUTH GRAND INTECHANGE, RAMP B	
RT STA 15+10.00 TO STA 27+02.00	2
<b>TOTAL</b>	<b>47</b>

PLOT DATE = 04-22-2007 08:15:38AM  
 FILE NAME = c:\p\projects\4652882\htsch.dgn  
 PLOT SCALE = 1/8"=1'-0" / IN.  
 USER NAME = laughlin-1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SCHEDULE OF QUANTITIES**  
 FA155(I-55), FA172(I-72), FAP666(I-55 BUS)  
 SECTION D6 INTERSTATE RS,BR,M CAB 2008  
 SANGAMON COUNTY  
 SCALE: DATE: DRAWN BY: CHECKED BY: