

F.A.P. RY.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
321	18(N-1,TS)	PIKE	55	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

LOCATION OF WORK				ROADWAY IMPROVEMENT	TRAFFIC SIGNALS
				90% FEDERAL 10% STATE	90% FEDERAL 5% STATE 5% CITY
SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE	
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	1000	Y031-IF
20200100	EARTH EXCAVATION	CU YD	145	145	
20800150	TRENCH BACKFILL	CU YD	10	10	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	7	7	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	7	7	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	7	7	
25000700	AGRICULTURAL GROUND LIMESTONE	TON	0.2	0.2	
25200100	SODDING	SQ YD	533	533	
25200200	SUPPLEMENTAL WATERING	UNIT	26.6	26.6	
31101000	SUB-BASE GRANULAR MATERIAL, TYPE B	TON	85	85	
35300400	PORTLAND CEMENT CONCRETE BASE COURSE 9"	SO YD	255	255	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	4.2	4.2	
40600300	AGGREGATE (PRIME COAT)	TON	22	22	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	367	367	
40600990	TEMPORARY RAMP	SQ YD	108	108	
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	123	123	
40603540	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1,138	1,138	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	48	48	
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SO FT	1,421	1,421	
42400800	DETECTABLE WARNINGS	SO FT	120	120	
44000100	PAVEMENT REMOVAL	SQ YD	38	38	
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SO YD	9,088	9,088	
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SO YD	1,433	1,433	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	92	92	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	489	489	
44000600	SIDEWALK REMOVAL	SO FT	1,224	1,224	
44200140	PAVEMENT PATCHING, TYPE I, 12 INCH	SO YD	4	4	
44200144	PAVEMENT PATCHING, TYPE II, 12 INCH	SO YD	36	36	
44200148	PAVEMENT PATCHING, TYPE III, 12 INCH	SO YD	16	16	

PLOT DATE = 04-10-2007 15:56:17PM
FILE NAME = I:\321\824\1\IN
PLOT SCALE = 100.0000 X 1.0000
USER NAME = laughton

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

FAP 321 (US 54/IL 106)
SECTION 18(N-1,TS)
PIKE COUNTY

SCALE: VERT.
HORIZ.
DATE

DRAWN BY
CHECKED BY