

| | | | | |
|---------------------|----------|------------------|--------------|-----------|
| FAP RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| 325 | # | MACOUPIN | 6 | 3 |
| STA. | | TO STA. | | |
| FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT | | |

- D-6 SHLDR RUMBLE STRIPS 2008-03

SUMMARY OF QUANTITIES

| CODE NO | PAY ITEM | UNIT | 90% FED 10% STATE SFTY - 2A QUANTITY |
|------------|---|--------|---|
| 20200600 | EXCAVATING AND GRADING EXISTING SHOULDER | UNIT | 48 |
| 25000200 | SEEDING, CLASS 2 | ACRE | 0.3 |
| 25000400 | NITROGEN FERTILIZER NUTRIENT | POUND | 27 |
| 25000500 | PHOSPHOROUS FERTILIZER NUTRIENT | POUND | 27 |
| 25000600 | POTASSIUM FERTLIZER NUTRIENT | POUND | 27 |
| 25100115 | MULCH, METHOD 2 | ACRE | 0.3 |
| 48101200 | AGGREGATE SHOULDERS, TYPE B | TON | 256 |
| 48203029 | HOT-MIX ASPHALT SHOULDERS, 8" | SQ YD | 1652 |
| * 63000000 | STEEL PLATE BEAM GUARDRAIL TYPE A | FOOT | 112.5 |
| * 63100167 | TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (TANGENT) | EACH | 2 |
| 63200310 | GUARDRAIL REMOVAL | FOOT | 169 |
| 64200105 | SHOULDER RUMBLE STRIP | FOOT | 4750 |
| 67100100 | MOBILIZATION | L SUM | 1 |
| 70100460 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701306 | L SUM | 1 |
| 70100500 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701326 | L SUM | 1 |
| 70103815 | TRAFFIC CONTROL SURVEILLANCE | CAL DA | 10 |
| * 72000100 | SIGN PANEL, TYPE 1 | SQ FT | 90.5 |
| * 78001120 | PAINT PAVEMENT MARKING - LINE 5" | FOOT | 5359 |
| * 72800100 | TELESCOPIC STEEL SIGN SUPPORT | FOOT | 190 |
| * 78201000 | TERMINAL MARKER - DIRECT APPLIED | EACH | 2 |

PLT FILE : C:\p05-2007\810211PM
 FILE NAME : 810211PM.dgn
 PLT SCALE : 1/8"=1'-0"
 USER NAME : laughlin-1

*SPECIALTY ITEMS

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
 FAP 325 (IL RTE. 16)
 SECTION D-6 SHLDR RUMBLE STRIPS 2008-03
 MACOUPIN COUNTY
 DATE JULY 23, 2007 DRAWN BY RTS