

S U M M A R Y O F Q U A N T I T I E S

CODE NO.	ITEM	UNIT	100% STATE
			Y030-1E TOTAL QTY
67100100	MOBILIZATION	L SUM	1
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1
80400100	ELECTRIC SERVICE INSTALLATION	EACH	1
81020700	CONDUIT PUSHED, 3" DIA. INTERMEDIATE METAL	FOOT	238
81603000	UNIT DUCT, 600V, 2-1C NO.8, 1/C NO.8 GROUND, (XLP-TYPE USE) 3/4" DIA. POLYETHYLENE	FOOT	1,335
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	948
82103900	LUMINAIRE, SODIUM VAPOR, MULTI-MOUNT, 250 WATT	EACH	10
82500605	LIGHTING CONTROLLER PHOTOCELL RELAY	EACH	1
83062730	LIGHT POLE, WEATHERING STEEL, 45 FT. M.H., TENON MOUNT	EACH	6
83062735	LIGHT POLE, WEATHERING STEEL, 45 FT. M.H., TENON MOUNT - TWIN	EACH	2
83600355	LIGHT POLE FOUNDATION METAL, 15" BOLT CIRCLE, 8" X 6'	EACH	6
83600357	LIGHT POLE FOUNDATION METAL, 15" BOLT CIRCLE, 8" X 8'	EACH	2
83800650	BREAKAWAY DEVICE, COUPLING, WITH STAINLESS STEEL SCREEN	EACH	32

QUANTITIES
FAP 310 (U.S. 67)
SECTION 69-12I
MORGAN COUNTY

Rev.