

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
310	60-15HB	MADISON	185	4
STA.		TO STA.		
FED. ROAD DIST. NO. -		ILLINOIS FED. AID PROJECT		
CONTRACT NO. 76626				

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	80% FEDERAL 20% STATE		
				ROADWAY	BOX CULVERT	BRIDGE
				CONSTRUCTION TYPE CODE		
				1000	X028-2A	X271-2A
M5020100	STRUCTURE EXCAVATION	CU M	372			372
M5030280	CONCRETE ENCASEMENT	CU M	2.4			2.4
M5030290	FORM LINER TEXTURED SURFACE	SQ M	217			217
M5030350	CONCRETE STRUCTURES	CU M	281.2			281.2
M5030360	CONCRETE SUPERSTRUCTURE	CU M	229.7			229.7
M5030390	BRIDGE DECK GROOVING	SQ M	681			681
M5080105	REINFORCEMENT BARS	KG	19,840		19,840	
M5080205	REINFORCEMENT BARS, EPOXY COATED	KG	51,510			51,510
M5110200	SLOPE WALL 150 MM	SQ M	48			48
M5120130	FURNISHING STEEL PILES HP200X54	METER	247.0			247.0
M5120140	FURNISHING STEEL PILES HP250X62	METER	213.5			213.5
M5120160	FURNISHING STEEL PILES HP310X79	METER	548.0			548.0
M5120335	DRIVING PILES	METER	1,008.5			1,008.5
M5120430	TEST PILE STEEL HP200X54	EACH	2			2
M5200225	PREFORMED JOINT STRIP SEAL	METER	23.0			23.0
M5403000	CONCRETE BOX CULVERTS	CU M	221.5		221.5	
M542E028	END SECTIONS 600MM	EACH	6	6		
M542E044	END SECTIONS 900MM	EACH	6	6		
M542E012	END SECTIONS 300MM	EACH	2	2		
M542E020	END SECTIONS 450MM	EACH	2	2		
M542E028	END SECTIONS 600MM	EACH	2	2		
M542E044	END SECTIONS 900MM	EACH	4	4		
M542H040	PIPE CULVERTS, CLASS A, TYPE 1 600MM	METER	15.5	15.5		
M542H425	PIPE CULVERTS, CLASS D, TYPE 1 375MM	METER	25.0	25.0		
M542I040	PIPE CULVERTS, CLASS A, TYPE 2 600MM	METER	18.0	18.0		
M542I430	PIPE CULVERTS, CLASS D, TYPE 2 450MM	METER	56.5	56.5		
M542I455	PIPE CULVERTS, CLASS D, TYPE 2 900MM	METER	18.5	18.5		
M542J440	PIPE CULVERTS, CLASS D, TYPE 3 600MM	METER	23.5	23.5		
M542J455	PIPE CULVERTS, CLASS D, TYPE 3 900MM	METER	40.0	40.0		
M542K055	PIPE CULVERTS, CLASS A, TYPE 4 900MM	METER	38.0	38.0		
M542T415	PIPE CULVERTS, CLASS D, TYPE 1 300MM (TEMPORARY)	METER	16.5	16.5		
M542T425	PIPE CULVERTS, CLASS D, TYPE 1 450MM (TEMPORARY)	METER	10.5	10.5		
M542U435	PIPE CULVERTS, CLASS D, TYPE 2 600MM (TEMPORARY)	METER	12.5	12.5		
M5870300	CONCRETE SEALER	SQ M	16			16
M5910100	GEOCOMPOSITE WALL DRAIN	SQ M	96.6			96.6
M5930100	CONTROLLED LOW-STRENGTH MATERIAL	CU M	3	3		
M6010125	PIPE DRAINS 300MM	METER	25.0	25.0		
M6011100	PIPE UNDERDRAINS FOR STRUCTURES 100MM	METER	29.9			29.9
M6060070	CONCRETE CURB, TYPE B	METER	16.3	16.3		
*M6300100	STEEL PLATE BEAM GUARD RAIL, TYPE A	METER	91.44	91.44		

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	80% FEDERAL 20% STATE		
				ROADWAY	BOX CULVERT	BRIDGE
				CONSTRUCTION TYPE CODE		
				1000	X028-2A	X271-2A
M7030100	SHORT-TERM PAVEMENT MARKING	METER	185	185		
M7031000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ M	19	19		
*M7200100	SIGN PANEL - TYPE 1	SQ M	0.6	0.6		
*M7300100	WOOD SIGN SUPPORT	METER	4.6	4.6		
*M7800205	PAINT PAVEMENT MARKING - LINE 100MM	METER	3,618	3,618		
M2034730	MODULAR RETAINING WALL SYSTEM	SQ M	8	8		
MX511050	BRICK SLOPEWALL	SQ M	147			147
X7011005	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	L SUM	1			1
*Z0049901	REMOVAL AND DISPOSAL OF NON-FRIABLE ASBESTOS, BUILDING NO. 1	L SUM	1	1		

*SPECIALTY ITEMS

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
SCALE: NONE		DRAWN BY: JH
DATE: 04/2005		