

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55/70	60-7K-2	MADISON	26	I
STA.		TO STA.		
FBI. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

PAVING SCHEDULE

LOCATION			PAVED SHOULDER REMOVAL	HOT-MIX ASPHALT SHOULDERS, 8"	SUB-BASE GRANULAR MATERIAL, TYPE B 12"	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 10"	HMA SURFACE REMOVAL, 1.5"	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	HMA SHOULDERS MIX	LEVELING BINDER (MM)	HMA SURFACE COURSE	STRIP REFLECTIVE CRACK CONTROL TREATMENT	COMB CONC CURB & GUTTER TYPE B-6.24
STA	TO	STA	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	TON	TON	TON	TON	TON	FOOT	FOOT
254+82.	TO	255+01.5	17.2	15.1	5.4	2	30	0.019	0.090	-	1.3	2.5	19.5	-
255+01.5	=	0+00	-	-	-	-	-	-	-	-	-	-	-	-
0+00	TO	0+14	11.7	9.1	3.8	3	20	0.014	0.069	-	1.0	1.9	14	-
0+14	TO	0+23	7.2	5.0	3.7	3	21	0.016	0.076	-	0.7	1.4	9	-
0+23	TO	0+48.5	17.6	14.2	14.3	12	42	0.034	0.162	-	2.3	4.5	25.5	-
0+48.5	TO	1+00.	29.5	28.6	46.4	42	102	0.090	0.433	-	6.1	12.1	51.5	-
1+00.	TO	2+00.	57.2	55.6	138.9	131	208	0.212	1.017	2.3	14.2	28.5	100	-
2+00.	TO	3+00.	62.2	55.6	162.2	154	220	0.234	1.122	5.6	15.7	31.4	100	-
3+00.	TO	4+00.	60.0	55.6	141.1	133	262	0.247	1.185	5.6	16.6	33.2	100	-
4+00.	TO	5+00.	56.1	55.6	92.8	84	316	0.250	1.200	5.6	16.8	33.6	100	-
5+00.	TO	5+57.5	42.5	31.9	24.0	19	212	0.145	0.693	3.2	9.7	19.4	57.5	-
5+57.5	TO	5+74.	14.5	-	7.8	5	67	0.045	0.216	0.9	10.5	21.0	16.5	16
5+74.	TO	6+00.	24.6	-	-	-	122	0.076	0.365	1.3	5.1	10.2	-	26.5
6+00.	TO	6+25.	26.3	-	0.5	0	158	0.099	0.474	0.3	6.6	13.3	-	32
6+25.	TO	6+52.5	97.1	-	91.8	75	342	0.214	1.026	-	14.4	28.7	105	96.5
FOR SHOULDERS							197	0.060	0.300					
TOTALS			524	326	733	663	2319	1.8	8.4	25	121	242	699	171

EARTHWORK SCHEDULE

LOCATION			EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
STA	TO	STA	CUBIC YARD	CUBIC YARD	CUBIC YARD	CUBIC YARD
254+75	TO	0+00	0.81	0.61	8.77	-8.16
0+00	TO	0+25	3.59	2.69	16.34	-13.65
0+25	TO	0+50	7.39	5.54	19.15	-13.61
0+50	TO	0+75	10.26	7.70	24.99	-17.30
0+75	TO	1+00	12.71	9.53	31.5	-21.97
1+00	TO	1+25	15.28	11.46	38.62	-27.16
1+25	TO	1+50	17.56	13.17	41.42	-28.25
1+50	TO	1+75	19.02	14.27	41.67	-27.41
1+75	TO	2+00	20.62	15.47	39.71	-24.25
2+00	TO	2+25	22.36	16.77	35.72	-18.95
2+25	TO	2+41	16.16	12.12	16.31	-4.19
2+41	TO	2+50	8.23	6.17	9.47	-3.30
2+50	TO	2+75	21.20	15.90	35.57	-19.67
2+75	TO	3+00	20.86	15.65	36.53	-20.89
3+00	TO	3+25	19.58	14.69	45.53	-30.85
3+25	TO	3+50	17.95	13.46	53.56	-40.10
3+50	TO	3+75	16.94	12.71	53.51	-40.81
3+75	TO	4+00	16.49	12.37	50.56	-38.19
4+00	TO	4+25	14.62	10.97	44.58	-33.62
4+25	TO	4+50	13.05	9.79	37.4	-27.61
4+50	TO	4+75	11.14	8.36	31.66	-23.31
4+75	TO	5+00	9.36	7.02	25	-17.98
5+00	TO	5+25	7.42	5.57	17.27	-11.71
5+25	TO	5+50	4.31	3.23	8.31	-5.08
5+50	TO	5+75	3.30	2.48	3.75	-1.28
5+75	TO	6+00	3.33	2.50	2.49	0.01
6+00	TO	6+25	3.22	2.42	1.47	0.95
6+25	TO	6+39	2.05	1.54	0.56	0.98
TOTALS			339	254	771	-517

PAVEMENT MARKING SCHEDULE

LOCATION			4" PREFORMED PLASTIC					8" PREFORMED PLASTIC	12" PREFORMED PLASTIC	24" PREFORMED PLASTIC	PREFORMED PLASTIC LETTERS & SYMBOLS			RAISED REFLECTIVE PAVEMENT MARKERS	
			WHITE		YELLOW			WHITE	WHITE	WHITE	WHITE			ONE-WAY CRYSTAL	REMOVAL
			SKIP DASH, 2' - 6"	SKIP DASH, 10' - 30"	EDGE LINE	LANE LINE	EDGE LINE	WHITE	WHITE	WHITE	LEFT TURN ARROW	STRAIGHT/LEFT TURN ARROW	RIGHT TURN ARROW		
			FOOT	FOOT	FOOT	FOOT	FOOT	EDGE LINE	DIAGONALS	STOP BAR	SQ FT	SQ FT	SQ FT	EACH	EACH
254+82.	TO	255+01.5	10	-	19.5	-	-	19.5	-	-	-	-	-	-	-
255+01.5	=	0+00	-	-	-	-	-	-	-	-	-	-	-	-	-
0+00	TO	1+63.5	82	-	163.5	-	-	163.5	-	-	-	-	-	-	-
1+63.5	TO	3+85.	55	60	221.5	-	221.5	-	-	-	-	-	3	-	-
	TO	1+88.5	-	-	-	-	-	-	-	15.6	26	-	-	-	-
3+85.	TO	5+74.	-	50	189	189	189	-	-	-	-	-	3	6	-
	TO	3+91.5	-	-	-	-	-	-	-	15.6	26	-	-	-	-
	TO	4+10.	-	-	-	-	-	-	-	-	-	15.6	-	-	-
	TO	5+14.	-	-	-	-	-	-	-	-	-	-	-	-	-
5+74.	TO	5+90.	-	0	16	16	16	-	-	-	-	-	-	-	-
5+90.	TO	6+30.5	-	10	40.5	40.5	40.5	-	49.5	-	-	-	-	3	-
	TO	6+05.5	-	-	-	-	-	-	-	15.6	26	-	-	-	-
	TO	6+16.	-	-	-	-	-	-	-	-	-	15.6	-	-	-
	TO	6+29.	-	-	-	-	-	-	18	-	-	-	-	-	-
	TO	6+30.5	-	-	-	-	-	-	24	-	-	-	-	-	-
6+30.5	TO	6+52.5	-	-	67	232.5	-	-	119.5	-	-	-	-	11	4
SUB TOTALS			147	120	717	478	467	183	169	42	46.8	78	31.2	17	13
TOTALS					1929			183	169	42		156		17	13

MEDIAN SCHEDULE

LOCATION	MEDIAN REMOVAL	SUB-BASE GRANULAR MATERIAL TYPE B 12"	PCC BASE COURSE 10"	COMB CURB & GUTTER REMOVAL	CONC MEDIAN SURFACE REMOVAL	COMB CONC CURB & GUTTER TYPE B-6.24	CONC MEDIAN SURFACE 4"	CONC MEDIAN
	SF	SY	SY	FT	SF	FT	SF	SF
MEDIAN	14	17	13	59	250	34	97	39

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SCHEDULE OF QUANTITIES**  
 FAIRROUTE 55/70  
 SECTION 60-7K-2  
 MADISON COUNTY

SCALE: VERT. \_\_\_\_\_  
 HORIZ. \_\_\_\_\_  
 DATE \_\_\_\_\_

DRAWN BY \_\_\_\_\_  
 CHECKED BY \_\_\_\_\_

PLOT DATE = 10/25/2007  
 FILE NAME = c:\p\proj\meta\489307\plan\plan09307.dgn  
 PLOT SCALE = 50.0000 / 1" = 100'  
 REFERENCE = #REF#