

SUMMARY OF QUANTITIES

*...EAP_829_7_785_7_312
 **...DIST_8_FLASHING_BEACONS_2008-1
 ***...MONROE_&_MADISON

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	***	14	3
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _ ILLINOIS FED. AID PROJECT				

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE - Y031-IF		
CODE NO	ITEM	UNIT		IL 156 MONROE CO.	IL 4 MADISON CO.	IL 003 MONROE CO.
67100100	MOBILIZATION	L SUM	1	0.3	0.3	0.4
*72000100	SIGN PANEL - TYPE 1	SQ FT	36.5	20	4.5	12
*72000200	SIGN PANEL - TYPE 2	SQ FT	112	32	16	64
*72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	5	2		3
*72400200	REMOVE SIGN PANEL ASSEMBLY - TYPE B	EACH	1		1	
*73000100	WOOD SIGN SUPPORT	FOOT	51		17	34
80500100	SERVICE INSTALLATION, TYPE A	EACH	3	2		1
81012500	CONDUIT IN TRENCH, 1 1/2" DIA., PVC	FOOT	1881	20	10	1851
81018400	CONDUIT PUSHED, 1 1/2" DIA., GALVANIZED STEEL	FOOT	180			180
81100500	CONDUIT ATTACHED TO STRUCTURE, 1 1/2" DIA., GALVANIZED STEEL	FOOT	72	16	20	36
81400700	HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	10			10
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	1881	20	10	1851
85800100	FLASHER CONTROLLER	EACH	4	2	1	1
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	770		40	730
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	2155	90		2065
87502680	TRAFFIC SIGNAL POST, ALUMINUM 14 FT.	EACH	1	1		
87502700	TRAFFIC SIGNAL POST, ALUMINUM 16 FT.	EACH	2			2
87502720	TRAFFIC SIGNAL POST, ALUMINUM 18 FT.	EACH	1	1		
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	12	6		6
88040020	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 1-SECTION, BRACKET MOUNTED	EACH	11	4	1	6
X0323153	ELECTRIC CABLE IN CONDUIT, GROUND, NO. 6 1C (GREEN)	FOOT	2258		40	2218

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		IL 156	IL_140	IL_Q03

*SPECIALTY ITEMS

FED. - 90%
 STATE - 10%