

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
778	3BR-1, 4BR-1	HARDIN	69	3

STA.	TO STA.
FED. ROAD DIST. NO. 7 ILLINOIS	FED. AID PROJECT

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	HARDIN COUNTY	
				F.A.P. 778 (IL RTE. 34)	
				SEC. 3BR-1	SEC. 4BR-1
				S.N. 035-0005	S.N. 035-0008
				HBP FUNDING 80% FEDERAL 20% STATE	HBP FUNDING 80% FEDERAL 20% STATE
				CONSTRUCTION TYPE CODE	CONSTRUCTION TYPE CODE
				X080-2A	X080-2A
25000210	SEEDING, CLASS 2A	ACRE	0.2	0.1	0.1
25000350	SEEDING, CLASS 7	ACRE	0.2	0.1	0.1
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	18	9	9
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	18	9	9
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	18	9	9
25000700	AGRICULTURAL GROUND LIMESTONE	TON	0.4	0.2	0.2
25100115	MULCH, METHOD 2	ACRE	0.4	0.2	0.2
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	40	20	20
28000400	PERIMETER EROSION BARRIER	FOOT	1,090	530	560
35650500	BASE COURSE WIDENING 10"	SQ YD	332	168	164
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	2	1	1
50300260	BRIDGE DECK GROOVING	SO YD	411	271	140
50300300	PROTECTIVE COAT	SO YD	411	271	140
50400305	PRECAST PRESTRESSED CONCRETE DECK BEAMS (17" DEPTH)	SO FT	3,491	2,333	1,158
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	5,270	3,470	1,800
50800515	BAR SPLICERS	EACH	126	82	44
50901050	STEEL RAILING, TYPE SM	FOOT	226	151	75
50901125	STEEL RAILING (TEMPORARY)	FOOT	114	76	38
51500100	NAME PLATES	EACH	2	1	1
58700300	CONCRETE SEALER	SO FT	97	6	91
59000200	EPOXY CRACK INJECTION	FOOT	36	36	0
* 63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	8	4	4
63200310	GUARDRAIL REMOVAL	FOOT	360	180	180
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	3	3
67100100	MOBILIZATION	L SUM	1	0.5	0.5

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	HARDIN COUNTY	
				F.A.P. 778 (IL RTE. 34)	
				SEC. 3BR-1	SEC. 4BR-1
				S.N. 035-0005	S.N. 035-0008
				HBP FUNDING 80% FEDERAL 20% STATE	HBP FUNDING 80% FEDERAL 20% STATE
				CONSTRUCTION TYPE CODE	CONSTRUCTION TYPE CODE
				X080-2A	X080-2A
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	2	1	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	0.5	0.5
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	0.5	0.5
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	20	10	10
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	2	1	1
70106700	TEMPORARY RUMBLE STRIP	EACH	12	6	6
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	12	6	6
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	84	44	40
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	2,146	1,156	990
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	1,003	512	491
70400100	TEMPORARY CONCRETE BARRIER	FOOT	570	300	270
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	400	200	200
70500690	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 11	EACH	4	2	2
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	2	1	1
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	2,146	1,156	990
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	8	4	4
* 78200520	BARRIER WALL MARKERS, TYPE B	EACH	6	4	2
78300100	PAVEMENT MARKING REMOVAL	SO FT	608	308	300
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1	1	0
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SO FT	97	6	91
X0325326	TEMPORARY TRAFFIC CONTROL REMOVAL	L SUM	1	1	0
X5030305	CONCRETE WEARING SURFACE, 5"	SO YD	411	271	140
XX006661	UNINTERRUPTIBLE POWER SUPPLY	EACH	2	1	1
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	4	2	2
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	4	2	2
Z0073500	TEMPORARY SUPPORT SYSTEM	L SUM	1	1	0

* SPECIALTY ITEM



10/04/07

SUMMARY OF QUANTITIES
F.A.P. ROUTE 778 (IL ROUTE 34)
SECTION 3BR-1, 4BR-1
HARDIN COUNTY

PLOT DATE * DATE
 FILE NAME * FILE#
 PLOT SCALE * SCALE
 USER NAME * USER#