

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
778	3BR-1	HARDIN	69	5
STA.		TO STA.		
FED. ROAD DIST. NO. 7		ILLINOIS	FED. AID PROJECT	

PAVEMENT MARKING SCHEDULE				
LOCATION	DESCRIPTION	SHORT-TERM PAVEMENT MARKING	PAINT PAVEMENT MARKING - LINE	TEMP PAVEMENT MARKING - LINE
		FOOT	4"	4"
STA. 802+94 TO STA. 804+77, CENTERLINE	SKIP DASH YELLOW CENTERLINE	18		
STA. 805+75.33 TO STA. 806+54.67, CENTERLINE	SKIP DASH YELLOW CENTERLINE	8		
STA. 807+53 TO STA. 809+30, CENTERLINE	SKIP DASH YELLOW CENTERLINE	18		
STA. 802+94 TO STA. 804+77, CENTERLINE	SKIP DASH AND SOLID YELLOW CENTERLINE		229	229
STA. 805+75.33 TO STA. 806+54.67, CENTERLINE	DOUBLE SOLID YELLOW CENTERLINE		159	159
STA. 807+53 TO STA. 809+30, CENTERLINE	SKIP DASH AND SOLID YELLOW CENTERLINE		221	221
STA. 804+84 TO STA. 807+46, LT	SOLID WHITE EDGE LINE		262	262
STA. 804+72.50 TO STA. 807+57.50, RT	SOLID WHITE EDGE LINE		285	285
<b>TOTALS</b>		<b>44</b>	<b>1156</b>	<b>1156</b>

GUARDRAIL REMOVAL SCHEDULE		
LOCATION	FOOT	
STRUCTURE NO. 035-0005 - NE	45*	
STRUCTURE NO. 035-0005 - NW	45*	
STRUCTURE NO. 035-0005 - SE	45*	
STRUCTURE NO. 035-0005 - SW	45*	
<b>TOTALS</b>		<b>180.0</b>

\* QUANTITY MAY VARY DEPENDING ON LAYOUT PROPOSED BY THE CONTRACTOR. SEE SHEET NO. 10 FOR DETAILS.

BASE COURSE SCHEDULE		
LOCATION	BASE COURSE WIDENING, 10"	
	50 YD	
NE QUADRANT	43	
NW QUADRANT	41	
SE QUADRANT	43	
SW QUADRANT	41	
<b>TOTALS</b>		<b>168</b>

PAVEMENT MARKERS AND REMOVAL SCHEDULE				
LOCATION	RRPM (BRIDGE)	RRPM REMOVAL		
	EACH	EACH		
STA. 806+10	1	1		
<b>TOTAL</b>			<b>1</b>	<b>1</b>

WORK ZONE AND PAVEMENT MARKING REMOVAL SCHEDULE			
LOCATION	PAVEMENT MARKING DESCRIPTION	WORK ZONE PAVEMENT MARKING REMOVAL	PAVEMENT MARKING REMOVAL
		SO. FT	SO. FT
CENTERLINE	SHORT-TERM	15	150
EDGELINES	TEMPORARY	497	
STA. 804+84 TO STA. 807+46, LT	EDGELINES		88
STA. 804+72.50 TO STA. 805+75.33, RT	EDGELINES		35
STA. 806+54.67 TO STA. 807+57.50, RT	EDGELINES		35
<b>TOTALS</b>		<b>512</b>	<b>308</b>

EROSION CONTROL SCHEDULE		
LOCATION	PERIMETER EROSION BARRIER	TEMPORARY EROSION CONTROL SEEDING (2 APPLICATIONS)
	FOOT	POUND
NE QUADRANT	130	5
NW QUADRANT	140	5
SE QUADRANT	120	5
SW QUADRANT	140	5
<b>TOTAL</b>		<b>20</b>

GUARDRAIL SCHEDULE				
LOCATION	TRAFFIC BARRIER TERMINAL TYPE 6A	GUARDRAIL MARKERS TYPE A	BARRIER WALL MARKERS, TYPE B	STEEL RAILING, TYPE SM
	EACH	EACH	EACH	FOOT
STRUCTURE NO. 035-0005 - NE	1	1		
STRUCTURE NO. 035-0005 - NW	1	1		
STRUCTURE NO. 035-0005 - SE	1	1		
STRUCTURE NO. 035-0005 - SW	1	1		
STRUCTURE NO. 035-0005 - BRIDGE			4	151
<b>TOTALS</b>		<b>4</b>	<b>4</b>	<b>151</b>

SEEDING SCHEDULE							
LOCATION	SEEDING, CLASS 2A	SEEDING, CLASS 7	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	AGRICULTURAL GROUND LIMESTONE	MULCH, METHOD 2
	ACRE	ACRE	POUND	POUND	POUND	TON	ACRE
NE QUADRANT	0.025	0.025	2.25	2.25	2.25	0.05	0.05
NW QUADRANT	0.025	0.025	2.25	2.25	2.25	0.05	0.05
SE QUADRANT	0.025	0.025	2.25	2.25	2.25	0.05	0.05
SW QUADRANT	0.025	0.025	2.25	2.25	2.25	0.05	0.05
<b>TOTALS</b>		<b>0.10</b>	<b>0.10</b>	<b>9.0</b>	<b>9.0</b>	<b>9.0</b>	<b>0.20</b>

HMA SURF REMOVAL SCHEDULE		
LOCATION	5"	
	SO. YD	
WEST ABUTMENT	6	
EAST ABUTMENT	6	
<b>TOTALS</b>		<b>12</b>

NOTE: HMA SURFACE REMOVAL IS INCLUDED IN THE COST OF REMOVAL OF EXISTING SUPERSTRUCTURE.

**SCHEDULE OF QUANTITIES**  
**F.A.P. ROUTE 778 (IL ROUTE 34)**  
**SECTION 3BR-1**  
**HARDIN COUNTY**

PLT DATE  
 FILE NAME  
 PLT SCALE  
 USER NAME

