

SUMMARY OF QUANTITIES

F. A. D. NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1476	07-00096-00-RS	DU PAGE	14	2
FED. ROAD DIST. NO. 1		ILLINOIS	FED. AID PROJECT	
CONTRACT NO. 83935				

39th STREET				CONSTRUCTION TYPE CODE		
ITEM NO.	PAY ITEM	UNIT	TOTAL BID QUANTITY	1000-2A		
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ. YD.	1816	1816		
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	23	23		
25000500	PHOSPHOROUS FERTILIZER NUTRIENT	POUND	23	23		
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	23	23		
25200110	SODDING, SALT TOLERANT	SQ. YD.	1816	1816		
25200200	SUPPLEMENTAL WATERING	UNIT	15	15		
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GAL.	945	945		
40600300	AGGREGATE (PRIME COAT)	TON	19	19		
40600825	POLYMERIZED LEVELING BINDER (MACHINE METHOD), N50,	TON	408	408		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ. YD.	730	730		
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	1843	1843		
42001300	PROTECTIVE COAT	SQ. YD.	36	36		
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ. YD.	9452	9452		
^ 44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	175	175		
44201713	CLASS D PATCHES, TYPE I, 6 INCH	SQ. YD.	240	240		
44201717	CLASS D PATCHES, TYPE II, 6 INCH	SQ. YD.	240	240		
44201721	CLASS D PATCHES, TYPE III, 6 INCH	SQ. YD.	240	240		
44201723	CLASS D PATCHES, TYPE IV, 6 INCH	SQ. YD.	225	225		
44300100	AREA REFLECTIVE CRACK CONTROL TREATMENT	SQ. YD.	9452	9452		
48101200	AGGREGATE SHOULDERS, TYPE B	TON	250	250		
^ 67100100	MOBILIZATION	L. SUM	1	1		
70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L. SUM	1	1		
70300100	SHORT - TERM PAVEMENT MARKING	FOOT	6200	6200		
* 78000100	THERMOPLASTIC PAVEMENT MARKING-LETTERS AND SYMBOLS	SQ.FT.	21	21		
* 78000200	THERMOPLASTIC PAVEMENT MARKING-LINE 4"	FOOT	6119	6119		
* 78000400	THERMOPLASTIC PAVEMENT MARKING-LINE 6"	FOOT	126	126		
* 78000600	THERMOPLASTIC PAVEMENT MARKING-LINE 12"	FOOT	48	48		
* 78000650	THERMOPLASTIC PAVEMENT MARKING-LINE 24"	FOOT	25	25		
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	68	68		
^ XX003435	PORTLAND CONCRETE CEMENT DRIVEWAY REMOVAL AND REPLACEMENT	SQ. YD.	7	7		
^ Z0018400	DRAINAGE STRUCTURES TO BE ADJUSTED	EACH	4	4		
^ XX007171	AGGREGATE SHOULDER REMOVAL	CU. YD.	1210	1210		
^ XX006947	HOT-MIX ASPHALT DRIVEWAY REMOVAL AND REPLACEMENT	SQ. YD.	203	203		

* DENOTES SPECIALTY ITEM
 ^ DENOTES SPECIAL PROVISION

VILLAGE OF DOWNERS GROVE
 PUBLIC WORKS ENGINEERING DIVISION
 5101 WALNUT AVENUE 60515 (630)434-5460

REVISIONS		39th STREET RESURFACING PROJECT SUMMARY OF QUANTITIES	
NAME	DATE		
		DATE: 1/12/07	CHECKED BY: S.A.V.
		SCALE: N.T.S.	DRAWN BY: R.W.B.
FILE NAME: C:\CADFILES\39th St\SUNOFQUANT			