

# SUMMARY OF QUANTITIES

CODE NUMBER	PAY ITEM	TOTAL BID QNTY	UNIT	CONSTRUCTION TYPE CODE		
				1000-2A	Y030-1E	Y031-1F
20101000	TEMPORARY FENCE	450	FOOT	450		
20101200	TREE ROOT PRUNING	15	EACH	15		
20200100	EARTH EXCAVATION	340	CU YD	340		
20800150	TRENCH BACKFILL	10	TON	10		
21101615	TOPSOIL FURNISH AND PLACE, 4"	1035	SQ YD	1035		
25000400	NITROGEN FERTILIZER NUTRIENT	13	POUND	13		
25000500	PHOSPHOROUS FERTILIZER NUTRIENT	13	POUND	13		
25000600	POTASSSIUM FERTILIZER NUTRIENT	13	POUND	13		
25200110	SODDING, SALT TOLERANT	1035	SQ YD	1035		
25200200	SUPPLEMENTAL WATERING	5	UNIT	5		
40600100	BITUMINOUS MATERIALS (PRIME COAT)	1526	GAL	1526		
40600300	AGGREGATE (PRIME COAT)	31	TON	31		
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0 N70	424	TON	424		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	560	SQ YD	560		
40600825	POLYMERIZED LEVELING BINDER (MACHINE METHOD), N50	831	TON	831		
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	1831	TON	1831		
42001300	PROTECTIVE COAT	800	SQ YD			
42400200	PORTLAND CONCRETE CEMENT SIDEWALK, 5"	2505	SQ FT	2505		
44000161	HOT-MIX ASPHALT SURFACE REMOVAL, 3"	14440	SQ YD	14440		
44000500	COMBINATION CURB & GUTTER REMOVAL	3406	FOOT	3406		
44000600	SIDEWALK REMOVAL	2685	SQ FT	2685		
44201737	CLASS D PATCHES, TYPE I, 8 INCH	500	SQ YD	500		
44201741	CLASS D PATCHES, TYPE II, 8 INCH	500	SQ YD	500		
44201745	CLASS D PATCHES, TYPE III, 8 INCH	500	SQ YD	500		
44201747	CLASS D PATCHES, TYPE IV, 8 INCH	500	SQ YD	500		
44300100	AREA REFLECTIVE CRACK CONTROL TREATMENT	14440	SQ YD	14440		
551A0700	STORM SEWER INSTALLATION, CLASS A, 15"	12	FOOT	12		
55100700	STORM SEWER REMOVAL 15"	6	FOOT	6		
60260300	INLETS TO BE ADJUSTED WITH NEW TYPE 1 FRAME AND OPEN LID	15	EACH	15		
60500060	REMOVING INLETS	2	EACH	2		
60603800	COMBINATION CONCRETE CURB & GUTTER B6.12	3106	FOOT	3106		
67100100	MOBILIZATION	1	L SUM	1		
70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	1	L SUM	1		
70300100	SHORT - TERM PAVEMENT MARKING	6000	FOOT	6000		
* 78000100	THERMOPLASTIC PAVEMENT MARKINGS - LETTERS & SYMBOLS	218.4	SQ FT	218.4		
* 78000200	THERMOPLASTIC PAVEMENT MARKINGS - LINE 4"	5700	FOOT	5700		
* 78000400	THERMOPLASTIC PAVEMENT MARKINGS - LINE 6"	1157	FOOT	1157		
* 78000600	THERMOPLASTIC PAVEMENT MARKINGS - LINE 12"	67	FOOT	67		
* 78000650	THERMOPLASTIC PAVEMENT MARKINGS - LINE 24"	120	FOOT	120		
* 80400200	ELECTRIC UTILITY SERVICE CONNECTION	1	L SUM		1	
* 81000600	CONDUIT TRENCH, 2" DIA GALVANIZED STEEL	100	FOOT		100	
* 81000700	CONDUIT TRENCH, 2 1/2" DIA. GALVANIZED STEEL	1478	FOOT		488	990
* 81001000	CONDUIT TRENCH, 4" DIA. GALVANIZED STEEL	275	FOOT			275
* 81001100	CONDUIT TRENCH, 5" DIA. GALVANIZED STEEL	10	FOOT			10
* 81018600	CONDUIT PUSH, 2 1/2" DIA. GALVANIZED STEEL	572	FOOT		572	
* 81400700	HANDHOLE, PORTLAND CEMENT CONCRETE	6	EACH			6
* 81400720	DOUBLE HANDHOLE, PORTLAND CEMENT CONCRETE	1	EACH			1
* 81700335	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE RHW) 3-1/C NO. 6	200	FOOT		200	
* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	5029	FOOT		4498	531
* 82102250	LUMINARE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	36	EACH		36	
* 82500530	LIGHTING CONTROLLER TYPE CB-RCS 100 AMP - 240VOLT	1	EACH		1	

\* DENOTES SPECIALTY ITEM  
^ DENOTES SPECIAL PROVISION

REVISIONS		WOODWARD AVENUE IMPROVEMENTS SUMMARY OF QUANTITIES	
NAME	DATE	DATE: 2/02/07	CHECKED BY: S.A.V.
		SCALE: N.T.S.	DRAWN BY: R.W.B.
		FILE NAME: C:\CADFILES\WOODWARD\SUMOFQUANT	

VILLAGE OF DOWNERS GROVE  
PUBLIC WORKS ENGINEERING DIVISION

5101 WALNUT AVENUE 60515 (630)434-5460