

F.A.J. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3869	07-00009-00-RS	McHENRY	14	3
STA.		TO STA.		
FED. ROAD DIST. NO	ILLINOIS	FED AID PROJECT		
C-91-340-07		M-8003 (840)		

CONTRACT: 83979

SUMMARY OF QUANTITIES

ITEM NO.	PAY ITEM	UNIT	I000-2A TOTAL
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	3643
40600300	AGGREGATE (PRIME COAT)	TON	73
40600400	MIXTURE FOR CRACKS JOINTS AND FLANGWAYS	TON	15
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1447
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	159
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D" N50	TON	1861
44000158	HOT-MIX ASPHALT SURFACE REMOVAL 2 1/4"	SQ YD	257
44000161	HOT-MIX ASPHALT SURFACE REMOVAL 3"	SQ YD	918
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	678
44201713	CLASS D PATCHES, TYPE I, 6-INCH	SQ YD	52
44201717	CLASS D PATCHES, TYPE II, 6-INCH	SQ YD	481
44201721	CLASS D PATCHES, TYPE III, 6-INCH	SQ YD	507
44201723	CLASS D PATCHES, TYPE IV, 6-INCH	SQ YD	1856
48101200	AGGREGATE SHOULDERS, TYPE B	TON	700
67100100	MOBILIZATION	LSUM	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	LSUM	1
70100455	TRAFFIC CONTROL AND PROTECTION, STANDARD 701206	LSUM	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	LSUM	1
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	25000
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	48
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	660


• INDICATES SPECIALTY ITEM

SCHEDULE OF MATERIALS

HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT

LOCATION	AREA (SQ YD)
HALIGUS ROAD - SOUTH PROJECT LIMITS	120
LAKEWOOD ROAD	165
CONLEY ROAD	125
BONNIE DRIVE	50
WOODLAND HILLS DRIVE (STA 54+90)	290
WOODLAND HILLS DRIVE (STA 74+04)	290
BALLARD ROAD (EAST OF HALIGUS)	50
BALLARD ROAD (WEST OF HALIGUS)	50
HALIGUS ROAD - NORTH PROJECT LIMITS	80
DRIVEWAYS	227
TOTAL	1,447

DRAWN BY: BAXTER & WOODMAN, INC.
 STATE OF ILLINOIS - PROFESSIONAL DESIGN FIRM
 LICENSE NO. 194-00081 - EXPIRES 12/31/2009
 527-Hm 11/25/2007 9:50:52 AM I:\PROJECTS\070489-HALIGUS STP-40-Design\070489-500.dwg



REVISIONS	
NAME	DATE
MWP	10/2/07
MWP	11/1/07

VILLAGE OF LAKEWOOD
SUMMARY OF QUANTITIES AND SCHEDULE OF MATERIALS
 PROJECT NO.: 070489 DESIGNED BY: (DJS)
 SCALE: NONE DRAWN BY: (RKM)
 DATE: 08/07/07 CHECKED BY: (MWP)