

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3783	00-00080-00FP	COOK	49	4
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
CONTRACT NO. 83988				

CODE NO.		UNIT	TOTAL QUANTITY	SUMMARY OF QUANTITIES				
				ROADWAY 70% FED 30% VILLAGE J000-2A	LIGHTING ADJUSTMENTS 70% FED 30% VILLAGE Y030-1E	VILLAGE LIGHTING 100% VILLAGE Y030-1E	VILLAGE WATER MAIN 100% VILLAGE Y060	SANITARY SEWER REPAIR 100% VILLAGE Y060
60200205	CATCH BASINS, TYPE A, 4' DIAMETER, TYPE 1 FRAME CLOSED LID	EACH	2	2				
60200305	CATCH BASINS, TYPE A, 4' DIAMETER, TYPE 3 FRAME AND GRATE	EACH	8	8				
60201330	CATCH BASINS, TYPE A, 4' DIAMETER, TYPE 23 FRAME AND GRATE	EACH	11	11				
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	5	5				
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	5	5				
60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	4	4				
60228110	MANHOLES, SANITARY, 4' DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	8	8				
60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	5	5				
60237460	INLETS, TYPE A, TYPE 23 FRAME AND GRATE	EACH	3	3				
60250200	CATCH BASINS TO BE ADJUSTED	EACH	1	1				
60250400	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, OPEN LID	EACH	1	1				
60250500	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	1	1				
60255500	MANHOLES TO BE ADJUSTED	EACH	1	1				
60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	2	2				
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	2	2				
60258200	MANHOLES TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	7	7				
60265700	VALVE VAULTS TO BE ADJUSTED	EACH	1	1				
60265900	VALVE VAULTS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	2	2				
60266100	VALVE VAULTS TO BE RECONSTRUCTED	EACH	2	2				
60266300	VALVE VAULTS TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	6	6				
60266600	VALVE BOXES TO BE ADJUSTED	EACH	1	1				
60500040	REMOVING MANHOLES	EACH	11	11				
60500050	REMOVING CATCH BASINS	EACH	1	1				
60500060	REMOVING INLETS	EACH	2	2				
60500105	FILLING MANHOLES	EACH	2	2				
60500205	FILLING CATCH BASINS	EACH	10	10				
60500305	FILLING INLETS	EACH	6	6				
60500405	FILLING VALVE VAULTS	EACH	4	4				
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	2,275	2,275				
60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	8,949	8,949				
66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	600	600				
66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1				
66900500	BETX SOIL ANALYSIS	EACH	1	1				
66900530	SOIL DISPOSAL ANALYSIS	EACH	1	1				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	7	7				
67100100	MOBILIZATION	L SUM	1	1				
70102620	TRAFFIC CONTROL AND PROTECTION STANDARD 701501	L SUM	1	1				
70102640	TRAFFIC CONTROL AND PROTECTION STANDARD 701801	L SUM	1	1				
78008200	POLYUREA PAVEMENT MARKING TYPE I - LETTERS & SYMBOLS	SQ FT	36.4	36.4				
78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	7,124	7,124				
78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	126	126				
78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	792	792				
78008270	POLYUREA PAVEMENT MARKING TYPE I - LINE 24"	FOOT	101	101				

* - DENOTES SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.U. 3783
BURLINGTON AVENUE

SUMMARY OF QUANTITIES

SCALE: NTS
DATE: 8/15/07

DRAWN BY SMP
CHECKED BY BDH