

F.A.P. NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
315		ILLINOIS	329	29
STA.	TO STA.			
FED. ROAD DIST. NO. 4 ILLINOIS FED. AID PROJECT				

*109W-1,RS-2;110W,RS-1

RIPRAP SCHEDULE

LOCATION	STONE DUMPED RIPRAP CLASS A3	STONE DUMPED RIPRAP CLASS A4	STONE DUMPED RIPRAP CLASS A5	STONE DUMPED RIPRAP CLASS A6	FILTER FABRIC
	TON	TON	TON	TON	SO. YD.
US 136					
LT. STA. 499+00 TO STA. 507+00					
LT. STA. 507+00 TO STA. 521+00	33.56				
LT. STA. 521+00 TO STA. 535+00	210.38				
LT. STA. 535+00 TO STA. 547+00	298.48	333.20			422.29
LT. STA. 547+00 TO STA. 561+00	4.20				
LT. STA. 561+00 TO STA. 575+00	1.05				
LT. STA. 575+00 TO STA. 587+00			746.63		773.70
LT. STA. 587+00 TO STA. 602+00	24.61		150.06		189.37
LT. STA. 602+00 TO STA. 616+00	735.21				
LT. STA. 616+00 TO STA. 630+00	123.19		54.57		45.37
LT. STA. 630+00 TO STA. 645+00		351.92	364.82		543.20
LT. STA. 645+00 TO STA. 658+00		280.15			321.17
CULVERT OUTLET					
STA. 1+00 TO STA. 2+87			567.50		471.98
LT. STA. TOTALS	1430.68	965.27	1,883.58		2767.08
US 136					
RT. STA. 499+00 TO STA. 507+00					
RT. STA. 507+00 TO STA. 521+00					
RT. STA. 521+00 TO STA. 535+00					
RT. STA. 535+00 TO STA. 547+00		388.97			334.05
RT. STA. 547+00 TO STA. 561+00					
RT. STA. 561+00 TO STA. 575+00	3.08				
RT. STA. 575+00 TO STA. 587+00			590.85	62.50	538.87
RT. STA. 587+00 TO STA. 602+00	56.47	376.70	86.24		517.10
RT. STA. 602+00 TO STA. 616+00	278.46	151.37			82.61
RT. STA. 616+00 TO STA. 630+00	98.71				
RT. STA. 630+00 TO STA. 645+00		87.33			94.44
RT. STA. 645+00 TO STA. 658+00		686.27			722.48
RT. STA. TOTALS	436.72	1,690.64	677.09	62.50	2289.55
GRAND TOTALS	1867	2,656	2,561	63	5,057

CONCRETE GUTTER

LOCATION	TYPE A (MOD)	OUTLET (SPCL) (TO STA.)	INLET (SPCL) (TO STA.)
	FOOT	EACH	EACH
LT. STA. 578+67.30			1 TO STA. 578+55.00
LT. STA. 582+78.85	411.6	1 TO STA. 583+14.85	
LT. STA. 586+95.95			1 TO STA. 586+83.95
LT. STA. 596+00.00	904.1	1 TO STA. 596+36.90	
LT. STA. 607+00.00		1 TO STA. 606+64.00	
LT. STA. 612+51.00	551.0		1 TO STA. 612+63.00
LT. STA. 651+43.50			1 TO STA. 651+31.50
LT. STA. 655+00.00	356.5	1 TO STA. 655+36.90	
RT. STA. 533+33.85			
RT. STA. 537+85.80	452.0	1 TO STA. 538+21.80	
RT. STA. 578+67.30			1 TO STA. 578+55.00
RT. STA. 583+17.95	450.7	1 TO STA. 583+53.95	
RT. STA. 586+95.95			1 TO STA. 586+83.95
RT. STA. 596+00.00	904.1	1 TO STA. 596+36.90	
RT. STA. 607+00.00		1 TO STA. 606+64.00	
RT. STA. 612+51.00	551.0		1 TO STA. 612+63.00
RT. STA. 642+30.58			1 TO STA. 642+18.58
RT. STA. 652+00.00	969.4	1 TO STA. 652+36.9	
TOTAL	5,550	9	8

CONCRETE THRUST BLOCKS (SPECIAL)

LOCATION	EACH
LT. STA. 641+33.80	1
TOTAL	1

CONCRETE COLLARS

LOCATION	CLASS SI CONCRETE	*REINFORCEMENT BARS, EPOXY COATED	*EXPANSION BOLTS 3/4"
	CU. YD.	POUND	EACH
LT. STA. 613+37.60	0.27	21.0	8
LT. STA. 618+84.60	0.27	21.0	8
LT. STA. 641+33.80 (SEE DETAIL)	0.55	42.0	16
RT. STA. 613+37.60	0.27	21.0	8
RT. STA. 618+84.60	0.27	21.0	8
RT. STA. 641+33.80	0.27	21.0	8
TOTAL	1.9	147	56

*SEE STRUCTURE PLANS FOR ADDITIONAL QUANTITY
CLASS SI CONCRETE WILL BE PAID FOR AS CONCRETE COLLAR

SEDIMENT BASIN

LOCATION	EACH
BEGIN RT. STA. 572+65	1
(SEE COMMITMENTS)	
TOTAL	1

TEMPORARY SOIL RETENTION SYSTEM

LOCATION	SO. FT.
STA. 539+54.90	524
STA. 586+00.00	810
STA. 601+79.18	1042
TOTAL	2,376

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT. NONE
HORIZ. DATE 03/02/2007

DRAWN BY CEM
CHECKED BY