

F.A.R. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
315		EUILTON	324	29
STA.	TO STA.			
FED. ROAD DIST. NO. 4 ILLINOIS FED. AID PROJECT				

*109W-1,RS-2;110W,RS-1

LOCATION	EPOXY AND TEMPORARY PAINT PAVEMENT MARKING						SHORT-TERM PAVEMENT MARKING	WORK ZONE PAVEMENT MARKING REMOVAL
	24 INCH LINE	4 INCH LINE						
	STOP BARS (WHITE)	LT EDGE OF PVT SOLID (WHITE)	RT EDGE OF PVT SOLID (WHITE)	CENTERLINE		RT SOLID (YELLOW)		
STATION TO STATION	FOOT	FOOT	FOOT	LT SOLID (YELLOW)	SKIP - DASH (YELLOW)	FOOT	FOOT	SO. FT.
502+20 - 522+50		2030	2030		507.5		203	67.67
522+50 - 532+90		1040	1040		260	1040	104	34.67
532+90 - 542+70		980	980	980		980	98	32.67
542+70 - 550+15		745	745	745	186.25		74.5	24.83
550+15 - 552+40		225	225	225		225	22.5	7.50
552+40 - 565+50		1310	1310		327.5	1310	131	43.67
565+50 - 578+00		1250	1250	1250		1250	125	41.67
578+00 - 588+20		1006	1006	1006	250		102	34.00
588+20 - 602+75		1455	1455		363.75		145.5	48.50
602+75 - 612+75		1000	1000		250	1000	100	33.33
612+75 - 622+00		925	925	925		925	92.5	30.83
622+00 - 629+00		700	700		175	700	70	23.33
629+00 - 637+10		810	810	810		810	81	27.00
637+10 - 645+50		840	840	840	210		84	28.00
645+50 - 658+30		1280	1280		320		128	42.67
BRANSON SCHOOL RD	15							
BEADLES ROAD	12							
CARLS LANE	15							
MILE LOAD ROAD	20							
SUBTOTALS	62	15,596	15,596	6,781	2,850	8,240	1,561	520
TOTAL 4 INCH YELLOW				17,871				
TOTAL 4 INCH WHITE		31,192						
X 3 APPLICATIONS							X 3	
TOTALS	62			49,063			4,683	520

RAISED REFLECTIVE PAVEMENT MARKER	
LOCATION	EACH
STA. 502+50 TO STA. 658+00	195
TOTAL	195

RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	
LOCATION	EACH
STA. 502+50 TO STA. 658+00	165
TOTAL	165

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES PAVEMENT MARKINGS

SCALE: VERT. NONE
 HORIZ. DATE 03/02/2007

DRAWN BY CEM
 CHECKED BY