


**PLAN**  
(D'=Designated Skew Angle)



**ELEVATION**

**DIMENSION 'E'**

GRADE	'D'=25°		'D'=30°	
	UPGRADE END	DOWNGRADE END	UPGRADE END	DOWNGRADE END
0%	2 1/2"	2 1/2"	2 3/8"	2 3/8"
Over 0% to 1%	2 1/8"	2 7/8"	2"	2 1/8"
Over 1% to 2%	1 3/8"	3 5/8"	1"	3 3/4"
Over 2% to 3%	5/8"	4 3/8"	1/2"	4 5/8"
Over 3% to 4%	0"	5 1/8"		

**NOTES**


- The Backwall and the portion of the Wingwalls above the bonded construction joint shall be cast against the in-place beam.
- Reinforcement bars shall conform to the requirements of A.A.S.H.T.O. M-31 or M-322, Grade 60.
- Space reinforcement in cap to miss anchor bolts.

**MAXIMUM PILE LOADS**


SPAN	TONS
40'	34
50'	38
60'	43

**DESIGN STRESSES**


f'c = 3,500 psi  
fy = 60,000 psi




**SECTION THRU ABUTMENT**  
(At Right Angles)



**BAR s**



**BAR u**



**BAR h1**

**BILL OF MATERIAL FOR ONE ABUTMENT**

Bar	No.	Size	Length	Shape
h	16	#4	5'-0"	—
h1	4	#4	5'-3"	—
h2	6	#4	29'-2"	—
p	10	#7	29'-2"	—
s	30	#4	9'-5"	□
u	8	#6	12'-1"	□
v	8	#4	3'-2"	—
v1	8	#4	4'-2"	—
v2	58	#4	3'-11"	—
Concrete Structures			10.7 Cu. Yds.	
Reinforcement Bars			1310 Lb.	

**P.P.C. DECK BEAMS  
PILE BENT ABUTMENT**

24' RDWY. 27" BMS. 'D'=25° OR 30°

STANDARD CA-2427-30

Illinois Department of Transportation  
PASSED APRIL 4, 2005  
Thames S. Nimmagadda  
Engineer of Bridge Design  
APPROVED APRIL 4, 2005  
Ralph E. Anderson  
Engineer of Bridges and Structures