

CODED PAYITEM	DESCRIPTION	UNIT	TOTAL QUANTITY	L530		L400	
				HSIP 90% FEDERAL 10% LOCAL I000-1A	80% FEDERAL 20% LOCAL I000-1A	HSIP 90% FEDERAL 10% LOCAL I000-1A	80% FEDERAL 20% LOCAL I000-1A
20200100	EARTH EXCAVATION	CU YD	141	63	78		
20400800	FURNISHED EXCAVATION	CU YD	95	43	52		
20800150	TRENCH BACKFILL	CU YD	109	49	60		
25000100	SEEDING, CLASS 1	ACRE	0.16	0.07	0.09		
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	16	16			
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	16	16			
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	16	16			
25000700	AGRICULTURAL GROUND LIMESTONE	TON	0.36	0.36			
25100115	MULCH, METHOD 2	ACRE	0.16	0.16			
25200100	SODDING	SO YD	88	88			
28000255	TEMPORARY EROSION CONTROL SEEDING	ACRE	0.16	0.16			
28000400	PERIMETER EROSION BARRIER	FOOT	651	293	358		
28000500	INLET AND PIPE PROTECTION	EACH	16	7	9		
31100100	SUB-BASE GRANULAR MATERIAL, TYPE A	TON	418	188	230		
35501450	HOT-MIX ASPHALT BASE COURSE	TON	268	121	147		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	3	1	2		
40600645	LEVELING BINDER (MACHINE METHOD), N90	TON	81	36	45		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	367	165	202		
40603090	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	362	163	199		
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	190	86	104		
42000210	PORTLAND CEMENT CONCRETE PAVEMENT 7 1/2"	SQ YD	230	104	126		
42001200	PAVEMENT FABRIC	SQ YD	230	104	126		
42001300	PROTECTIVE COAT	SQ YD	299	135	164		
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	24	11	13		
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	3202	1441	1761		
42400800	DETECTABLE WARNINGS	SQ FT	160	72	88		
44000100	PAVEMENT REMOVAL	SQ YD	512	230	282		
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	155	70	85		
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	16	16			
44000300	CURB REMOVAL	FOOT	18	18			
44000500	COMBINATION CURB & GUTTER REMOVAL	FOOT	568	256	312		
44000600	SIDEWALK REMOVAL	SQ FT	1277	575	702		
44004250	PAVED SHOULDER REMOVAL	SQ YD	279	126	153		
44201976	CLASS D PATCHES, TYPE II	SQ YD	48	22	26		

CODED PAYITEM	DESCRIPTION	UNIT	TOTAL QUANTITY	L530		L400	
				HSIP 90% FEDERAL 10% LOCAL I000-1A	80% FEDERAL 20% LOCAL I000-1A	HSIP 90% FEDERAL 10% LOCAL I000-1A	80% FEDERAL 20% LOCAL I000-1A
48203100	HOT-MIX ASPHALT SHOULDERS	TON	37	17	20		
50105220	PIPE CULVERT REMOVAL	FOOT	158	71	87		
542A0220	PIPE CULVERTS, CLASS A, TYPE 1 15"	FOOT	183	82	101		
542A0223	PIPE CULVERTS, CLASS A, TYPE 1 18"	FOOT	82	37	45		
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	1	1			
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	1	1			
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	1	1			
60218500	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 3 FRAME AND GRATE	EACH	1	1			
60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	3	1	2		
60240220	INLETS, TYPE B, TYPE 3 FRAME AND GRATE	EACH	4	2	2		
60500040	REMOVING MANHOLES	EACH	1	1			
60500060	REMOVING INLETS	EACH	4	2	2		
60600105	CONCRETE CURB	FOOT	69	31	38		
60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	612	275	337		
60606800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-9.18	FOOT	125	56	69		
60607200	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-9.18 (SPECIAL)	FOOT	113	51	62		
60608250	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-2.06	FOOT	201	90	111		
60619200	CONCRETE MEDIAN, TYPE SB-6.06	SQ FT	1400	630	770		
67100100	MOBILIZATION	L SUM	1		1		
70103816	TRAFFIC CONTROL SURVEILLANCE	CAL MO	6	3	3		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1459	657	802		
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	42	19	23		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	1246	561	685		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	935	421	514		
72000100	SIGN PANEL - TYPE 1	SQ FT	188	85	103		
73000100	WOOD SIGN SUPPORT	FOOT	459	207	252		
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	136	61	75		
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	777	350	427		
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	88	88			

\* SPECIALTY ITEMS DESIGNATION

CITY OF O'FALLON, ILLINOIS

**SUMMARY OF QUANTITIES**  
 SHEET 1 OF 2

SCALE: N/A  
 DATE: 10/05/06

DRAWN BY: SSM  
 CHECKED BY: SRD