PAVING

LOCATION	SIDE	PAVEMENT REMOVAL	PORTLAND CEMENT CONCRETE PAVEMENT 7 1/2"	PAVEMENT FABRIC	HOT-MIX ASPHALT BASE COURSE	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	BITUMINOUS MATERIALS (PRIME COAT)	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	LEVELING BINDER (MACHINE METHOD), N90	SUB-BASE GRANULAR MATERIAL, TYPE A	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH
		SQ YD	SQ YD	SQ YD	TON	TON	TON	TON	TON	TON	SQ YD	SQ YD
28+18.52 TO 29+68.00 (STATE STREET)	LT/RT	30					0.8	54	23		84	97
28+18.52 (STATE STREET) TO 38+99.59 (GREENMOUNT)	SW QUADRANT				51							
28+43.39 TO 31+25.00 (STATE STREET)	LT/RT					254						
29+62.95 (STATE STREET) TO 40+89.79 (OBERNUEFEMANN)	NW QUADRANT				69							
29+68.00 TO 30+32.00 (STATE STREET)	LT/RT									331		
29+68.67 TO 30+31.33 (STATE STREET)	ROUNDABOUT	357	230	230								
30+32.00 TO 31+76.54 (STATE STREET)	LT/RT	30					0.8	53	23		80	58
39+00.00 TO 39+75.00 (GREENMOUNT)	LT/RT	31				48	0.5	33	14		110	
39+06.95 (GREENMOUNT) TO 31+66.22 (STATE STREET)	SE QUADRANT				78							
40+25.00 TO 41+73.95 (OBERNUEFEMANN)	LT/RT	64				60	0.7	50	21		93	
41+24.46 (OBERNUEFEMANN) TO 31+76.54 (STATE STREET)	NE QUADRANT				70							
	TOTAL:	512	230	230	268	362	3	190	81	331*	367	155

*NOT A TOTAL QUANTITY

CURB AND GUTTER

LOCATION	SIDE	CURB REMOVAL	COMBINATION CURB AND GUTTER REMOVAL	PROTECTIVE COAT	CONCRETE CURB	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-9.18	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-9.18 (SPECIAL)	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-2.06	SUB-BASE GRANULAR MATERIAL, TYPE A	CONCRETE MEDIAN, TYPE SB-6.06
		FOOT	FOOT	SQ YD	FOOT	FOOT	FOOT	FOOT	FOOT	TON	SQ FT
28+74.02 TO 29+02.56 (STATE STREET)	RT	18			30						
28+74.02 (STATE STREET) TO 38+99.61 (GREENMOUNT)	SW QUADRANT		92	27		159					
28+85.55 (STATE STREET) TO 40+75.08 (OBERNUEFEMANN)	NW QUADRANT		184	21			125				
29+00.00 TO 29+50.00 (STATE STREET)	CL			30						17	273
29+14.48 (STATE STREET) TO 29+43.81 (STATE STREET)	LT				39						
29+68.00 TO 30+32.00 (STATE STREET)	ROUNDABOUT			11							
29+82.00 TO 30+18.00 (STATE STREET)	ROUNDABOUT			19					201		
30+50.00 TO 31+00.00 (STATE STREET)	CL			30						17	273
39+00.00 TO 39+50.00 (GREENMOUNT)	CL			31						17	277
39+00.46 (GREENMOUNT) TO 31+07.29 (STATE STREET)	SE QUADRANT		105	15		146		113			
40+50.00TO 41+73.95 (OBERNUEFEMANN)	CL			64						36	577
40+75.08 TO 41+73.95 (OBERNUEFEMANN)	LT			15		89					
41+73.95 (OBERNUEFEMANN) TO 31+05.78 (STATE STREET)	NE QUADRANT		187	36		218					
	TOTAL:	18	568	299	69	612	125	113	201	87*	1400

* NOT A TOTAL QUANTITY

CITY OF O'FALLON, ILLINOIS

SCHEDULE OF QUANTITIES

SHEET 1 OF 6

SCALE: N/A | DRAWN BY: KMO
DATE: 10/05/06 | CHECKED BY: SSM