

TEMPORARY PAVEMENT MARKING						
LOCATION	WORK ZONE PAVEMENT MARKING REMOVAL		SHORT TERM PAVEMENT MARKING	TEMPORARY PAVEMENT MARKING		
	SHORT TERM	TEMP.		LINE 4" SOLID WHITE	LINE 4" SOLID YELLOW	LETTERS AND SYMBOLS
	SQ FT	SQ FT	FOOT	FOOT	FOOT	SQ FT
28+18.54 (STATE STREET) TO 38+99.59 (GREENMOUNT)	71.72	71.72	217.33	217.33		
28+18.54 (STATE STREET) TO 41+73.79 (OBERNUEFEMANN)	97.49	97.49	295.43	295.43		
29+43.14 (STATE STREET)	16.83	10.13	51.00			10.13
29+64.71 TO 30+35.29 (STATE STREET)	73.17	73.17	221.73		221.73	
30+57.01 (STATE STREET)	16.83	10.13	51.00			10.13
38+99.59 (GREENMOUNT) TO 31+76.51 (STATE STREET)	72.34	72.34	219.20	219.20		
39+42.99 (GREENMOUNT)	19.64	11.81	59.50			11.81
40+57.26 (OBERNUEFEMANN)	16.83	10.13	51.00			10.13
41+73.79 (OBERNUEFEMANN) TO 31+76.51 (STATE STREET)	96.51	96.51	292.45	292.45		
	481.36	453.43				
TOTAL:	935		1459	1024	222	42

PAVEMENT MARKING									
LOCATION	LENGTH	THERMOPLASTIC PAVEMENT MARKING						PRISMATIC CURB REFLECTOR	DESCRIPTION
		LINE 4"	LINE 4"	LINE 12"	LINE 12"	LINE 24"	LETTERS AND SYMBOLS		
		SOLID WHITE	SOLID YELLOW	SOLID YELLOW	3' -3' DASH WHITE	SOLID WHITE	SQ FT		
	FEET	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	EACH	
STATE STREET									
28+18.52 TO 28+85.58	67.0	67							SOLID WHITE EDGE LINE
28+18.52 TO 28+64.24	45.7		91						SOLID DOUBLE YELLOW CL
28+64.24 TO 29+00.00	72.8		146						SOLID DOUBLE YELLOW
28+64.24 TO 29+00.00	8.1			8					SOLID YELLOW DIAG.
29+00.00 TO 29+50.00								17	
29+25.00	90.0					90			SOLID WHITE CROSSWALK
29+43.14							18		WHITE YIELD BAR
29+50.55 TO 29+65.45	37.3				19				WHITE 3' -3' DASH
29+64.55 TO 29+92.49	31.9				16				WHITE 3' -3' DASH
30+04.02 TO 30+33.74	33.0				17				WHITE 3' -3' DASH
30+35.13 TO 30+49.45	32.2				16				WHITE 3' -3' DASH
30+50.00 TO 31+00.00								17	
30+57.01							18		WHITE YIELD BAR
30+75.00	90.0					90			SOLID WHITE CROSSWALK
31+00.00 TO 31+36.00	73.1		146						SOLID DOUBLE YELLOW
31+00.00 TO 31+36.00	8.4			8					SOLID YELLOW DIAG.
31+05.78 TO 31+76.54	70.8	71							SOLID WHITE EDGE LINE
31+07.23 TO 31.76.54	69.4	69							SOLID WHITE EDGE LINE
31+36.00 TO 31+76.54	40.5		81						SOLID DOUBLE YELLOW CL
GREENMOUNT									
38+74.07 TO 39+00.00	53.1		106						SOLID DOUBLE YELLOW
38+74.07 TO 39+00.00	4.4			4					SOLID YELLOW DIAG.
39+00.00 TO 39+50.00								17	
39+25.00	100.0					100			SOLID WHITE CROSSWALK
39+42.99							21		WHITE YIELD BAR
OBERNUEFEMANN									
40+50.00 TO 41+73.98								17	
40+57.26							18		WHITE YIELD BAR
40+75.00	90.0					90			SOLID WHITE CROSSWALK
40+98.42	12.0					12			WHITE STOP BAR
41+24.69							3.6		WHITE RAILROAD "R"
41+24.69							3.6		WHITE RAILROAD "R"
41+24.69							54.0		WHITE RAILROAD "X"
41+48.96	12.0					12			WHITE STOP BAR
TOTAL:		207	570	20	68	394	136	68	

CITY OF O'FALLON, ILLINOIS  
**SCHEDULE OF QUANTITIES**  
 SHEET 5 OF 6  
 SCALE: N/A  
 DATE: 10/05/06  
 DRAWN BY: KMO  
 CHECKED BY: SSM