## If you plan to submit a bid directly to the Department of Transportation

## **PREQUALIFICATION**

Any contractor who desires to become pre-qualified to bid on work advertised by IDOT must submit the properly completed pre-qualification forms to the Bureau of Construction no later that 4:30 p.m. prevailing time twenty-one days prior to the letting of interest. This pre-qualification requirement applies to first time contractors, contractors renewing expired ratings, contractors maintaining continuous pre-qualification or contractors requesting revised ratings. To be eligible to bid, existing pre-qualification ratings must be effective through the date of letting.

## **REQUESTS FOR AUTHORIZATION TO BID**

Contractors downloading and/or ordering CD-ROM's and are wanting to bid on items included in a particular letting must submit the properly completed "Request for Authorization to Bid/or Not For Bid Status" (BDE 124INT) and the ORIGINAL, signed and notarized, "Affidavit of Availability" (BC 57) to the proper office no later than 4:30 p.m. prevailing time, three (3) days prior to the letting date.

## WHO CAN BID?

Bids will be accepted from only those companies that request and receive written **Authorization to Bid** from IDOT's Central Bureau of Construction.

WHAT CONSTITUTES WRITTEN AUTHORIZATION TO BID? When a prospective prime bidder submits a "Request for Authorization to Bid/or Not For Bid Status" (BDE 124INT) he/she must indicate at that time which items are being requested For Bidding purposes. Only those items requested For Bidding will be analyzed. After the request has been analyzed, the bidder will be issued a Proposal Denial and/or Authorization Form, approved by the Central Bureau of Construction, that indicates which items have been approved For Bidding. If Authorization to Bid cannot be approved, the Proposal Denial and/or Authorization Form will indicate the reason for denial.

**ABOUT AUTHORIZATION TO BID:** Firms that have not received an authorization form within a reasonable time of complete and correct original document submittal should contact the department as to status. This is critical in the week before the letting. These documents must be received three days before the letting date. Firms unsure as to authorization status should call the Prequalification Section of the Bureau of Construction at the number listed at the end of these instructions.

**ADDENDA AND REVISIONS:** It is the contractor's responsibility to determine which, if any, addenda or revisions pertain to any project they may be bidding. Failure to incorporate all relevant addenda or revisions may cause the bid to be declared unacceptable.

Each addendum will be placed with the contract number. Addenda and revisions will also be placed on the Addendum/Revision Checklist and each subscription service subscriber will be notified by e-mail of each addendum and revision issued.

The Internet is the Department's primary way of doing business. The subscription server e-mails are an added courtesy the Department provides. It is suggested that bidder check IDOT's website <a href="http://www.dot.il.gov/desenv/delett.html">http://www.dot.il.gov/desenv/delett.html</a> before submitting final bid information.

## IDOT is not responsible for any e-mail related failures.

Addenda Questions may be directed to the Contracts Office at (217)782-7806 or D&Econtracts@dot.il.gov

Technical Questions about downloading these files may be directed to Tim Garman (217)524-1642 or garmantr@dot.il.gov.

**WHAT MUST BE INCLUDED WHEN BIDS ARE SUBMITTED?**: Bidders need not return the entire proposal when bids are submitted. That portion of the proposal that must be returned includes the following:

- 1. All documents from the Proposal Cover Sheet through the Proposal Bid Bond
- 2. Other special documentation and/or information that may be required by the contract special provisions

All proposal documents, including Proposal Guaranty Checks or Proposal Bid Bonds, should be stapled together to prevent loss when bids are processed by IDOT personnel.

**ABOUT SUBMITTING BIDS**: It is recommended that bidders deliver bids in person to insure they arrive at the proper location prior to the time specified for the receipt of bids. Any bid received at the place of letting after the time specified will not be accepted.

## WHO SHOULD BE CALLED IF ASSISTANCE IS NEEDED?

Questions Regarding	Call
Prequalification and/or Authorization to Bid	(217)782-3413
Preparation and submittal of bids	(217)782-7806
Mailing of plans and proposals	(217)782-7806
Electronic plans and proposals	(217)524-1642

## ADDENDUMS AND REVISIONS TO THE PROPOSAL FORMS

Planholders should verify that they have received and incorporated the addendum and/or revision prior to submitting their bid. Failure by the bidder to include an addendum could result in a bid being rejected as irregular.

## 119

1121 91111 111111 212	
Proposal Submitted By	
Name	
Address	
City	

## Letting January 18, 2008

## NOTICE TO PROSPECTIVE BIDDERS

This proposal can be used for bidding purposes by only those companies that request and receive written AUTHORIZATION TO BID from IDOT's Central Bureau of Construction. (SEE INSTRUCTIONS ON THE INSIDE OF COVER)

## Notice To Bidders, Specifications, Proposal, Contract and Contract Bond



Springfield, Illinois 62764

Contract No. 97324
MADISON County
Section 06-00056-01-WR (Highland)
Route FAU 8852 (Poplar Street)
Project CMM-M-5011(246)
District 8 Construction Funds

PLEASE MARK THE APPROPRIATE BOX BELOW:	
☐ A <u>Bid</u> <u>Bond</u> is included.	
☐ A <u>Cashier's Check</u> or a <u>Certified Check</u> is included	
	_

Prepared by

F

Checked by

(Printed by authority of the State of Illinois)

BIDDERS NEED NOT RETURN THE ENTIRE PROPOSAL (See instructions inside front cover)

## **INSTRUCTIONS**

**ABOUT IDOT PROPOSALS**: All proposals issued by IDOT are potential bidding proposals. Each proposal contains all Certifications and Affidavits, a Proposal Signature Sheet and a Proposal Bid Bond required for Prime Contractors to submit a bid after written **Authorization to Bid** has been issued by IDOT's Central Bureau of Construction.

**WHO CAN BID**?: Bids will be accepted from only those companies that request and receive written **Authorization to Bid** from IDOT's Central Bureau of Construction. To request authorization, a potential bidder <u>must complete and submit Part B of the Request for Authorization to Bid/or Not For Bid Status form (BDE 124 INT) and submit an original Affidavit of Availability (BC 57).</u>

WHAT CONSTITUTES WRITTEN AUTHORIZATION TO BID?: When a prospective prime bidder submits a "Request for Proposal Forms and Plans" he/she must indicate at that time which items are being requested For Bidding purposes. Only those items requested For Bidding will be analyzed. After the request has been analyzed, the bidder will be issued a Proposal Denial and/or Authorization Form, approved by the Central Bureau of Construction, that indicates which items have been approved For Bidding. If Authorization to Bid cannot be approved, the Proposal Denial and/or Authorization Form will indicate the reason for denial. If a contractor has requested to bid but has not received a Proposal Denial and/or Authorization Form, they should contact the Central Bureau of Construction in advance of the letting date.

WHAT MUST BE INCLUDED WHEN BIDS ARE SUBMITTED?: Bidders need not return the entire proposal when bids are submitted. That portion of the proposal that must be returned includes the following:

- 1. All documents from the Proposal Cover Sheet through the Proposal Bid Bond
- 2. Other special documentation and/or information that may be required by the contract special provisions

All proposal documents, including Proposal Guaranty Checks or Proposal Bid Bonds, should be stapled together to prevent loss when bids are processed by IDOT personnel.

**ABOUT SUBMITTING BIDS**: It is recommended that bidders deliver bids in person to insure they arrive at the proper location prior to the time specified for the receipt of bids. Any bid received at the place of letting after the time specified will not be accepted.

Call

## WHO SHOULD BE CALLED IF ASSISTANCE IS NEEDED?

**Questions Regarding** 

Prequalification and/or Authorization to Bid	217/782-3413
Preparation and submittal of bids	217/782-7806
Mailing of CD-ROMS	217/782-7806



**PROPOSAL** 

## TO THE DEPARTMENT OF TRANSPORTATION

Project CMM-M-5011(246)
Route FAU 8852 (Poplar Street)
District 8 Construction Funds

1.	Proposal of
Та	xpayer Identification Number (Mandatory)  for the improvement identified and advertised for bids in the Invitation for Bids as:
	Contract No. 97324  MADISON County  Section 06-00056-01-WR (Highland)

0.54 mile widening and resurfacing including storm sewers, pavement removal, combination curb and gutter, HMA binder and surface, PCC driveways and sidewalks on Poplar Street between Broadway to Sixth Street and construction of a modern roundabout at the intersection of Broadway and Poplar Street all in Highland.

2. The undersigned bidder will furnish all labor, material and equipment to complete the above described project in a good and workmanlike manner as provided in the contract documents provided by the Department of Transportation. This proposal will become part of the contract and the terms and conditions contained in the contract documents shall govern performance and payments.

- 3. **ASSURANCE OF EXAMINATION AND INSPECTION/WAIVER.** The undersigned further declares that he/she has carefully examined the proposal, plans, specifications, form of contract and contract bond, and special provisions, and that he/she has inspected in detail the site of the proposed work, and that he/she has familiarized themselves with all of the local conditions affecting the contract and the detailed requirements of construction, and understands that in making this proposal he/she waives all right to plead any misunderstanding regarding the same.
- 4. **EXECUTION OF CONTRACT AND CONTRACT BOND.** The undersigned further agrees to execute a contract for this work and present the same to the department within fifteen (15) days after the contract has been mailed to him/her. The undersigned further agrees that he/she and his/her surety will execute and present within fifteen (15) days after the contract has been mailed to him/her contract bond satisfactory to and in the form prescribed by the Department of Transportation, in the penal sum of the full amount of the contract, guaranteeing the faithful performance of the work in accordance with the terms of the contract.
- 5. PROPOSAL GUARANTY. Accompanying this proposal is either a bid bond on the department form, executed by a corporate surety company satisfactory to the department, or a proposal guaranty check consisting of a bank cashier's check or a properly certified check for not less than 5 per cent of the amount bid or for the amount specified in the following schedule:

<u> </u>	Amount o	of Bid	Proposal <u>Guaranty</u>	<u>Am</u>	ount c	Proposal <u>of Bid</u> <u>Guaranty</u>
Up to		\$5,000	\$150	\$2,000,000	to	\$3,000,000\$100,000
\$5,000	to	\$10,000	\$300	\$3,000,000	to	\$5,000,000 \$150,000
\$10,000	to	\$50,000	\$1,000	\$5,000,000	to	\$7,500,000 \$250,000
\$50,000	to	\$100,000	\$3,000	\$7,500,000	to	\$10,000,000 \$400,000
\$100,000	to	\$150,000	\$5,000	\$10,000,000	to	\$15,000,000 \$500,000
\$150,000	to	\$250,000	\$7,500	\$15,000,000	to	\$20,000,000 \$600,000
\$250,000	to	\$500,000	\$12,500	\$20,000,000	to	\$25,000,000\$700,000
\$500,000	to	\$1,000,000	\$25,000	\$25,000,000	to	\$30,000,000\$800,000
\$1,000,000	to	\$1,500,000	\$50,000	\$30,000,000	to	\$35,000,000 \$900,000
\$1,500,000	to	\$2,000,000	\$75,000	over		\$35,000,000 \$1,000,000

Bank cashier's checks or properly certified checks accompanying proposals shall be made payable to the Treasurer, State of Illinois, when the state is awarding authority; the county treasurer, when a county is the awarding authority; or the city, village, or town treasurer, when a city, village, or town is the awarding authority.

If a combination bid is submitted, the proposal guaranties which accompany the individual proposals making up the combination will be considered as also covering the combination bid.

The amount of the proposal guaranty check is	\$(	). If this proposal is accepted
and the undersigned shall fail to execute a contract bond as required herein, it is	s hereby agreed that the amount	of the proposal guaranty shall become
the property of the State of Illinois, and shall be considered as payment of dama	ges due to delay and other cause	s suffered by the State because of the
failure to execute said contract and contract bond; otherwise, the bid bond sha	Il become void or the proposal g	uaranty check shall be returned to the
undersigned.	-	

## 

Mark the proposal cover sheet as to the type of proposal guaranty submitted.

BD 354 (Rev. 11/2001)

6. **COMBINATION BIDS.** The undersigned further agrees that if awarded the contract for the sections contained in the following combination, he/she will perform the work in accordance with the requirements of each individual proposal comprising the combination bid specified in the schedule below, and that the combination bid shall be prorated against each section in proportion to the bid submitted for the same. If an error is found to exist in the gross sum bid for one or more of the individual sections included in a combination, the combination bid shall be corrected as provided in the specifications.

When a combination bid is submitted, the schedule below must be completed in each proposal comprising the combination.

If alternate bids are submitted for one or more of the sections comprising the combination, a combination bid must be submitted for each alternate.

## **Schedule of Combination Bids**

Combination		Combination Bid	
No.	Sections Included in Combination	Dollars 0	Cents

- 7. SCHEDULE OF PRICES. The undersigned bidder submits herewith, in accordance with the rules and instructions, a schedule of prices for the items of work for which bids are sought. The unit prices bid are in U.S. dollars and cents, and all extensions and summations have been made. The bidder understands that the quantities appearing in the bid schedule are approximate and are provided for the purpose of obtaining a gross sum for the comparison of bids. If there is an error in the extension of the unit prices, the unit prices shall govern. Payment to the contractor awarded the contract will be made only for actual quantities of work performed and accepted or materials furnished according to the contract. The scheduled quantities of work to be done and materials to be furnished may be increased, decreased or omitted as provided elsewhere in the contract.
- 8. **CERTIFICATE OF AUTHORITY.** The undersigned bidder, if a business organized under the laws of another State, assures the Department that it will furnish a copy of its certificate of authority to do business in the State of Illinois with the return of the executed contract and bond. Failure to furnish the certificate within the time provided for execution of an awarded contract may be cause for cancellation of the award and forfeiture of the proposal guaranty to the State.

STATE JOB #- C-98-312-08 PPS NBR - 8-10253-0000

# ILLINOIS DEPARTMENT OF TRANSPORTATION SCHEDULE OF PRICES CONTRACT NUMBER - 97324

ECMS002 DTGECM03 ECMR003 PAGE RUN DATE - 11/13/07 RUN TIME - 205951

1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1		0 1	C i	ANITARY CLEANOUT 6	03470
1	- 11 -	0	LS	CONC STEP REMOVAL	X002176
1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1		82.000	F00	CASING PIPE	X000731
   1   1   1   1   1   1   1	1	658.000	<b>-</b>	CONC PAVER PAVEMENT	R430030
	11 11	. 000	EAC	E-PICEA PUNG GLAU 8'	2002288
   1   1   1   1   1   1   1		2,000	EAC	E-PICEA OMORIKA 8'	2002088
                     	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	2.000	EAC	E-PICEA GLAUCA 6'	2001872
1 1 1 1 1 1 1	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	14.000	EAC	EUONY ALAT COMP 18C	202618
1   	1	.000	EAC	-CORNUS FLOR CL 6'	2001366
1 3 5 1 1 1 2 1	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	8,000	AC	-CERCIS CAN CL 7'	2001168
1		. 000		T-QUERCUS RUBRA 2-1/2	2007120
1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	11	0		T-LIRIODEN TUL 2-1/2	005420
	1 1 1 1	.000	EAC	-FRAX AMER AP CL 8'	2003570
	I	. 000	AC	T-ACER RUB RS 2-1/2	2001220
	,	. 000	EACH	2-1/	2001120
TOTAL PRICE DOLLARS CTS	UNIT PRICE DOLLARS CENTS	QUANTITY	UNIT OF MEASURE	PAY ITEM DESCRIPTION	I TEM NUMBER
ROUTE FAU 8852	PROJECT NUMBER -5011/246/000	CMM-M-	TION NUMBER R (HIGHLAND)	AME   CODE   DIST   SEC   119   08   06-00056-01-W	COUNTY N. MADISON

FAU 8852 06-00056-01-WR (HIGHLAND) MADISON

# ILLINOIS DEPARTMENT OF TRANSPORTATION SCHEDULE OF PRICES CONTRACT NUMBER - 97324

ECMS002 DTGECM03 ECMR003 PAGE RUN DATE - 11/13/07 RUN TIME - 205951

ıl					
NUMBER	PAY ITEM DESCRIPTION	MEASURE	QUANTITY	UNIT PRICE DOLLARS CENTS	TOTAL PRICE DOLLARS CTS
X00543	OC UNDERGR UTILITY	AC	20.000 X		- 11
X14640	TORM SEWER REMOVAL	F00	516.000 X		
7800200	AINT PVT MARK CURB	0	6.0	I I I I I	
0015000	RB STOPS 1	EAC	00		
010011	REE REMOV 6-15	INI	4.00		
010021	REE REMOV OVER 15	UNIT	2.00		1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1
200100	RTH EXCAVATION	CU YD	3,014.00		
080015	RENCH BACKFILL	CU YD	2,247.00		1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1
101605	TOPSOIL F & P 2	SQ Y	81.000		1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1
500011	EDING CL 1B	AC	1.100	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	
500040	ITROGEN FERT NUTR	NOO	99.000		
5000500	PHOSPHORUS FERT NUTR	POUN	9.00		
5000600	SSIUM FERT NUTR	POUN	9.000		
510011	IULCH	ACR	100		
51006	ROSION CONTR BLANKET	SQ YD	967.000 X	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1

# ILLINOIS DEPARTMENT OF TRANSPORTATION SCHEDULE OF PRICES CONTRACT NUMBER - 97324

ECMS002 DTGECM03 ECMR003 PAGE RUN DATE - 11/13/07 RUN TIME - 205951

1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	 	09.00	NOT	C IL-19.0 N70	40603085
   1   1   1   1   1   1   1   1   1		738.000	TON	EV BIND MM N70	060063
	 	20.000	NON	AGG PR CT	0600300
	                     	1,378.000	GALLON	BIT MATLS PR CT	
	 	200.000	TON	AGGREGATE-TEMP ACCESS	020100
	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	8.000	ĭ.	GG SURF CSE A 6	20050
	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	155.000	SQ	HMA BC WID 9	5600712
1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	1 1 1 - 11 - 11	107.000	SQ YD	PCC BASE CSE W 9	540040
.	   1   1   1   1   1	398.000	SQ YD	AGG BASE CSE A 6	510050
	1	,270.000	ŞQ	SUB GRAN MAT A 12	1100910
	1	316.000	SQ YD	FILTER FABRIC	200200
1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1		316.000	SQ YD	STONE RIPRAP CL A4	810010
1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1		68.000	EACH	INLET & PIPE PROTECT	8000500
	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	950.000	F00	PERIMETER EROS BAR	800040
		,120.000	$\subseteq$	EROS CON	28000250
TOTAL PRICE DOLLARS CTS	UNIT PRICE DOLLARS CENTS	QUANTITY	UNIT OF MEASURE	PAY ITEM DESCRIPTION	I TEM NUMBER

FAU 8852 06-00056-01-WR (HIGHLAND) MADISON

# ILLINOIS DEPARTMENT OF TRANSPORTATION SCHEDULE OF PRICES CONTRACT NUMBER - 97324

ECMS002 DTGECM03 ECMR003 PAGE RUN DATE - 11/13/07 RUN TIME - 205951

	1,679.000 X 10,858.000 X	1		
	1,679.000 X	SQ FT	DEWALK REM	44000600
- II		FQ	COMB CURB GUTTER REM	400050
- II -	3.000 X	F00	GUTTER REM	0040
	92.000 X	FOOT	CURB REM	00030
	885.000 X	Q YD	DRIVE PAVEMENT REM	0020
1 1 1 1 1	5,972.000 X	SQ YD	HMA SURF REM VAR DP	4000198
- 11	4,641.000 X	SQ YD	PAVEMENT REM	00010
; ; ; ; ; ; ; ; ; ; ; ; ; ; ; ; ; ; ;	553.000 X	SQ FT	DETECTABLE WARNINGS	240080
1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	1,278.000 X	SQ FT	PC CONC SIDEWALK 6	40030
	18,539.000 X	SQ FT	PC CONC SIDEWALK 4	240010
- 11 - 1 - 1 - 1 - 1 - 1 - 1 - 1 - 1 -	208.000 X	SQ YD	PCC DRIVEWAY PAVT 8	2300400
1 1 1	587.000 X	SQ YD	PCC DRIVEWAY PAVT 6	230020
1 	75.000 X	TON	IDENTAL HMA SURF	40800050
	57.000 X		HMA SC "D" N70	40603340
UNIT PRICE TOTAL PRICE DOLLARS CENTS DOLLARS CTS	QUANTITY	UNIT OF MEASURE	PAY ITEM DESCRIPTION	I TEM NUMBER

4

## ILLINOIS DEPARTMENT OF TRANSPORTATION EC SCHEDULE OF PRICES RU CONTRACT NUMBER - 97324 RU

ECMS002 DTGECM03 ECMR003 PAGE RUN DATE - 11/13/07 RUN TIME - 205951

-							
 		- II I	1 1 1 1 1 1 1 1		FOOT	S 2 RCP CL 3	502180
1   	;             	- 11 -	! ! ! ! ! !	i	T00	2 RCP CL 3 1	0216
1 1 1	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	 		347.000	F00	S 1 RCP CL 4 24	501990
 	         	; ; ; 11 —		175.000	FOOT	SS 1 RCP CL 4 18	5019
 	 	- II -	1	62.000	007	SS 1 RCP CL 4 15	5019600
I I	[ ] ]	  -  -  -		823.000	00	SS 1 RCP CL 4 12	5019500
1	; ; ; ; ; ;	- II -		4.000	EACH	R C PIPE TEE 36P 12R	4216220
1 1 1	1 1 1 1 1 1 1	 	             	5.000	EACH	R C PIPE TEE 30P 12R	4216210
1	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	- 11		1.000	오 :	R C PIPE TEE 24P 12R	216200
I I	4 1 1 1 1 1 1	  -  -  -  -		2.000	ACH	R C PIPE TEE 18P 12R	4216190
! !		 	                 	1.000	EACH	PRC FLAR END SEC 36	4213681
1	 	! ! ! ! !	! !	27.000	F00T	PIPE CULVERT REMOV	105220
 	;;;;;;;;;;;;;;;;;;;;;;;;;;;;;;;;;;;;;;	- II -	· I	77.000	F00	STRIP REF CR CON TR	430020
I I I	                 	- II -	               	731.000	SQ YD	CL D PATCH T4 12	4201
		- 11		0	SQ Y	ATCH T3 12	
CTS	TOTAL PRICE	CENTS _	UNIT PRIO	QUANTITY	WEASURE	PAY ITEM DESCRIPTION	I TEM NUMBER

FAU 8852 06-00056-01-WR (HIGHLAND) MADISON

# ILLINOIS DEPARTMENT OF TRANSPORTATION ECMS002 DTGECM03 ECMR003 PAGE SCHEDULE OF PRICES RUN DATE - 11/13/07 CONTRACT NUMBER - 97324 RUN TIME - 205951

I TEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE DOLLARS   CENTS	TOTAL PRICE DOLLARS   CT
5022	S 2 RCP CL 3 30	F00	440.000	· 11 —	
55022400	2 RCP CL 3 36	F00T	1,664.000		
6100	WATER MAIN 6	FOOT	26.000	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	
6100	WATER MAIN 10	FOOT	449.000 X		
6105100	WATER VALVES 10	EACH	I		
6108	TAP VALVE & SLEEVE 6	EACH	00	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1
6200300	WATER SERV LINE 1	FOOT	125.000	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	
6201400	CORP STOPS 1	EACH	5.000		
6300100	ADJ SAN SEWER 8 LESS	FOOT	163:000	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	
6400	FIRE HYDNT & VAL SPL	EACH	2.000		
0218	MAN TA 4 DIA T1F OL	ACH	1.000	. 11	. 1
0218	MAN TA 4 DIA T1F CL	EACH	3.000	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	
0218	AN TA 4 DIA T3F&G	EAC	00		1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1
1 (0	MAN TA 4 DIA T24F&G	EACH	000	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	
022110	TA 5 DIA T1F CL	EACH	11.000 X	11	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1

တ ·

FAU 8852 06-00056-01-WR (HIGHLAND) MADISON

# ILLINOIS DEPARTMENT OF TRANSPORTATION SCHEDULE OF PRICES CONTRACT NUMBER - 97324

ECMS002 DTGECM03 ECMR003 PAGE RUN DATE - 11/13/07 RUN TIME - 205951

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE DOLLARS CENTS	TOTAL PRICE	<u>   </u>
0222	AN TA 5 DIA T24F&G	$\triangleright$	3.000 X	. 11 —		
020	MAN SPL 4 DIA T1F OL	ΕΑι	1.000 X		1	<u> </u>
0234	INLETS TA T1F OL	ÞΙ	1.000 X			i
023570	INLETS TA T3F&G	AC	1.0			i
0236200	INLETS TA T8G		00		1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	<u>i</u>
0237470	INLETS TA T24F&G	Ε'n	20.000		1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	<u>i</u>
238610	INLETS TA SALV GRATE	EACH	1.000			i
102	LETS TB T3F&G	EACH	00		1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	i
0240328	INLETS TB T24F&G	ACH ·	10.000			<u>i</u>
02425	NLETS SPL N1	EACH	1.000	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	<u>.</u> i
024260	NLETS SPL N2	EACH	Ō	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	<u>i</u>
0242700	INLETS SPL N3	EAC	1.000 X			i
2428	NLETS SPL N4	EACH	1.000	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	i
024800	UNCTION CHAMBER N1	EAC	000	- 11 - 1		i
24810	TION CHAMBER N2	EA		;;;;;;;;;;;;;;;;;;;;;;;;;;;;;;;;;;;;;;	, I , I , I , I I I	t
						<u> </u>

7

# ILLINOIS DEPARTMENT OF TRANSPORTATION SCHEDULE OF PRICES CONTRACT NUMBER - 97324

ECMS002 DTGECM03 ECMR003 PAGE RUN DATE - 11/13/07 RUN TIME - 205951

1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	1 1 1 1 -		1.000 X	SUM	IZATION	71001
	- 11	-	000	F00T	OMB CC&G SPL	6116
1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	  -  -  -  -	1 1 1 1 1 1	118.000	FOOT	B CC&G TM2.24	060852
1 1 1 1 1 1 1 1 1 1	- 11	 	383.0	F00T	B CC&G TM2.12	060830
1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	- 11 -	1 2 1 1 1 1 1	276.000	00T	B CC&G TB9.	060590
1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	1 1 1 1 - 11 -	; ; ; ; ; ; ; ; ;	97.000	FOOT	B CC&G TB6 24	060
	  -  -  -		45.000	FOOT	CONC GUTTER SPL	90
	  -  -  -		189.000	FOOT	CONC CURB TB	90
1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	  -  -  -	                 	2.000	CU YD	CLASS SI CONC OUTLET	960
1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	- II —	1 1 1 1 1 1 1	00	E I	REMOV INLETS	050006
1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	- II - I	1 1 1	3.000	EACH	REMOV MANHOLES	050004
	- 11 -	1 	4.000	EAC	ALVE BOX ADJ	02666
	- 11 -	                 	1.000 X	EAC	LETS ADJ NEW T24F&G	026154
1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	- II -	, I I I I I I I	1.000	EACH	AN ADJUST SPL	025560
	- 11		00	AC	DUUST	60255500
TOTAL PRICE DOLLARS CTS	CENTS _	UNIT PRIO	QUANTITY	UNIT OF MEASURE	PAY ITEM DESCRIPTION	I TEM NUMBER

ω

# ILLINOIS DEPARTMENT OF TRANSPORTATION SCHEDULE OF PRICES CONTRACT NUMBER - 97324

ECMS002 DTGECM03 ECMR003 PAGE RUN DATE - 11/13/07 RUN TIME - 205951

_						
! !	: : : : : : : :	- 11	626.000 X	FOOT	TAL POST TY B	72900200
 	1 1 1 1 1 1 1	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	63.000	FOOT	ETAL POST TY A	29001
! !	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	1 1 1 1 1 1 1	751:000 X	POUN	UB STL SN SUPPORT BA	270020
! ! !	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	.	89.000 X	SQ FT	GN PANEL T3 SPL	20003
1	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	1 1 1 2 1 1	28.00	SQ FT	GN PANEL T2 SPL	200020
1 1 1	; ; ; ; ; ;	1	12.000	QFT	SIGN PANEL T1 SPL	2000105
1 1	I I I I I I I I		401.000	SQ FT	SIGN PANEL T1	2000100
1	1 1 1		689.000 X	SQ FT	WORK ZONE PAVT MK REM	0301000
 	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	                 	1,672.000 X	FOOT	TEMP PVT MK LINE 8	0300250
1 1		I I I I	570.000 X	FOOT	TEMP PVT MK LINE 4	300220
1 1	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	81.00	SQ F	TEMP PVT MK LTR & SYM	0300210
t 1 1		. 11	2,088.000	FOOT	SHORT-TERM PAVT MKING	0300100
! ! !	; ; ; ; ; ;	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	1.000 X	L SUM	TRAF CONT & PROT D2	0102000
ł 	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1		1.000 X	L SUM	TRAF CONT & PROT D1	0101900
		- II	1.000	L SUM	TRAF CO	010170
CIS	TOTAL PRICE	UNIT PRICE DOLLARS CENTS	QUANTITY	UNIT OF  MEASURE	PAY ITEM DESCRIPTION	I TEM NUMBER

FAU 8852 06-00056-01-WR (HIGHLAND) MADISON

# ILLINOIS DEPARTMENT OF TRANSPORTATION SCHEDULE OF PRICES CONTRACT NUMBER - 97324

ECMS002 DTGECM03 ECMR003 PAGE RUN DATE - 11/13/07 RUN TIME - 205951

10

TOTAL \$			•	
- II - I	5.000 X	EACH	EMOV EX CONC FD	N
	4.000 X	EAC	EMOV EX HANDHOLE	950238
- II	1.000 X	EACH	EMOV EX TS EQUIP	502
 		EACH	PRISMATIC CURB REFL	8200300
	83.000	SQ F	PREF THPL PM LTR-SYM	8006100
	796.000	FOOT	THPL PVT MK LINE 24	000650
- II - I I I I I I I I I I I I I I I I	. 000	F00T	THPL PVT MK LINE 1	8000600
	672.000	FOOT	THPL PVT MK LINE 8	8000500
- II - I - I - I - I - I - I - I - I -	2,963.000	FOOT	THPL PVT MK LINE 6	8000400
- 11 - 1 - 1 - 1 - 1 - 1 - 1 - 1 - 1 -	4,835.000	FOOT	THPL PVT MK LINE 4	800020
	17.0	QFT	THPL PVT MK LTR & SYM	8000100
	4.200 X	CU YD	CONC FOUNDATION	40010
	00	F00	00D	73000100
UNIT PRICE TOTAL PRICE DOLLARS CENTS DOLLARS CTS	QUANTITY	UNIT OF MEASURE	PAY ITEM DESCRIPTION	ITEM NUMBER

NOTE:
\*\*\* PLEASE TURN PAGE FOR IMPORTANT NOTES \*\*\*

=

NOTE:

- EACH PAY ITEM SHOULD HAVE A UNIT PRICE AND A TOTAL PRICE.
- 2. THE UNIT PRICE SHALL GOVERN IF NO TOTAL PRICE IS SHOWN OR IF THERE IS A DISCREPANCY BETWEEN THE PRODUCT OF THE UNIT PRICE MULTIPLIED BY THE QUANTITY.
- ω. IF A UNIT PRICE IS OMITTED, THE TOTAL PRICE WILL BE DIVIDED BY THE QUANTITY IN ORDER TO ESTABLISH A UNIT PRICE.
- Þ BID MAY BE DECLARED UNACCEPTABLE IF NEITHER A UNIT PRICE NOR A TOTAL PRICE IS SHOWN.

## STATE REQUIRED ETHICAL STANDARDS GOVERNING CONTRACT PROCUREMENT: ASSURANCES, CERTIFICATIONS AND DISCLOSURES

## I. GENERAL

- **A.** Article 50 of the Illinois Procurement Code establishes the duty of all State chief procurement officers, State purchasing officers, and their designees to maximize the value of the expenditure of public moneys in procuring goods, services, and contracts for the State of Illinois and to act in a manner that maintains the integrity and public trust of State government. In discharging this duty, they are charged by law to use all available information, reasonable efforts, and reasonable actions to protect, safeguard, and maintain the procurement process of the State of Illinois.
- **B.** In order to comply with the provisions of Article 50 and to carry out the duty established therein, all bidders are to adhere to ethical standards established for the procurement process, and to make such assurances, disclosures and certifications required by law. By execution of the Proposal Signature Sheet, the bidder indicates that each of the mandated assurances has been read and understood, that each certification is made and understood, and that each disclosure requirement has been understood and completed.
- **C.** In addition to all other remedies provided by law, failure to comply with any assurance, failure to make any disclosure or the making of a false certification shall be grounds for termination of the contract and the suspension or debarment of the bidder.

## **II. ASSURANCES**

**A.** The assurances hereinafter made by the bidder are each a material representation of fact upon which reliance is placed should the Department enter into the contract with the bidder. The Department may terminate the contract if it is later determined that the bidder rendered a false or erroneous assurance, and the surety providing the performance bond shall be responsible for the completion of the contract.

## B. Felons

1. The Illinois Procurement Code provides:

Section 50-10. Felons. Unless otherwise provided, no person or business convicted of a felony shall do business with the State of Illinois or any state agency from the date of conviction until 5 years after the date of completion of the sentence for that felony, unless no person held responsible by a prosecutorial office for the facts upon which the conviction was based continues to have any involvement with the business.

2. The bidder assures the Department that the award and execution of the contract would not cause a violation of Section 50-10.

## C. Conflicts of Interest

1. The Illinois Procurement Code provides in pertinent part:

Section 50-13. Conflicts of Interest.

- (a) Prohibition. It is unlawful for any person holding an elective office in this State, holding a seat in the General Assembly, or appointed to or employed in any of the offices or agencies of state government and who receives compensation for such employment in excess of 60% of the salary of the Governor of the State of Illinois, or who is an officer or employee of the Capital Development Board or the Illinois Toll Highway Authority, or who is the spouse or minor child of any such person to have or acquire any contract, or any direct pecuniary interest in any contract therein, whether for stationery, printing, paper, or any services, materials, or supplies, that will be wholly or partially satisfied by the payment of funds appropriated by the General Assembly of the State of Illinois or in any contract of the Capital Development Board or the Illinois Toll Highway authority.
- (b) Interests. It is unlawful for any firm, partnership, association or corporation, in which any person listed in subsection (a) is entitled to receive (i) more than 7 1/2% of the total distributable income or (ii) an amount in excess of the salary of the Governor, to have or acquire any such contract or direct pecuniary interest therein.
- (c) Combined interests. It is unlawful for any firm, partnership, association, or corporation, in which any person listed in subsection (a) together with his or her spouse or minor children is entitled to receive (i) more than 15%, in the aggregate, of the total distributable income or (ii) an amount in excess of 2 times the salary of the Governor, to have or acquire any such contract or direct pecuniary interest therein.
- (d) Securities. Nothing in this Section invalidates the provisions of any bond or other security previously offered or to be offered for sale or sold by or for the State of Illinois.
- (e) Prior interests. This Section does not affect the validity of any contract made between the State and an officer or employee of the State or member of the General Assembly, his or her spouse, minor child or any combination of those persons if that contract was in existence before his or her election or employment as an officer, member, or employee. The contract is voidable, however, if it cannot be completed within 365 days after the officer, member, or employee takes office or is employed.

The current salary of the Governor is \$171,000.00. Sixty percent of the salary is \$102,600.00.

2. The bidder assures the Department that the award and execution of the contract would not cause a violation of Section 50-13, or that an effective exemption has been issued by the Board of Ethics to any individual subject to the Section 50-13 prohibitions pursuant to the provisions of Section 50-20 of the Code and Executive Order Number 3 (1998). Information concerning the exemption process is available from the Department upon request.

## D. Negotiations

1. The Illinois Procurement Code provides in pertinent part:

Section 50-15. Negotiations.

- (a) It is unlawful for any person employed in or on a continual contractual relationship with any of the offices or agencies of State government to participate in contract negotiations on behalf of that office or agency with any firm, partnership, association, or corporation with whom that person has a contract for future employment or is negotiating concerning possible future employment.
- 2. The bidder assures the Department that the award and execution of the contract would not cause a violation of Section 50-15, and that the bidder has no knowledge of any facts relevant to the kinds of acts prohibited therein.

## E. Inducements

1. The Illinois Procurement Code provides:

Section 50-25. Inducement. Any person who offers or pays any money or other valuable thing to any person to induce him or her not to bid for a State contract or as recompense for not having bid on a State contract is guilty of a Class 4 felony. Any person who accepts any money or other valuable thing for not bidding for a State contract or who withholds a bid in consideration of the promise for the payment of money or other valuable thing is guilty of a Class 4 felony.

2. The bidder assures the Department that the award and execution of the contract would not cause a violation of Section 50-25, and that the bidder has no knowledge of any facts relevant to the kinds of acts prohibited therein.

## F. Revolving Door Prohibition

1. The Illinois Procurement Code provides:

Section 50-30. Revolving door prohibition. Chief procurement officers, associate procurement officers, State purchasing officers, their designees whose principal duties are directly related to State procurement, and executive officers confirmed by the Senate are expressly prohibited for a period of 2 years after terminating an affected position from engaging in any procurement activity relating to the State agency most recently employing them in an affected position for a period of at least 6 months. The prohibition includes, but is not limited to: lobbying the procurement process; specifying; bidding; proposing bid, proposal, or contract documents; on their own behalf or on behalf of any firm, partnership, association, or corporation. This Section applies only to persons who terminate an affected position on or after January 15, 1999.

2. The bidder assures the Department that the award and execution of the contract would not cause a violation of Section 50-30, and that the bidder has no knowledge of any facts relevant to the kinds of acts prohibited therein.

## G. Reporting Anticompetitive Practices

1. The Illinois Procurement Code provides:

Section 50-40. Reporting anticompetitive practices. When, for any reason, any vendor, bidder, contractor, chief procurement officer, State purchasing officer, designee, elected official, or State employee suspects collusion or other anticompetitive practice among any bidders, offerors, contractors, proposers, or employees of the State, a notice of the relevant facts shall be transmitted to the Attorney General and the chief procurement officer.

2. The bidder assures the Department that it has not failed to report any relevant facts concerning the practices addressed in Section 50-40 which may involve the contract for which the bid is submitted.

## H. Confidentiality

1. The Illinois Procurement Code provides:

Section 50-45. Confidentiality. Any chief procurement officer, State purchasing officer, designee, or executive officer who willfully uses or allows the use of specifications, competitive bid documents, proprietary competitive information, proposals, contracts, or selection information to compromise the fairness or integrity of the procurement, bidding, or contract process shall be subject to immediate dismissal, regardless of the Personnel code, any contract, or any collective bargaining agreement, and may in addition be subject to criminal prosecution.

2. The bidder assures the Department that it has no knowledge of any fact relevant to the practices addressed in Section 50-45 which may involve the contract for which the bid is submitted.

## I. Insider Information

1. The Illinois Procurement Act provides:

Section 50-50. Insider information. It is unlawful for any current or former elected or appointed State official or State employee to knowingly use confidential information available only by virtue of that office or employment for actual or anticipated gain for themselves or another person.

2. The bidder assures the Department that it has no knowledge of any facts relevant to the practices addressed in Section 50-50 which may involve the contract for which the bid is submitted.

## **III. CERTIFICATIONS**

**A.** The certifications hereinafter made by the bidder are each a material representation of fact upon which reliance is placed should the Department enter into the contract with the bidder. The Department may terminate the contract if it is later determined that the bidder rendered a false or erroneous certification, and the surety providing the performance bond shall be responsible for completion of the contract.

## B. Bribery

1. The Illinois Procurement Code provides:

Section 50-5. Bribery.

- (a) Prohibition. No person or business shall be awarded a contract or subcontract under this Code who:
  - (1) has been convicted under the laws of Illinois or any other state of bribery or attempting to bribe an officer or employee of the State of Illinois or any other state in that officer's or employee's official capacity; or
  - (2) has made an admission of guilt of that conduct that is a matter of record but has not been prosecuted for that conduct.
- (b) Businesses. No business shall be barred from contracting with any unit of State or local government as a result of a conviction under this Section of any employee or agent of the business if the employee or agent is no longer employed by the business and:
  - (1) the business has been finally adjudicated not guilty; or
  - (2) the business demonstrates to the governmental entity with which it seeks to contract, and that entity finds that the commission of the offense was not authorized, requested, commanded, or performed by a director, officer, or high managerial agent on behalf of the business as provided in paragraph (2) of subsection (a) of Section 5-4 of the Criminal Code of 1961.
- (c) Conduct on behalf of business. For purposes of this Section, when an official, agent, or employee of a business committed the bribery or attempted bribery on behalf of the business and in accordance with the direction or authorization of a responsible official of the business, the business shall be chargeable with the conduct.
- (d) Certification. Every bid submitted to and contract executed by the State shall contain a certification by the contractor that the contractor is not barred from being awarded a contract or subcontract under this Section. A contractor who makes a false statement, material to the certification, commits a Class 3 felony.
- 2. The bidder certifies that it is not barred from being awarded a contract under Section 50.5.

## C. Educational Loan

- 1. Section 3 of the Educational Loan Default Act provides:
- § 3. No State agency shall contract with an individual for goods or services if that individual is in default, as defined in Section 2 of this Act, on an educational loan. Any contract used by any State agency shall include a statement certifying that the individual is not in default on an educational loan as provided in this Section.
- 2. The bidder, if an individual as opposed to a corporation, partnership or other form of business organization, certifies that the bidder is not in default on an educational loan as provided in Section 3 of the Act.

## D. Bid-Rigging/Bid Rotating

- 1. Section 33E-11 of the Criminal Code of 1961 provides:
- § 33E-11. (a) Every bid submitted to and public contract executed pursuant to such bid by the State or a unit of local government shall contain a certification by the prime contractor that the prime contractor is not barred from contracting with any unit of State or local government as a result of a violation of either Section 33E-3 or 33E-4 of this Article. The State and units of local government shall provide the appropriate forms for such certification.

(b) A contractor who makes a false statement, material to the certification, commits a Class 3 felony.

A violation of Section 33E-3 would be represented by a conviction of the crime of bid-rigging which, in addition to Class 3 felony sentencing, provides that any person convicted of this offense or any similar offense of any state or the United States which contains the same elements as this offense shall be barred for 5 years from the date of conviction from contracting with any unit of State or local government. No corporation shall be barred from contracting with any unit of State or local government as a result of a conviction under this Section of any employee or agent of such corporation if the employee so convicted is no longer employed by the corporation and: (1) it has been finally adjudicated not guilty or (2) if it demonstrates to the governmental entity with which it seeks to contract and that entity finds that the commission of the offense was neither authorized, requested, commanded, nor performed by a director, officer or a high managerial agent in behalf of the corporation.

A violation of Section 33E-4 would be represented by a conviction of the crime of bid-rotating which, in addition to Class 2 felony sentencing, provides that any person convicted of this offense or any similar offense of any state or the United States which contains the same elements as this offense shall be permanently barred from contracting with any unit of State or local government. No corporation shall be barred from contracting with any unit of State or local government as a result of a conviction under this Section of any employee or agent of such corporation if the employee so convicted is no longer employed by the corporation and: (1) it has been finally adjudicated not guilty or (2) if it demonstrates to the governmental entity with which it seeks to contract and that entity finds that the commission of the offense was neither authorized, requested, commanded, nor performed by a director, officer or a high managerial agent in behalf of the corporation.

2. The bidder certifies that it is not barred from contracting with the Department by reason of a violation of either Section 33E-3 or Section 33E-4.

## E. International Anti-Boycott

- 1. Section 5 of the International Anti-Boycott Certification Act provides:
- § 5. State contracts. Every contract entered into by the State of Illinois for the manufacture, furnishing, or purchasing of supplies, material, or equipment or for the furnishing of work, labor, or services, in an amount exceeding the threshold for small purchases according to the purchasing laws of this State or \$10,000.00, whichever is less, shall contain certification, as a material condition of the contract, by which the contractor agrees that neither the contractor nor any substantially-owned affiliated company is participating or shall participate in an international boycott in violation of the provisions of the U.S. Export Administration Act of 1979 or the regulations of the U.S. Department of Commerce promulgated under that Act.
- 2. The bidder makes the certification set forth in Section 5 of the Act.

## F. Drug Free Workplace

- 1. The Illinois "Drug Free Workplace Act" applies to this contract and it is necessary to comply with the provisions of the "Act" if the contractor is a corporation, partnership, or other entity (including a sole proprietorship) which has 25 or more employees.
- 2. The bidder certifies that if awarded a contract in excess of \$5,000 it will provide a drug free workplace by:
- (a) Publishing a statement notifying employees that the unlawful manufacture, distribution, dispensation, possession or use of a controlled substance, including cannabis, is prohibited in the contractor's workplace; specifying the actions that will be taken against employees for violations of such prohibition; and notifying the employee that, as a condition of employment on such contract, the employee shall abide by the terms of the statement, and notify the employer of any criminal drug statute conviction for a violation occurring in the workplace no later than five (5) days after such conviction.
- (b) Establishing a drug free awareness program to inform employees about the dangers of drug abuse in the workplace; the contractor's policy of maintaining a drug free workplace; any available drug counseling, rehabilitation, and employee assistance programs; and the penalties that may be imposed upon employees for drug violations.
- (c) Providing a copy of the statement required by subparagraph (1) to each employee engaged in the performance of the contract and to post the statement in a prominent place in the workplace.
- (d) Notifying the Department within ten (10) days after receiving notice from an employee or otherwise receiving actual notice of the conviction of an employee for a violation of any criminal drug statute occurring in the workplace.
- (e) Imposing or requiring, within 30 days after receiving notice from an employee of a conviction or actual notice of such a conviction, an appropriate personnel action, up to and including termination, or the satisfactory participation in a drug abuse assistance or rehabilitation program approved by a federal, state or local health, law enforcement or other appropriate agency.
- (f) Assisting employees in selecting a course of action in the event drug counseling, treatment, and rehabilitation is required and indicating that a trained referral team is in place.
- (g) Making a good faith effort to continue to maintain a drug free workplace through implementation of the actions and efforts stated in this certification.

## G. Debt Delinquency

1. The Illinois Procurement Code provides:

Section 50-11 and 50-12. Debt Delinquency.

The contractor or bidder certifies that it, or any affiliate, is not barred from being awarded a contract under 30 ILCS 500. Section 50-11 prohibits a person from entering into a contract with a State agency if it knows or should know that it, or any affiliate, is delinquent in the payment of any debt to the State as defined by the Debt Collection Board. Section 50-12 prohibits a person from entering into a contract with a State agency if it, or any affiliate, has failed to collect and remit Illinois Use Tax on all sales of tangible personal property into the State of Illinois in accordance with the provisions of the Illinois Use Tax Act. The contractor further acknowledges that the contracting State agency may declare the contract void if this certification is false or if the contractor, or any affiliate, is determined to be delinquent in the payment of any debt to the State during the term of the contract.

## H. Sarbanes-Oxley Act of 2002

1. The Illinois Procurement Code provides:

Section 50-60(c).

The contractor certifies in accordance with 30 ILCS 500/50-10.5 that no officer, director, partner or other managerial agent of the contracting business has been convicted of a felony under the Sarbanes-Oxley Act of 2002 or a Class 3 or Class 2 felony under the Illinois Securities Law of 1953 for a period of five years prior to the date of the bid or contract. The contractor acknowledges that the contracting agency shall declare the contract void if this certification is false.

## I. Addenda

The contractor or bidder certifies that all relevant addenda have been incorporated in to this contract. Failure to do so may cause the bid to be declared unacceptable.

## J. Section 42 of the Environmental Protection Act

The contractor certifies in accordance with 30 ILCS 500/50-12 that the bidder or contractor is not barred from being awarded a contract under this Section which prohibits the bidding on or entering into contracts with the State of Illinois or a State agency by a person or business found by a court or the Pollution Control Board to have committed a willful or knowing violation of Section 42 of the Environmental Protection Act for a period of five years from the date of the order. The contractor acknowledges that the contracting agency may declare the contract void if this certification is false.

## K. Apprenticeship and Training Certification (Does not apply to federal aid projects)

In accordance with the provisions of Section 30-22 (6) of the Illinois Procurement Code, the bidder certifies that it is a participant, either as an individual or as part of a group program, in the approved apprenticeship and training programs applicable to each type of work or craft that the bidder will perform with its own forces. The bidder further certifies for work that will be performed by subcontract that each of its subcontractors submitted for approval either (a) is, at the time of such bid, participating in an approved, applicable apprenticeship and training program; or (b) will, prior to commencement of performance of work pursuant to this contract. begin participation in an approved apprenticeship and training program applicable to the work of the subcontract. The Department, at any time before or after award, may require the production of a copy of each applicable Certificate of Registration issued by the United States Department of Labor evidencing such participation by the contractor and any or all of its subcontractors. Applicable apprenticeship and training programs are those that have been approved and registered with the United States Department of Labor. The bidder shall list in the space below, the official name of the program sponsor holding the Certificate of Registration for all of the types of work or crafts in which the bidder is a participant and that will be performed with the bidder's forces. Types of work or craft work that will be subcontracted shall be included and listed as subcontract work. The list shall also indicate any type of work or craft job category that does not have an applicable apprenticeship or training program. The bidder is responsible for making a complete report and shall make certain that each type of work or craft job category that will be utilized on the project as reported on the Construction Employee Workforce Projection (Form BC-1256) and returned with the bid is accounted for and listed.

## NA - FEDERAL

The requirements of this certification and disclosure are a material part of the contract, and the contractor shall require this certification provision to be included in all approved subcontracts. In order to fulfill this requirement, it shall not be necessary that an applicable program sponsor be currently taking or that it will take applications for apprenticeship, training or employment during the performance of the work of this contract.

## L. Executive Order Number 1 (2007) Regarding Lobbying on Government Procurements

The bidder hereby warrants and certifies that they have complied and will comply with the requirements set forth in this Order. The requirements of this warrant and certification are a material part of the contract, and the contractor shall require this warrant and certification provision to be included in all approved subcontracts.

Public Act 95-0616 provides that each bid, offer, or proposal submitted for a State contract shall include a disclosure of whether or not the Company acting as the bidder, offeror, or proposing entity, or any of its corporate parents or subsidiaries, within the 24 months before submission of the bid, offer, or proposal had business operations that involved contracts with or provision of supplies or services to the Government of Iran, companies in which the Government of Iran has any direct or indirect equity share, consortiums or projects commissioned by the Government of Iran and either of the following conditions apply:

- (1) More than 10% of the Company's revenues produced in or assets located in Iran involve oil-related activities or mineral-extraction activities; less than 75% of the Company's revenues produced in or assets located in Iran involve contracts with or provision of oil-related or mineral-extraction products or services to the Government of Iran or a project or consortium created exclusively by that government; and the Company has failed to take substantial action.
- (2) The Company has, on or after August 5, 1996, made an investment of \$20 million or more, or any combination of investments of at least \$10 million each that in the aggregate equals or exceeds \$20 million in any 12-month period, which directly or significantly contributes to the enhancement of Iran's ability to develop petroleum resources of Iran.

The terms "Business operations", "Company", "Mineral-extraction activities", "Oil-related activities", "Petroleum resources", and "Substantial action" are all defined in the Act.

Failure to make the disclosure required by the Act shall cause the bid, offer or proposal to be considered not responsive. The disclosure will be considered when evaluating the bid, offer, or proposal or awarding the contract. The name of each Company disclosed as doing business or having done business in Iran will be provided to the State Comptroller.

Check the appropriate statement:
// Company has no business operations in Iran to disclose.
// Company has business operations in Iran as disclosed the attached document.

## TO BE RETURNED WITH BID

## **IV. DISCLOSURES**

**A.** The disclosures hereinafter made by the bidder are each a material representation of fact upon which reliance is placed should the Department enter into the contract with the bidder. The Department may terminate the contract if it is later determined that the bidder rendered a false or erroneous disclosure, and the surety providing the performance bond shall be responsible for completion of the contract.

## **B.** Financial Interests and Conflicts of Interest

1. Section 50-35 of the Illinois Procurement Code provides that all bids of more than \$10,000 shall be accompanied by disclosure of the financial interests of the bidder. This disclosed information for the successful bidder, will be maintained as public information subject to release by request pursuant to the Freedom of Information Act.

The financial interests to be disclosed shall include ownership or distributive income share that is in excess of 5%, or an amount greater than 60% of the annual salary of the Governor, of the bidding entity or its parent entity, whichever is less, unless the contractor or bidder is a publicly traded entity subject to Federal 10K reporting, in which case it may submit its 10K disclosure in place of the prescribed disclosure. If a bidder is a privately held entity that is exempt from Federal 10K reporting, but has more than 400 shareholders, it may submit the information that Federal 10K companies are required to report, and list the names of any person or entity holding any ownership share that is in excess of 5%. The disclosure shall include the names, addresses, and dollar or proportionate share of ownership of each person making the disclosure, their instrument of ownership or beneficial relationship, and notice of any potential conflict of interest resulting from the current ownership or beneficial interest of each person making the disclosure having any of the relationships identified in Section 50-35 and on the disclosure form.

In addition, all disclosures shall indicate any other current or pending contracts, proposals, leases, or other ongoing procurement relationships the bidding entity has with any other unit of state government and shall clearly identify the unit and the contract, proposal, lease, or other relationship.

2. <u>Disclosure Forms</u>. Disclosure Form A is attached for use concerning the individuals meeting the above ownership or distributive share requirements. Subject individuals should be covered each by one form. In addition, a second form (Disclosure Form B) provides for the disclosure of current or pending procurement relationships with other (non-IDOT) state agencies. **The forms must be included with each bid or incorporated by reference.** 

## C. <u>Disclosure Form Instructions</u>

## Form A: For bidders that have previously submitted the information requested in Form A

The Department has retained the Form A disclosures submitted by all bidders responding to these requirements for the April 24, 1998 or any subsequent letting conducted by the Department. The bidder has the option of submitting the information again or the bidder may check the following certification statement indicating that the information previously submitted by the bidder is, as of the date of submission, current and accurate. Before checking this certification, the bidder should carefully review its prior submissions to ensure the Certification is correct. If the Bidder checks the Certification, the Bidder should proceed to Form B instructions.

## **CERTIFICATION STATEMENT**

I have determined that the Form A disclosure information previously submitted is accurate, and all forms are hereby incorporated by reference in this bid. Any nec forms or amendments to previously submitted forms are attached to this bid.			
(Bidding Company)			
Signature of Authorized Representative	Date		

## Form A: For bidders who have NOT previously submitted the information requested in Form A

D.

If the bidder is a publicly traded entity subject to Federal 10K reporting, the 10K Report may be submitted to meet the requirements of Form A. If a bidder is a privately held entity that is exempt from Federal 10K reporting, but has more than 400 shareholders, it may submit the information that Federal 10K companies are required to report, and list the names of any person or entity holding any ownership share that is in excess of 5%. If a bidder is not subject to Federal 10K reporting, the bidder must determine if any individuals are required by law to complete a financial disclosure form. To do this, the bidder should answer each of the following questions. A "YES" answer indicates Form A must be completed. If the answer to each of the following questions is "NO", then the NOT APPLICABLE STATEMENT on the second page of Form A must be signed and dated by a person that is authorized to execute contracts for the bidding company. Note: These questions are for assistance only and are not required to be completed.

1.	Does anyone in your organization have a direct or beneficial ownership share of greater than 5% of the bidding entity or parent entity? YES NO
2.	Does anyone in your organization have a direct or beneficial ownership share of less than 5%, but which has a value greater than \$102,600.00? YES NO
3.	Does anyone in your organization receive more than \$102,600.00 of the bidding entity's or parent entity's distributive income? (Note: Distributive income is, for these purposes, any type of distribution of profits. An annual salary is not distributive income.) YES NO
4.	Does anyone in your organization receive greater than 5% of the bidding entity's or parent entity's total distributive income, but which is less than \$102,600.00? YES NO
	(Note: Only one set of forms needs to be completed <u>per person per bid</u> even if a specific individual would require a yes answer to more than one question.)
bidding e authorize	answer to any of these questions requires the completion of Form A. The bidder must determine each individual in the bidding entity or the entity's parent company that would cause the questions to be answered "Yes". Each form must be signed and dated by a person that is ed to execute contracts for your organization. <b>Photocopied or stamped signatures are not acceptable</b> . The person signing can be, but have to be, the person for which the form is being completed. The bidder is responsible for the accuracy of any information provided.
	swer to each of the above questions is "NO", then the <u>NOT APPLICABLE STATEMENT</u> on page 2 of Form A must be signed and dated by that is authorized to execute contracts for your company.
bidding 6	Identifying Other Contracts & Procurement Related Information  Disclosure Form B must be completed for each bid submitted by the entity. Note: Checking the NOT APPLICABLE STATEMENT on Form A does not allow the bidder to ignore Form B. Form B must be end, checked, and dated or the bidder may be considered nonresponsive and the bid will not be accepted.
ongoing	der shall identify, by checking Yes or No on Form B, whether it has any pending contracts (including leases), bids, proposals, or other procurement relationship with any other (non-IDOT) State of Illinois agency. If "No" is checked, the bidder only needs to complete the box on the bottom of Form B. If "Yes" is checked, the bidder must do one of the following:
agency pattached and are	If the bidder did not submit an Affidavit of Availability to obtain authorization to bid, the bidder must list all non-IDOT State of Illinois pending contracts, leases, bids, proposals, and other ongoing procurement relationships. These items may be listed on Form B or on an sheet(s). Do not include IDOT contracts. Contracts with cities, counties, villages, etc. are not considered State of Illinois agency contracts not to be included. Contracts with other State of Illinois agencies such as the Department of Natural Resources or the Capital Development ust be included. Bidders who submit Affidavits of Availability are suggested to use Option II.
"See Affi agency p	: If the bidder is required and has submitted an Affidavit of Availability in order to obtain authorization to bid, the bidder may write or type davit of Availability" which indicates that the Affidavit of Availability is incorporated by reference and includes all non-IDOT State of Illinois bending contracts, leases, bids, proposals, and other ongoing procurement relationships. For any contracts that are not covered by the of Availability, the bidder must identify them on Form B or on an attached sheet(s). These might be such things as leases.
Bidders	Submitting More Than One Bid
	submitting multiple bids may submit one set of forms consisting of all required Form A disclosures and one Form B for use with all bids. Indicate in the space provided below the bid item that contains the original disclosure forms and the bid items which incorporate the forms ence.
	ne bid submitted for letting item contains the Form A disclosures or Certification Statement and the Form B sclosures. The following letting items incorporate the said forms by reference:

## ILLINOIS DEPARTMENT OF TRANSPORTATION

## Form A Financial Information & Potential Conflicts of Interest Disclosure

Contractor Name		
egal Address		
city, State, Zip		
elephone Number	Email Address	Fax Number (if available)
also as of the later water as of the later	in Face in the Continue	50.05 of the III's a Process of Oak
sclosure of the information contained in the CS 500). Vendors desiring to enter into a tential conflict of interest information as a blicly available contract file. This Form intracts. A publicly traded company may requirements set forth in Form A. See	a contract with the State of Illinois specified in this Disclosure Form. A must be completed for bids in early submit a 10K disclosure (or early submit a 10K disclosure)	must disclose the financial information This information shall become part of excess of \$10,000, and for all open-en
•	OSURE OF FINANCIAL INFORM	<u>MATION</u>
Disclosure of Financial Information. Perms of ownership or distributive income s 102,600.00 (60% of the Governor's salary eparate Disclosure Form A for each income FOR INDIVIDUAL (type or print informa	hare in excess of 5%, or an interest as of 7/1/07). (Make copies of this lividual meeting these requireme	which has a value of more than s form as necessary and attach a
FOR INDIVIDUAL (type or print informa	tion)	
NAME:		
ADDRESS		
Type of ownership/distributable inco	me share:	
stock sole proprietorship		other: (explain on separate sheet):
% or \$ value of ownership/distributable i		Other. (explain on separate sheet).
·		
<ol> <li>Disclosure of Potential Conflicts of In octential conflict of interest relationships ap lescribe.</li> </ol>		
(a) State employment, currently or in	the previous 3 years, including cont	ractual employment of services. YesNo
If your answer is yes, please answ	er each of the following questions.	
Are you currently an office Highway Authority?	er or employee of either the Capitol	Development Board or the Illinois Toll YesNo
currently appointed to or e exceeds \$102,600.00, (6)	ed to or employed by any agency employed by any agency of the State 0% of the Governor's salary as of 7 employed and your annual salary.	

3.	If you are currently appointed to or employed by any agency salary exceeds \$102,600.00, (60% of the Governor's salary (i) more than 7 1/2% of the total distributable income of y corporation, or (ii) an amount in excess of the salary of the G	as of 7/1/07) are you entitled to receive your firm, partnership, association or
4.	If you are currently appointed to or employed by any agency salary exceeds \$102,600.00, (60% of the Governor's salary or minor children entitled to receive (i) more than 15% in agg of your firm, partnership, association or corporation, or (ii) a salary of the Governor?	as of 7/1/07) are you and your spouse gregate of the total distributable income
` '	employment of spouse, father, mother, son, or daughter, include previous 2 years.	ding contractual employment for services
	answer is yes, please answer each of the following questions.	YesNo
1.	Is your spouse or any minor children currently an officer or en Board or the Illinois Toll Highway Authority?	nployee of the Capitol Development YesNo
	Is your spouse or any minor children currently appointed to or of Illinois? If your spouse or minor children is/are currently appeared of the State of Illinois, and his/her annual salary excording salary as of 7/1/07) provide the name of the spour of the State agency for which he/she is employed and his/her annual salary excording the State agency for which he/she is employed and his/her annual salary excording the state agency for which he/she is employed and his/her annual salary excording the salary excor	ppointed to or employed by any seeds \$102,600.00, (60% of the use and/or minor children, the name
	If your spouse or any minor children is/are currently appointed State of Illinois, and his/her annual salary exceeds \$102,600 as of 7/1/07) are you entitled to receive (i) more than 71/2% of firm, partnership, association or corporation, or (ii) an amo Governor?	.00, (60% of the salary of the Governor of the total distributable income of your
	If your spouse or any minor children are currently appointed State of Illinois, and his/her annual salary exceeds \$102,600.07/1/07) are you and your spouse or any minor children entitled aggregate of the total distributable income from your firm, part (ii) an amount in excess of 2 times the salary of the Governor?	00, (60% of the Governor's salary as of d to receive (i) more than 15% in the nership, association or corporation, or
		Yes No
unit of I	e status; the holding of elective office of the State of Illinois, the ocal government authorized by the Constitution of the State ocurrently or in the previous 3 years.	
` '	nship to anyone holding elective office currently or in the previous	ous 2 years; spouse, father, mother, YesNo
America of the S	tive office; the holding of any appointive government office of to a, or any unit of local government authorized by the Constitution State of Illinois, which office entitles the holder to compensation charge of that office currently or in the previous 3 years.	on of the State of Illinois or the statues
. ,	nship to anyone holding appointive office currently or in the predaughter.	evious 2 years; spouse, father, mother, YesNo
(g) Employ	ment, currently or in the previous 3 years, as or by any register	ered lobbyist of the State government. YesNo

(h) Relationship to anyone who is or was a registered lobbyist in the previous 2 years; spouse, father, mother, son, or daughter.  YesNo				
(i) Compensated employment, currently or in the previous 3 years, by any registered election committee registered with the Secretary of State or any county clerk of the State of Illinois action committee registered with either the Secretary of State or the Federal Board of Election State St	s, or any political ctions.			
(j) Relationship to anyone; spouse, father, mother, son, or daughter; who was a compensated employee in the last 2 years by any registered election or re-election committee registered with the Secretary of State or any county clerk of the State of Illinois, or any political action committee registered with either the Secretary of State or the Federal Board of Elections.				
Yes No	<del></del>			
APPLICABLE STATEMENT				
This Disclosure Form A is submitted on behalf of the INDIVIDUAL named on previous	page.			
Completed by:				
Signature of Individual or Authorized Representative Date				
NOT APPLICABLE STATEMENT				
I have determined that no individuals associated with this organization meet the criteria that would require the completion of this Form A.				
This Disclosure Form A is submitted on behalf of the CONTRACTOR listed on the previous page.				
Signature of Authorized Representative	Date			

## ILLINOIS DEPARTMENT OF TRANSPORTATION

## Form B Other Contracts & Procurement Related Information Disclosure

Contractor Name			
Legal Address			
City, State, Zip			
Telephone Number	Email Address	Fax Number (if available	<b>(</b> )
Disclosure of the information conta	ined in this Form is required by the	Section 50-35 of the Illinois P	rocurement
Act (30 ILCS 500). This information	n shall become part of the publicly	available contract file. This For	m B must
be completed for bids in excess of	\$10,000, and for all open-ended c	ontracts.	
DISCLOSURE OF	OTHER CONTRACTS AND PRO	CUREMENT RELATED INFOR	MATION
has any pending contracts (included any other State of Illinois agency:	& Procurement Related Informating leases), bids, proposals, or other Yes No ally needs to complete the signature.	her ongoing procurement relation	nship with
	each such relationship by showing number (attach additional pages a		
	THE FOLLOWING STATEMENT	MUST BE CHECKED	
	Signature of Authorized Repre	esentative	Date

## **SPECIAL NOTICE TO CONTRACTORS**

The following requirements of the Illinois Department of Human Rights' Rules and Regulations are applicable to bidders on all construction contracts advertised by the Illinois Department of Transportation:

## **CONSTRUCTION EMPLOYEE UTILIZATION PROJECTION**

- (a) All bidders on construction contracts shall complete and submit, along with and as part of their bids, a Bidder's Employee Utilization Form (Form BC-1256) setting forth a projection and breakdown of the total workforce intended to be hired and/or allocated to such contract work by the bidder including a projection of minority and female employee utilization in all job classifications on the contract project.
- (b) The Department of Transportation shall review the Employee Utilization Form, and workforce projections contained therein, of the contract awardee to determine if such projections reflect an underutilization of minority persons and/or women in any job classification in accordance with the Equal Employment Opportunity Clause and Section 7.2 of the Illinois Department of Human Rights' Rules and Regulations for Public Contracts adopted as amended on September 17, 1980. If it is determined that the contract awardee's projections reflect an underutilization of minority persons and/or women in any job classification, it shall be advised in writing of the manner in which it is underutilizing and such awardee shall be considered to be in breach of the contract unless, prior to commencement of work on the contract project, it submits revised satisfactory projections or an acceptable written affirmative action plan to correct such underutilization including a specific timetable geared to the completion stages of the contract.
- (c) The Department of Transportation shall provide to the Department of Human Rights a copy of the contract awardee's Employee Utilization Form, a copy of any required written affirmative action plan, and any written correspondence related thereto. The Department of Human Rights may review and revise any action taken by the Department of Transportation with respect to these requirements.



Contract No. 97324
MADISON County
Section 06-00056-01-WR (Highland)
Project CMM-M-5011(246)
Route FAU 8852 (Poplar Street)
District 8 Construction Funds

PART I. IDENTIFICATION	
Dept. Human Rights #	Duration of Project:
Name of Bidder:	

## PART II. WORKFORCE PROJECTION

A. The undersigned bidder has analyzed minority group and female populations, unemployment rates and availability of workers for the location in which this contract work is to be performed, and for the locations from which the bidder recruits employees, and hereby submits the following workforce projection including a projection for minority and female employee utilization in all job categories in the workforce to be allocated to this contract:

TABLE A

TABLE B

TOTAL Workforce Projection for Contract CURRENT EMPLOYEES								S									
													IGNED				
JOB	TOT	TAI	MINORITY EMPLOYEES *OTHER			APPREN- ON THE JOB			TO CONTRACT TOTAL MINOR			DITV					
CATEGORIES	EMPLO		BI /	ACK	HISPANIC		_				AINEES		TOTAL EMPLOYEES		EMPLO		
CATEGORIES	M	F	M	F	M	F	M	F	M	F	M	F		M	F	M	F
OFFICIALS (MANAGERS)																	
SUPERVISORS																	
FOREMEN																	
CLERICAL																	
EQUIPMENT OPERATORS																	
MECHANICS																	
TRUCK DRIVERS																	
IRONWORKERS																	
CARPENTERS																	
CEMENT MASONS																	
ELECTRICIANS																	
PIPEFITTERS, PLUMBERS																	
PAINTERS																	
LABORERS, SEMI-SKILLED																	
LABORERS, UNSKILLED																	
TOTAL																	

TABLE C									
TOTAL Training Projection for Contract									
EMPLOYEES	_	TAL	DI.	V C IV	*OTHER				
IIN	EMPL	OYEES	BL	ACK	HISP	ANIC	MINOR.		
TRAINING	M	F	M	F	M	F	M	F	
APPRENTICES									
ON THE JOB TRAINEES									

<sup>\*</sup>Other minorities are defined as Asians (A) or Native Americans (N).

Please specify race of each employee shown in Other Minorities column.

Note: See instructions on the next page

FOR DEPARTMENT USE ONLY

Contract No. 97324
MADISON County
Section 06-00056-01-WR (Highland)
Project CMM-M-5011(246)
Route FAU 8852 (Poplar Street)
District 8 Construction Funds

## PART II. WORKFORCE PROJECTION - continued

B.	Included in "Total Employees" under Table A is the total number of <b>new hires</b> that would be employed in the event the undersigned bidder is awarded this contract.
	The undersigned bidder projects that: (number) new hires would be recruited from the area in which the contract project is located; and/or (number) new hires would be recruited from the area in which the bidder's principal
	office or base of operation is located.
C.	Included in "Total Employees" under Table A is a projection of numbers of persons to be employed directly by the undersigned bidder as well as a projection of numbers of persons to be employed by subcontractors.
	The undersigned bidder estimates that (number) persons will be directly employed by the prime contractor and that (number) persons will be employed by subcontractors.
PART	II. AFFIRMATIVE ACTION PLAN
A.	The undersigned bidder understands and agrees that in the event the foregoing minority and female employee utilization projection included under <b>PART II</b> is determined to be an underutilization of minority persons or women in any job category, and in the event that the undersigned bidder is awarded this contract, he/she will, prior to commencement of work, develop and submit a written Affirmative Action Plan including a specific timetable (geared to the completion stages of the contract) whereby deficiencies in minority and/or female employee utilization are corrected. Such Affirmative Action Plan will be subject to approval by the contracting agency and the <b>Department of Human Rights</b> .
B.	The undersigned bidder understands and agrees that the minority and female employee utilization projection submitted herein, and the goals and timetable included under an Affirmative Action Plan if required, are deemed to be part of the contract specifications.
Comp	any Telephone Number
Addre	
	NOTICE REGARDING SIGNATURE
	The Bidder's signature on the Proposal Signature Sheet will constitute the signing of this form. The following signature block needs to be completed only if revisions are required.
	Signature:          Date:
Instruct	ons: All tables must include subcontractor personnel in addition to prime contractor personnel.
Table A	Include both the number of employees that would be hired to perform the contract work and the total number currently employed (Table B) that will be allocated to contract work, and include all apprentices and on-the-job trainees. The "Total Employees" column should include all employees including all minorities, apprentices and on-the-job trainees to be employed on the contract work.
Table B	- Include all employees currently employed that will be allocated to the contract work including any apprentices and on-the-job trainees currently employed.
Table C	- Indicate the racial breakdown of the total apprentices and on-the-job trainees shown in Table A.

## **ADDITIONAL FEDERAL REQUIREMENTS**

In addition to the Required Contract Provisions for Federal-Aid Construction Contracts (FHWA 1273), all bidders make the following certifications.

- A. By the execution of this proposal, the signing bidder certifies that the bidding entity has not, either directly or indirectly, entered into any agreement, participated in any collusion, or otherwise taken any action, in restraint of free competitive bidding in connection with the submitted bid. This statement made by the undersigned bidder is true and correct under penalty of perjury under the laws of the United States.
- B. <u>CERTIFICATION</u>, <u>EQUAL EMPLOYMENT OPPORTUNITY</u>:

1.	Have you participated in any previous contracts or subcontracts subject to the equal opportunity clause. YES NO
2.	If answer to #1 is yes, have you filed with the Joint Reporting Committee, the Director of OFCC, any Federal agency, or the former President's Committee on Equal Employment Opportunity, all reports due under the applicable filing requirements of those organizations? YES NO

Contract No. 97324
MADISON County
Section 06-00056-01-WR (Highland)
Project CMM-M-5011(246)
Route FAU 8852 (Poplar Street)
District 8 Construction Funds

## PROPOSAL SIGNATURE SHEET

The undersigned bidder hereby makes and submits this bid on the subject Proposal, thereby assuring the Department that all requirements of the Invitation for Bids and rules of the Department have been met, that there is no misunderstanding of the requirements of paragraph 3 of this Proposal, and that the contract will be executed in accordance with the rules of the Department if an award is made on this bid.

	Firm Name	
(IF AN INDIVIDUAL)	Signature of Owner	
	Firm Name	
	Ву	
(IF A CO-PARTNERSHIP)		
		Name and Address of All Members of the Firm:
_		
	•	
	Ву	Signature of Authorized Representative
(IF A CORPORATION)		•
		Typed or printed name and title of Authorized Representative
	Attent	
(III	Attest	Signature
(IF A JOINT VENTURE, USE THIS SECTION FOR THE MANAGING PARTY AND THE	Business Address	
SECOND PARTY SHOULD SIGN BELOW)		
	Corporate Name	
(IE A JOINT VENTURE)	Ву	Signature of Authorized Representative
(IF A JOINT VENTURE)		Signature of Authorized Representative
		Typed or printed name and title of Authorized Representative
	Attest	Signature
	Business Address	•
	200000 / (001000	
If more than two parties are in the joint venture,	please attach an addit	ional signature sheet.



## Division of Highways Proposal Bid Bond

(Effective November 1, 1992)

	Item No.
	Letting Date
KNOW ALL MEN BY THESE PRESENTS, That We	
as PRINCIPAL, and	
	as SURETY, are
Article 102.09 of the "Standard Specifications for Road and Bridge	NOIS in the penal sum of 5 percent of the total bid price, or for the amount specified in the Construction" in effect on the date of invitation for bids, whichever is the lesser sum, well tent of which we bind ourselves, our heirs, executors, administrators, successors and assigns.
	S SUCH, That Whereas, the PRINCIPAL has submitted a bid proposal to the STATE OF the improvement designated by the Transportation Bulletin Item Number and Letting Date
the bidding and contract documents, submit a DBE Utilization Plar PRINCIPAL shall enter into a contract in accordance with the term coverages and providing such bond as specified with good and sufflabor and material furnished in the prosecution thereof; or if, in the into such contract and to give the specified bond, the PRINCIPAL	proposal of the PRINCIPAL; and if the PRINCIPAL shall, within the time and as specified in that is accepted and approved by the Department; and if, after award by the Department, the is of the bidding and contract documents including evidence of the required insurance ficient surety for the faithful performance of such contract and for the prompt payment of event of the failure of the PRINCIPAL to make the required DBE submission or to enter pays to the Department the difference not to exceed the penalty hereof between the amount Department may contract with another party to perform the work covered by said bid hall remain in full force and effect.
Surety shall pay the penal sum to the Department within fifteen (15	has failed to comply with any requirement as set forth in the preceding paragraph, then by days of written demand therefor. If Surety does not make full payment within such mount owed. Surety is liable to the Department for all its expenses, including attorney's or in part.
In TESTIMONY WHEREOF, the said PRINCIPAL and the s	said SURETY have caused this instrument to be signed by their respective officers this A.D.,
PRINCIPAL	SURETY
(Company Name)	(Company Name)
By:	By:
(Signature & Title)	(Signature of Attorney-in-Fact)
Notar	y Certification for Principal and Surety
STATE OF ILLINOIS, COUNTY OF	
I,	, a Notary Public in and for said County, do hereby certify that
and	
(Insert names of individua	als signing on behalf of PRINCIPAL & SURETY)
	se names are subscribed to the foregoing instrument on behalf of PRINCIPAL and and respectively, that they signed and delivered said instrument as their free and voluntary
Given under my hand and notarial seal this day	y of, A.D
My commission expires	
	Notary Public
	the Principal may file an Electronic Bid Bond. By signing below the Principal is ensuring pal and Surety are firmly bound unto the State of Illinois under the conditions of the bid
Electronic Bid Bond ID# Company/Bidder Name	Signature and Title

#### PROPOSAL ENVELOPE



### **PROPOSALS**

for construction work advertised for bids by the Illinois Department of Transportation

Item No.	Item No.	Item No.

#### Submitted By:

Name:	
Address:	
Phone No.	

Bidders should use an IDOT proposal envelope or affix this form to the front of a 10" x 13" envelope for the submittal of bids. If proposals are mailed, they should be enclosed in a second or outer envelope addressed to:

Engineer of Design and Environment - Room 326 Illinois Department of Transportation 2300 South Dirksen Parkway Springfield, Illinois 62764

#### **NOTICE**

Individual bids, including Bid Bond and/or supplemental information if required, should be securely stapled.

# CONTRACTOR OFFICE COPY OF CONTRACT SPECIFICATIONS

#### **NOTICE**

None of the following material needs to be returned with the bid package unless the special provisions require documentation and/or other information to be submitted.

Contract No. 97324
MADISON County
Section 06-00056-01-WR (Highland)
Project CMM-M-5011(246)
Route FAU 8852 (Poplar Street)
District 8 Construction Funds



## Illinois Department of Transportation

#### **NOTICE TO BIDDERS**

- 1. TIME AND PLACE OF OPENING BIDS. Sealed proposals for the improvement described herein will be received by the Department of Transportation at the Harry R. Hanley Building, 2300 South Dirksen Parkway, in Springfield, Illinois until 10:00 o'clock a.m., January 18, 2008. All bids will be gathered, sorted, publicly opened and read in the auditorium at the Department of Transportation's Harry R. Hanley Building shortly after the 10:00 a.m. cut off time.
- **2. DESCRIPTION OF WORK**. The proposed improvement is identified and advertised for bids in the Invitation for Bids as:

Contract No. 97324
MADISON County
Section 06-00056-01-WR (Highland)
Project CMM-M-5011(246)
Route FAU 8852 (Poplar Street)
District 8 Construction Funds

0.54 mile widening and resurfacing including storm sewers, pavement removal, combination curb and gutter, HMA binder and surface, PCC driveways and sidewalks on Poplar Street between Broadway to Sixth Street and construction of a modern roundabout at the intersection of Broadway and Poplar Street all in Highland.

- 3. INSTRUCTIONS TO BIDDERS. (a) This Notice, the invitation for bids, proposal and letter of award shall, together with all other documents in accordance with Article 101.09 of the Standard Specifications for Road and Bridge Construction, become part of the contract. Bidders are cautioned to read and examine carefully all documents, to make all required inspections, and to inquire or seek explanation of the same prior to submission of a bid.
  - (b) State law, and, if the work is to be paid wholly or in part with Federal-aid funds, Federal law requires the bidder to make various certifications as a part of the proposal and contract. By execution and submission of the proposal, the bidder makes the certification contained therein. A false or fraudulent certification shall, in addition to all other remedies provided by law, be a breach of contract and may result in termination of the contract.
- 4. AWARD CRITERIA AND REJECTION OF BIDS. This contract will be awarded to the lowest responsive and responsible bidder considering conformity with the terms and conditions established by the Department in the rules, Invitation for Bids and contract documents. The issuance of plans and proposal forms for bidding based upon a prequalification rating shall not be the sole determinant of responsibility. The Department reserves the right to determine responsibility at the time of award, to reject any or all proposals, to readvertise the proposed improvement, and to waive technicalities.

By Order of the Illinois Department of Transportation

Milton R. Sees, Secretary

BD 351 (Rev. 01/2003)

## INDEX FOR SUPPLEMENTAL SPECIFICATIONS AND RECURRING SPECIAL PROVISIONS

#### Adopted January 1, 2008

This index contains a listing of SUPPLEMENTAL SPECIFICATIONS and frequently used RECURRING SPECIAL PROVISIONS.

ERRATA Standard Specifications for Road and Bridge Construction (Adopted 1-1-07) (Revised 1-1-08)

#### SUPPLEMENTAL SPECIFICATIONS

Std. Sp	<u>Pec. Sec.</u>	<u>age No.</u>
205	Embankment	. 1
251	Mulch	
253	Planting Woody Plants	. 3
280	Temporary Erosion Control	. 5
443	Reflective Crack Control Treatment	
502	Excavation for Structures	. 9
503	Concrete Structures	. 10
505	Steel Structures	. 11
540	Box Culverts	
633	Removing and Reerecting Guardrail and Terminals	. 13
672	Sealing Abandoned Water Wells	. 14
701	Work Zone Traffic Control and Protection	. 15
838	Breakaway Devices	
1004	Coarse Aggregates	. 17
1020	Portland Cement Concrete	. 18
1022	Concrete Curing Materials	. 20
1042	Precast Concrete Products	. 21
1062	Reflective Crack Control System	. 22
1069	Pole and Tower	. 24
1081	Materials for Planting	. 27
1083	Elastomeric Bearings	
1102	Hot-Mix Asphalt Equipment	

#### RECURRING SPECIAL PROVISIONS

The following RECURRING SPECIAL PROVISIONS indicated by an "X" are applicable to this contract and are included by reference:

	K SI	<u>PAGE</u>	<u>= NO.</u>
1 >	<b>(</b>	Additional State Requirements For Federal-Aid Construction Contracts	
		(Eff. 2-1-69) (Rev. 1-1-07)	31
2 >	ζ 8	Subletting of Contracts (Federal-Aid Contracts) (Eff. 1-1-88) (Rev. 5-1-93)	
$\frac{2}{3}$	<b>〈</b> E	EO (Eff. 7-21-78) (Rev. 11-18-80)	34
4	5	Specific Equal Employment Opportunity Responsibilities	
		Non Federal-Aid Contracts (Eff. 3-20-69) (Rev. 1-1-94)	44
5	F	Required Provisions - State Contracts (Eff. 4-1-65) (Rev. 1-1-07)	49
6	F	Reserved	54
7		Reserved	55
8	ŀ	Haul Road Stream Crossings, Other Temporary Stream Crossings, and	
		In-Stream Work Pads (Eff. 1-2-92) (Rev. 1-1-98)	
9	(	Construction Layout Stakes Except for Bridges (Eff. 1-1-99) (Rev. 1-1-07)	57
10	(	Construction Layout Stakes (Eff. 5-1-93) (Rev. 1-1-07)	60
11	ι	Use of Geotextile Fabric for Railroad Crossing (Eff. 1-1-95) (Rev. 1-1-07)	63
12	5	Subsealing of Concrete Pavements (Eff. 11-1-84) (Rev. 1-1-07)	65
13	H	Hot-Mix Asphalt Surface Removal (Cold Milling) (Eff. 11-1-87) (Rev. 1-1-07)	69
14	F	Pavement and Shoulder Resurfacing (Eff. 2-1-00) (Rev. 1-1-07)	71
15	F	PCC Partial Depth Hot-Mix Asphalt Patching (Eff. 1-1-98) (Rev. 1-1-07)	72
16	F	Patching with Hot-Mix Asphalt Overlay Removal (Eff. 10-1-95) (Rev. 1-1-07)	74
17	F	Polymer Concrete (Eff. 8-1-95) (Rev. 1-1-08)	75
18		PVC Pipeliner (Eff. 4-1-04) (Rev. 1-1-07)	
19	F	Pipe Underdrains (Eff. 9-9-87) (Rev. 1-1-07)	
20	(	Guardrail and Barrier Wall Delineation (Eff. 12-15-93) (Rev. 1-1-97)	79
21	Е	Bicycle Racks (Eff. 4-1-94) (Rev. 1-1-07)	83
22	Т	Femporary Modular Glare Screen System (Eff. 1-1-00) (Rev. 1-1-07)	85
23		Temporary Portable Bridge Traffic Signals (Eff. 8-1-03) (Rev. 1-1-07)	87
24		Work Zone Public Information Signs (Eff. 9-1-02) (Rev. 1-1-07)	89
25	N	Night Time Inspection of Roadway Lighting (Eff. 5-1-96)	90
26	E	English Substitution of Metric Bolts (Eff. 7-1-96)	91
27	Е	English Substitution of Metric Reinforcement Bars (Eff. 4-1-96) (Rev. 1-1-03)	92
28	C	Calcium Chloride Accelerator for Portland Cement Concrete (Eff. 1-1-01)	93
29	(	Quality Control of Concrete Mixtures at the Plant-Single A(Eff. 8-1-00) (Rev. 1-1-04)	94
30	(	Quality Control of Concrete Mixtures at the Plant-Double A (Eff. 8-1-00) (Rev. 1-1-04)	100
31	(	Quality Control/Quality Assurance of Concrete Mixtures(Eff. 4-1-92) (Rev. 1-1-07)	108
•		, , , , , , , , , , , , , , , , , , ,	
LRS 1		Reserved	121
LRS 2		Furnished Excavation (Eff. 1-1-99) (Rev. 1-1-07)	122
LRS 3	oxdot	Work Zone Traffic Control (Eff. 1-1-99) (Rev. 1-1-07)	123
LRS 4	$\boxtimes$	Flaggers in Work Zones (Eff. 1-1-99) (Rev 1-1-07)	124
LRS 5		Contract Claims (Eff. 1-1-02) (Rev. 1-1-07)	125
LRS 6	F	1 Ridding Requirements and Conditions for Contract Proposals (Eff. 1-1-02)	126
LRS 7	┌	Bidding Requirements and Conditions for Material Proposals (Eff. 1-1-02) (Rev. 1-1-03)	132
LRS 8	Ē	Failure to Complete the Work on Time (Eff. 1-1-99)	138
LRS 9	┌	Bituminous Surface Treatments (Eff. 1-1-99)	139
LRS 10	F	Reflective Sheeting Type C (Eff. 1-1-99) (Rev. 1-1-02)	140
LRS 11	一	Employment Practices (Eff. 1-1-99)	141
LRS 12	F	Wages of Employees on Public Works (Eff. 1-1-99) (Rev. 4-1-06)	143
LRS 13	F	Selection of Labor (Eff. 1-1-99)	144
LRS 14	×		145
LRS 15	<u> </u>	Partial Payments (Eff. 1-1-07)	148
	_	-	

# SPECIAL PROVISIONS FAU ROUTE 8852 (POPLAR STREET) SECTION: 06-00056-01-WR PROJECT: M-5011(246) HIGHLAND, ILLINOIS

#### **INDEX TO SPECIAL PROVISIONS**

DESCRIPTION OF WORK	1
EMPLOYMENT SOLICITATION	1
STANDARDS IN THE PLANS	
UTILITIES	2
WORK TO BE PERFORMED BY OTHERS	2
SHOP DRAWINGS	3
CONSTRUCTION STAKING	3
SAFETY AND HEALTH	5
SAFETY AND PROTECTION	5
NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM (NPDES) PERMIT	
JOINT UTILITY LOCATING INFORMATION FOR EXCAVATORS (J.U.L.I.E.)	6
CONSTRUCTION CONTRACTS	7
SEQUENCE OF CONSTRUCTION OPERATIONS	7
TRAFFIC CONTROL PLAN	9
TRENCH BACKFILL	
SEEDING, CLASS 1B	10
AGGREGATE FOR TEMPORARY ACCESS	
INCIDENTAL HOT-MIX ASPHALT SURFACING	11
HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	.12
TEMPORARY RAMPS FOR HOT-MIX ASPHALT SURFACE REMOVAL	.14
WATER MAIN, SIZE SPECIFIED	.14
WATER VALVES, SIZE SPECIFIED	.15
TAPPING VALVES AND SLEEVES 6"	
WATER SERVICE LINE, 1"	.16
CORPORATION STOPS, 1"	17
ADJUSTING SANITARY SEWERS, 8-INCH DIAMETER OR LESS	18
FIRE HYDRANT AND VALVE (SPECIAL)	.18
SEALING EXISTING SEWERS	19
TYPE 3 FRAME AND GRATE	19
MANHOLES, SPECIAL, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	19
INLETS, TYPE A, WITH SALVAGED GRATE	20
INLETS, SPECIAL, NUMBER SPECIFIED	20
JUNCTION CHAMBER, NUMBER SPECIFIED	20
MANHOLES TO BE ADJUSTED (SPECIAL)	.21
CLASS SI CONCRETE (OUTLET)	.21
CONCRETE GUTTER (SPECIAL)	21
COMBINATION CONCRETE CURB AND GUTTER, (SPECIAL)	22

CONCRETE CURB, GUTTER, OR CURB & GUTTER TRANSITIONS	22
TRAFFIC CONTROL AND PROTECTION (DETOUR, NUMBER SPECIFIED)	
TRAFFIC CONTROL AND PROTECTION	23
CONTRACTOR ACCESS	24
SIGN PANEL, TYPE SPECIFIED (SPECIAL)	24
TUBULAR STEEL SIGN SUPPORT - BREAKAWAY	
CONCRETE FOUNDATIONS	
REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	26
REMOVE EXISTING HANDHOLE	27
REMOVE EXISTING CONCRETE FOUNDATION	27
PAINT PAVEMENT MARKING CURB	27
CASING PIPE	27
CONCRETE STEP REMOVAL	28
SANITARY CLEANOUT 6"	
CONCRETE PAVER PAVEMENT	28
LOCATING UNDERGROUND UTILITY	29
STORM SEWER REMOVAL	
CURB STOPS 1"	30
STATUS OF UTILITIES TO BE ADJUSTED	31
REQUIRED CONTRACT PROVISIONS ALL CONTRACTS	32
NPDES CONTRACTOR CERTIFICATION STATEMENT	35
NOTICE OF INTENT	
CODDS OF FWCINFFDS: FFTFD	38

#### INDEX LOCAL ROADS AND STREETS SPECIAL PROVISIONS

<u>LR#</u>	Pg #		Special Provision Title	<b>Effective</b>	<u>Revised</u>
LR SD 12			Slab Movement Detection Device	Nov. 11, 1984	Jan. 1, 2007
LR SD 13			Required Cold Milled Surface Texture	Nov. 1, 1987	Jan. 1, 2007
LR 102			Protests on Local Lettings	Jan. 1, 2007	
, LR 105	43	Х	Cooperation with Utilities	Jan. 1, 1999	Jan. 1, 2007
LR 107-2			Railroad Protective Liability Insurance for Local Lettings	Mar. 1, 2005	Jan. 1, 2006
LR 107-3			Disadvantaged Business Enterprise Participation	Jan. 1, 2007	
LR 107-4	46	Х	Insurance	Feb. 1, 2007	Aug. 1, 2007
LR 108			Combination Bids	Jan. 1, 1994	Mar. 1, 2005
LR 212			Shaping Roadway	Aug. 1, 1969	Jan. 1, 2002
LR 355-1			Asphalt Stabilized Base Course, Road Mix or Traveling Plant Mix	Oct. 1, 1973	Jan. 1, 2007
LR 355-2			Asphalt Stabilized Base Course, Plant Mix	Feb. 2, 1963	Jan. 1, 2007
LR 400-1			Bituminous Treated Earth Surface	Jan. 1, 2008	
LR 400-2			Bituminous Surface Mixture (Class B)	Jan. 1, 2008	
LR 400-3			Pavement Rehabilitation by the Heat-Scarify-Overlay Method	Jan. 1, 2008	
LR 402			Salt Stabilized Surface Course	Feb. 20, 1963	Jan. 1, 2007
LR 403-2			Bituminous Hot Mix Sand Seal Coat	Aug. 1, 1969	Jan. 1, 2007
LR 406			Filling HMA Core Holes with Non-shrink Grout	Jan. 1, 2008	
LR 420		<u></u>	PCC Pavement (Special)	May 12, 1964	Jan. 2, 2007
LR 442			Bituminous Patching Mixtures for Maintenance Use	Jan. 1, 2004	Jun. 1, 2007
LR 451			Crack Filling Bituminous Pavement with Fiber-Asphalt	Oct. 1, 1991	Jan. 1, 2007
LR 503-1			Furnishing Class SI Concrete	Oct. 1, 1973	Jan. 1, 2002
LR 503-2			Furnishing Class SI Concrete (Short Load)	Jan. 1, 1989	Jan. 1, 2002
LR 542			Pipe Culverts, Type (Furnished)	Sep. 1, 1964	Jan. 1, 2007
LR 663			Calcium Chloride Applied	Jun. 1, 1958	Jan. 1, 2007
LR 702			Construction and Maintenance Signs	Jan. 1, 2004	Jun. 1, 2007
LR 1004			Coarse Aggregate for Bituminous Surface Treatment	Jan. 1, 2002	Jan. 1, 2007
LR 1013			Rock Salt (Sodium Chloride)	Aug. 1, 1969	Jan. 1, 2002
LR 1032-1			Penetrating Emulsions	Jan. 1, 2007	Feb. 1, 2007
LR 1032-2			Multigrade Cold Mix Asphal	Jan. 1, 2007	Feb. 1, 2007
LR 1102			Road Mix or Traveling Plan Mix Equipment	Jan. 1, 2007	

#### BDE SPECIAL PROVISIONS For the January 18 and March 7, 2008 Lettings

The following special provisions indicated by an "x" are applicable to this contract. An  $^{\star}$  indicates a new or revised special provision for the letting.

File Name	Pg#		Special Provision Title	<u>Effective</u>	Revised
80099			Accessible Pedestrian Signals (APS)	April 1, 2003	Jan. 1, 2007
80186			Alkali-Silica Reaction for Cast-in-Place Concrete	Aug. 1, 2007	
80108			Asbestos Bearing Pad Removal	Nov. 1, 2003	
72541			Asbestos Waterproofing Membrane and Asbestos Hot-Mix Asphalt	June 1, 1989	Jan. 2, 2007
, 20			Surface Removal	•	•
* 80192			Automated Flagger Assistance Device	Jan. 1, 2008	
80173	47	X	Bituminous Materials Cost Adjustments	Nov. 2, 2006	Jan. 2, 2007
50261			Building Removal-Case I (Non-Friable and Friable Asbestos)	Sept. 1, 1990	Jan. 1, 2007
50481			Building Removal-Case II (Non-Friable Asbestos)	Sept. 1, 1990	Jan. 1, 2007
50491			Building Removal-Case III (Friable Asbestos)	Sept. 1, 1990	Jan. 1, 2007
50531			Building Removal-Case IV (No Asbestos)	Sept. 1, 1990	Jan. 1, 2007
80166	50	X	Cement	Jan. 1, 2007	Nov. 1, 2007
* 80193			Concrete Barrier	Jan. 1, 2008	
80177	*******************************		Digital Terrain Modeling for Earthwork Calculations	April 1, 2007	
80029	53	X	Disadvantaged Business Enterprise Participation	Sept. 1, 2000	Jan. 1, 2007
* 80178	61	Х		April 1, 2007	Jan. 1, 2008
80167			Electrical Service Installation – Traffic Signals	Jan. 1, 2007	
80190			Engineer's Field Office (Long Distance Bill)	Nov. 1, 2007	
80179			Engineer's Field Office Type A	April 1, 2007	
80175			Epoxy Pavement Markings	Jan. 1, 2007	
* 80189	62	X	Equipment Rental Rates	Aug. 2, 2007	Jan. 2, 2008
80180	64	Х	Erosion and Sediment Control Deficiency Deduction	April 1, 2007	
80169			High Tension Cable Median Barrier	Jan. 1, 2007	
* 80194			HMA - Hauling on Partially Completed Full-Depth Pavement	Jan. 1, 2008	
80181			Hot-Mix Asphalt – Field Voids in the Mineral Aggregate	April 1, 2007	
* 80136			Hot-Mix Asphalt Mixture IL-4.75	Nov. 1, 2004	Jan. 1, 2008
* 80195			Hot-Mix Asphalt Mixture IL-9.5L	Jan. 1, 2008	
80109	***************************************		Impact Attenuators	Nov. 1, 2003	Jan. 1, 2007
80110			Impact Attenuators, Temporary	Nov. 1, 2003	Jan. 1, 2007
* 80196			Mast Arm Assembly and Pole	Jan. 1, 2008	
80045			Material Transfer Device	June 15, 1999	Jan. 1, 2007
80165			Moisture Cured Urethane Paint System	Nov. 1, 2006	Jan. 1, 2007
80082			Multilane Pavement Patching	Nov. 1, 2002	
80129			Notched Wedge Longitudinal Joint	July 1, 2004	Jan. 1, 2007
80182			Notification of Reduced Width	April 1, 2007	
* 80069			Organic Zinc-Rich Paint System	Nov. 1, 2001	Jan. 1, 2008
80022	65	Х	Payments to Subcontractors	June 1, 2000	Jan. 1, 2006
80134			Plastic Blockouts for Guardrail	Nov. 1, 2004	Jan. 1, 2007
80119			Polyurea Pavement Marking	April 1, 2004	Jan. 1, 2007
80170			Portland Cement Concrete Plants	Jan. 1, 2007	
80171	67	X	Precast Handling Holes	Jan. 1, 2007	
80015			Public Convenience and Safety	Jan. 1, 2000	
34261			Railroad Protective Liability Insurance	Dec. 1, 1986	Jan. 1, 2006
80157			Railroad Protective Liability Insurance (5 and 10)	Jan. 1, 2006	
80172	69	Х	Reclaimed Asphalt Pavement (RAP)	Jan. 1, 2007	Aug. 1, 2007
			•		

File Name	Pg#		Special Provision Title	<b>Effective</b>	<u>Revised</u>
80183	75	X	Reflective Sheeting on Channelizing Devices	April 1, 2007	
* 80151	76	X	Reinforcement Bars	Nov. 1, 2005	Jan. 2, 2008
80164	***************************************		Removal and Disposal of Regulated Substances	Aug. 1, 2006	Jan. 1, 2007
80184	78	X	Retroreflective Sheeting, Nonreflective Sheeting, and Translucent	April 1, 2007	
			Overlay Film for Highway Signs		
80131	84	X	Seeding	July 1, 2004	Aug. 1, 2007
80152			Self-Consolidating Concrete for Cast-In-Place Construction	Nov. 1, 2005	Jan. 1, 2007
80132	86	X	Self-Consolidating Concrete for Precast Products	July 1, 2004	Jan. 1, 2007
* 80197	88	Х	Silt Filter Fence	Jan. 1, 2008	
80127			Steel Cost Adjustment	April 2, 2004	April 1, 2007
80153			Steel Plate Beam Guardrail	Nov. 1, 2005	Aug. 1, 2007
80191	89	X	Stone Gradation Testing	Nov. 1, 2007	
80143	90	Х	Subcontractor Mobilization Payments	April 2, 2005	
80075			Surface Testing of Pavements	April 1, 2002	Jan. 1, 2007
* 80087	91	Х	Temporary Erosion Control	Nov. 1, 2002	Jan. 1, 2008
80176	92	X	Thermoplastic Pavement Markings	Jan. 1, 2007	
80161			Traffic Signal Grounding	April 1, 2006	Jan. 1, 2007
20338			Training Special Provisions	Oct. 15, 1975	
80185			Type ZZ Retroreflective Sheeting, Nonreflective Sheeting, and	April 1, 2007	
			Translucent Overlay Film for Highway Signs		
80162			Uninterruptable Power Supply (UPS)	April 1, 2006	Jan. 1, 2007
80149			Variable Spaced Tining	Aug. 1, 2005	Jan. 1, 2007
80163			Water Blaster with Vacuum Recovery	April 1, 2006	Jan. 1, 2007
80071	94	X	Working Days	Jan. 1, 2002	

The following special provisions have been deleted from use:

#### 80187 Legal Requirements to be Observed

The following special provisions are in the 2008 Supplemental Specifications and Recurring Special Provisions:

File Name 80168	Special Provision Title Errata for the 2007 Standard Specifications	New Location Supplemental	<u>Effective</u> Jan. 1, 2007	<u>Revised</u> Aug.1, 2007
	Hot-Mix Asphalt Equipment, Spreading and Finishing	Article 1102.3	Jan. 1, 2005	Jan. 1, 2007
80148 80160 80154	Machine Planting Woody Plants Reflective Crack Control Treatment Turf Reinforcement Mat	Section 253 Section 443, Article 1062.04 Section 251	Jan. 1, 2006 April 1, 2006 Nov. 1, 2005	Jan. 1, 2007 Jan. 1, 2007

The following special provisions require additional information from the designer. The additional information needs to be included in a separate document attached to this check sheet. The Project Development and Implementation section will then include the information in the applicable special provision. The Special Provisions are:

- Building Removal-Case I
- Building Removal-Case II
- Building Removal-Case III
- Building Removal-Case IV
- DBE Participation
- Material Transfer Device
- Railroad Protective Liability Insurance
- Training Special Provisions
- Working Days

#### **SPECIAL PROVISIONS**

FAU ROUTE 8852 (POPLAR STREET) SECTION: 06-00056-01-WR PROJECT: M-5011(246) HIGHLAND, ILLINOIS

The following special provisions supplement the "Standard Specifications for Road and Bridge Construction," prepared by the Department of Transportation of the State of Illinois, and adopted January 1, 2007, and the latest edition of the "Illinois Manual on Uniform Traffic Control Devices for Streets and Highways" in effect on the date of the invitation for bids, and the "Supplemental Specifications and Recurring Special Provisions" indicated on the check sheet included herein and the "Standards for Water and Sewer Main Construction in Illinois," Fifth Edition, adopted May, 1996 which apply to and govern the construction of FAU 8852 (POPLAR STREET), Section 06-00056-01-WR, Highland, Illinois and in case of conflict with any part or parts of said specifications, the said special provisions shall take precedence and shall govern.

#### **DESCRIPTION OF WORK**

The proposed improvement consists of furnishing all labor, equipment and materials to construct the following:

Widen and resurface Poplar Street from Broadway to 6<sup>th</sup> Street, a distance of 1,850 feet (0.350 miles). Improvements consist of storm sewers; pavement removal; combination concrete curb and gutter; pavement widening; hot-mix asphalt concrete binder course, leveling binder, and surface course; PCC driveway pavement; PCC sidewalks; and appurtenant construction items. A modern roundabout will be constructed at the intersection of IL 160 (Broadway) and Poplar Street and the existing traffic signals will be removed.

This contract also includes all incidental and collateral work necessary to complete the work in the above-described section according to the plans, specifications and special provisions.

#### **EMPLOYMENT SOLICITATION**

The Contractors shall notify the Department's Agency Ethics Officer if they solicit or intend to solicit for employment any of the Illinois Department of Transportation's employees during any part of the procurement process or during the term of the contract. The Departments Agency Ethics Officer is the Chief Counsel who can be contacted at (217) 782-0691.

#### STANDARDS IN THE PLANS

The Standards with the revision number listed in the Highway Standards on the cover sheet of the plans shall take precedence over the standard revision numbers listed in the special provisions or elsewhere in the contract.

#### UTILITIES

The following utility companies and municipalities are known to have facilities within or in the close proximity to the project limits:

\* City of Highland

\* Verizon

\* Charter Communications

\* Ameren IP

\* Signifies J.U.L.I.E. member

- Water, Sanitary Sewer & Electric

- Telephone

Cable Television

- Gas

Underground facilities, structures and utilities have been located from available surveys and records. Their locations must be considered to be approximate only. It is possible there may be others, the existence of which is not presently known or shown. It is the Contractor's responsibility to determine their existence and exact location and to avoid damage thereto.

#### **WORK TO BE PERFORMED BY OTHERS**

The Contractor's attention is called to the utility facilities within the right of way limits of construction. Unless otherwise provided, the adjustment of the various facilities will be performed by others.

The plans may not show the location of all utility facilities or the manner in which the adjustment will be made. In the event the Contractor desires more detailed information on the location of facilities and the working schedules for adjusting same, it is suggested that it be obtained from the STATUS OF UTILITIES TO BE ADJUSTED included in these special provisions, or the utility company involved. As far as it can be determined, the following utility companies have facilities requiring adjustment:

**Cable Television** 

Charter Communications 210 West Division Street Maryville, IL 62062

Telephone

Verizon Communications 111 East State Street Mascoutah, IL 62258 Water, Sanitary Sewer & Electric

City of Highland 2610 Plaza Drive Highland, Illinois 62249

Gas

Ameren IP 2600 North Center Maryville, IL 6206

It is understood and agreed that the Contractor has taken the foregoing into consideration in submitting his bid, and no additional compensation will be allowed for any delays or inconveniences caused by same.

#### **SHOP DRAWINGS**

The Contractor shall submit shop drawings of the following items according to Articles 1042.03(b) and 105.04 of the "Standard Specifications for Road and Bridge Construction":

Precast Concrete Inlets Precast Concrete Manholes and Manhole Sections Type 3 Frame and Grate Type 8 Grate Type 24 Frame and Grate All Specialty Sign Panel, Type Specified, Specials Gate Valves Fire Hydrants Water Main Pipe and Fittings Water Main "Hot" Tapping Assembly Corporation Stops **Curb Stops** Casing Pipe and Spacers Sanitary tee Cleanout adaptor and threaded cap Concrete pavers

Submit shop drawings for review and approval to:

Director of Public Works City of Highland, Illinois 2610 Plaza Drive Highland, Illinois 62249

A maximum of two reviews by the Engineer will be provided for each shop drawing submittal. If any additional reviews are required, the Contractor shall pay the Engineer for all costs incurred at an hourly rate of \$100.

#### **CONSTRUCTION STAKING**

This work shall consist of construction staking according to Article 105.09 of the "Standard Specifications for Road and Bridge Construction," except as modified herein.

The Local Agency will provide adequate reference points to the centerline of survey and bench marks as shown in the plans and listed herein. Any additional control points set by the Local Agency will be identified in the field to the Contractor and all field notes will be kept in the office of the Resident Engineer.

The Contractor shall provide labor, equipment and material to set all additional stakes for this project, which are needed to establish offset stakes, reference points, and any other horizontal or vertical controls, including supplementary bench marks, necessary to secure a correct layout for the roadway portion of the work.

The Contractor shall be responsible for having the finished work conform to the lines, grades, elevations and dimensions called for in the plans. Any inspection or checking of the Contractor's layout by the Engineer and the acceptance of all or any part of it shall not relieve the Contractor of his/her responsibility to secure the proper dimensions, grades and elevations of the several parts of the work. The Contractor shall exercise care in the preservation of stakes and benchmarks and shall have them reset at his/her expense when any are disturbed.

#### Responsibility of the Local Agency

- Control points referenced to the survey centerline will be provided at intervals not exceeding 1000 feet.
- Bench marks will be established along the project outside of the construction limits lines not exceeding 1000-foot intervals horizontally and 20 feet vertically.
- The Local Agency will locate and reference the centerline of all roads and streets. The centerline of entrances and short street intersection returns will not be located or referenced. Locating the centerline of survey will consist of establishing the centerline of surveys at PC's, PT's and POT's at intervals not exceeding 50 feet.
- Proposed right of way limits will be staked at break points and on tangent at intervals not to exceed 100 feet.
- Slope stakes or construction limits will be set at the limits of construction at intervals not to exceed 50 feet. Depth of cut and/or fill heights and horizontal offset will be referenced to the finish pavement grade at the proposed profile grade line.
- Drainage structures and culverts will be staked by the Local Agency to establish the proposed horizontal and vertical locations for the drainage system.
- At the completion of the grading operations, the Local Agency will set stakes at 25-foot intervals along the edge of pavement. The radius point of intersection corner turning radii will also be staked.
- The Local Agency will accept responsibility for the accuracy of the initial control
  points and stakes as provided herein. The Contractor shall assume full
  responsibility for all dimensions and measurements taken or derived by the
  Contractor from control points or stakes set by the Local Agency. It is not the
  responsibility of the Local Agency, except as provided herein, to check the
  correctness of the Contractor's stakes.

#### Responsibility of the Contractor

- The Contractor shall provide written requests for all staking to be provided by the Local Agency. A minimum 48-hour advance notice will be required prior to the commencement of any requested staking activities.
- The Contractor shall establish from the given survey points and bench marks any additional control points necessary to construct the individual project elements. It is the Contractor's responsibility to tie in centerline control points in order to preserve them during construction operations.

- The Contractor shall provide any additional staking required to assure completion
  of the work in substantial conformance with the plans.
- The Contractor shall be responsible for re-establishing any stakes removed or disturbed by construction operations.
- All work shall be according to normally accepted surveying practices. Field notes shall be kept in standard survey field notebooks and those books shall become the property of the Local Agency at the completion of the project. All notes shall be neat, orderly, and in accepted form.

This work will not be measured separately for payment. The cost incurred by the Contractor in complying with this requirement shall be considered as included in the contract unit prices bid for the various items of work involved and no additional compensation will be allowed.

#### SAFETY AND HEALTH

The Contractor shall be responsible for enforcing all O.S.H.A. Safety and Health Standards pertaining to the construction industry as established by the United States Department of Labor, Occupational Safety and Health Administration. Such standards include, but are not limited to, 29 CFR 1910 and 1926.

#### SAFETY AND PROTECTION

- A. CONTRACTOR shall be responsible for initiating, maintaining and supervising all safety and precautions and programs in connection with the Work. CONTRACTOR shall take all necessary precautions for the safety of, and shall provide the necessary protection to prevent damage, injury or loss to:
  - 1. All employees on the work and other persons and organizations who may be affected thereby;
  - 2. All the Work and materials and equipment to be incorporated therein, whether in storage on or off the site; and
  - 3. Other property at the site adjacent thereto, including trees, shrubs, lawns, walks, pavements, roadways, structures, utilities and underground facilities not designated for removal, relocation or replacement in the course of construction.

CONTRACTOR shall comply with all applicable laws and regulations of any public body having jurisdiction for the safety of persons and property or to protect them from damage, injury or loss; and shall erect and maintain all necessary safeguards for such safety and protection. CONTRACTOR shall notify owners of adjacent property and of underground facilities and utility owners when prosecution of the Work may affect them and shall cooperate with them in the protection, removal, relocation and replacement of their property. All damage, injury or loss to any property referred to in paragraph 2. or 3. caused, directly or indirectly, in whole or in part, by CONTRACTOR, any Subcontractor, Supplier or any other person or

organization directly or indirectly employed by any of them to perform or furnish any of the Work or anyone for whose acts either of them may be liable, shall be remedied by CONTRACTOR (except damage or loss attributable to the fault of Drawings or Specifications or to the acts or omissions of OWNER or ENGINEER or anyone employed by either of them or anyone for acts either of them may be liable, and not attributable, directly or indirectly, in whole or in part, to the fault or negligence of CONTRACTOR). CONTRACTOR's duties and responsibilities for the safety and protection of the Work shall continue until such time as all the Work is completed and ENGINEER has issued a notice to OWNER and CONTRACTOR that the Work is acceptable (except as otherwise expressly provided in connection with Substantial Completion).

- B. CONTRACTOR shall designate a responsible representative at the site whose duty shall be the prevention of accidents. This person shall be CONTRACTOR's superintendent, unless otherwise designated in writing by CONTRACTOR to OWNER.
- C. In EMERGENCIES affecting the safety or protection of persons or the Work or property at the site or adjacent thereto, CONTRACTOR, without special instructions or authorization from ENGINEER or OWNER, is obligated to act to prevent threatened damage, injury or loss. CONTRACTOR shall give ENGINEER prompt, written notice if CONTRACTOR believes that any significant changes in the Work or variations from the Contract Documents have been caused thereby. If ENGINEER determines that a change in the Contract Documents is required because of the action taken in response to an emergency, a Work Directive Change or Change Order will be issued to document the consequences of the changes or variations.

#### NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM (NPDES) PERMIT

The Contractor and Owner will be required to complete the attached Notice of Intent (NOI) form and the Contractor's Certification Statement, in compliance with the NPDES Phase II guidelines. These forms shall be completed at the pre-construction meeting. Work may commence 30 days after the NOI form is submitted to the Illinois Environmental Protection Agency for the purpose of obtaining a General Construction Permit.

The Storm Water Pollution Prevention Plan, the General Permit, and the Contractor's Certification Statement must be kept on site during working hours. Compliance with this special provision shall be considered as included in the contract unit prices for the various items of work involved and no additional compensation will be allowed.

#### JOINT UTILITY LOCATING INFORMATION FOR EXCAVATORS (J.U.L.I.E.)

This work shall be done according to Article 107.31 of the "Standard Specifications for Road and Bridge Construction."

Because a minimum of 48 hours advance notice is required for notification to utilities, the Contractor will be required to give the Resident Engineer 96 hours notice, in writing, for a specific area prior to beginning any excavation.

Locations of proposed signposts, guardrail, sign, light, or signal foundations, etc., shall be staked and then notice provided as above.

If any of the location markers placed by a utility company in conformance with this procedure is destroyed by Contractor operations, the Contractor shall immediately notify the utility owner and bear the cost of remarking the facilities at his own cost and expense. Compliance with this special provision shall be considered as included in the unit bid prices of the contract and no additional compensation will be allowed for any costs incurred.

Location information is provided as follows:

COUNTY: Madison TOWNSHIP: Saline

SECTIONS: Section 4, T.3 N., R.5 W., 3rd P.M.,

Section 5, T.3 N., R.5 W., 3rd P.M., Section 32, T.4 N., R.5 W., 3rd P.M., & Section 33, T.4 N., R.5 W., 3rd P.M.,

#### **CONSTRUCTION CONTRACTS**

The successful bidder, as a condition of this contract, must submit evidence that he has conducted a pre-job conference with his sub-contractors and their employees, or the employees' duly recognized representatives and union officials, to determine employee jurisdiction, job assignment and work schedules. This requirement is to promote industrial harmony and to eliminate work stoppages and jurisdictional disputes. Said pre-job conference shall be conducted at least fourteen (14) days prior to the commencement of any construction.

#### SEQUENCE OF CONSTRUCTION OPERATIONS

The Contractor shall conduct his work within the approved Sequence of Construction Operations at all times. The work shall be done in a manner that will minimize the inconvenience to local traffic.

The Contractor shall conduct his operations to insure local access to all properties throughout the project limits according to Article 107.09 and Section 701 and 703 of the "Standard Specifications for Road and Bridge Construction." If required, Type I, Type II or vertical barricades shall be used to channel traffic from the following locations to the adjoining side streets or private entrances. The number required shall be determined by the Engineer during construction.

The Contractor shall note the number and locations of the across road storm sewers and their effect on maintaining local access to all properties throughout the project limits.

Unless provided for in the plans, the Contractor will not be permitted to close any road entirely unless approved by the Engineer. All non-State route road closures must be approved in advance by the City of Highland Public Works Department. Other than the closure detailed in the plans, IL Route 160 shall not be closed. The Contractor shall notify the City of Highland Fire and Police Departments and the Illinois State Police at least 48 hours prior any road closure.

In order to insure access with minimal inconvenience to local traffic, the following sequence of operations is suggested.

#### SEQUENCE OF CONSTRUCTION OPERATIONS

During construction, the Contractor will be required to restore access to all properties affected by this work at the end of each working day. AGGREGATE FOR TEMPORARY ACCESS will be used for this purpose (see special provisions).

The Contractor will not be allowed to begin subsequent construction operations until the preceding work is completed. Subsequent operations should begin as soon as progress on previous operations will allow. The construction sequence shall be compressed as much as possible to minimize the inconvenience to local traffic.

Unless authorized by the Engineer, the Contractor shall complete the construction in the following suggested sequence:

#### ROUNDABOUT CONSTRUCTION

Construct the storm sewer from Lindenthal Creek to Lemon and 9<sup>th</sup> Streets. Close Poplar Street from Poplar Drive to Main Street, construct temporary pavement markings, erect temporary signs, detour IL Route 160 and Poplar Street traffic as indicated in the plans and remove the existing traffic signals. Construct the approximately 80% of the roundabout while maintaining Broadway through traffic. Do not construct the surface course.

Mill and level the Broadway approaches without closing Broadway. Reconfigure temporary pavement markings and then shift Broadway traffic onto the north half of the roundabout maintaining Broadway through traffic. Construct the remainder of the roundabout. <u>Do not construct the surface course.</u>

Remove temporary traffic control pavement markings and apply temporary roundabout temporary pavement markings. Open the roundabout and return Poplar Street and IL Route 160 traffic to their marked routes. Install temporary IL 160 signs as necessary. After opening the roundabout, remove all temporary incidental bituminous surfacing and construct the remaining splitter islands.

#### POPLAR STREET WIDENING AND RESURFACING

Construct the storm sewer, widen, mill, and level Poplar Street from Main Street to 34+00. Widen, mill and level any remaining pavement on Broadway. Construct surface course throughout the project. Apply permanent pavement markings.

Seeding operations shall be completed as soon as practicable to minimize erosion potential. TEMPORARY EROSION CONTROL SEEDING will be paid for according to Section 280 of the "Standard Specifications for Road and Bridge Construction."

The Contractor may submit an alternate sequence of operations and traffic control plan that would expedite construction and still maintain traffic control. Any and all changes to these plans must be submitted in writing and approved in advance by the Engineer. No additional compensation will be allowed if alternate plans are approved.

#### TRAFFIC CONTROL PLAN

Traffic control shall be according to the applicable sections of the "Standard Specifications for Road and Bridge Construction," the applicable guidelines contained in the "Illinois Manual on Uniform Traffic Control Devices for Streets and Highways," these special provisions, and any special details and Highway Standards contained herein and in the plans.

At the preconstruction meeting, the Contractor shall furnish the name of the individual in his direct employ who is responsible for the installation and maintenance of the traffic control for this project. If the actual installation and maintenance are to be accomplished by the sub-contractor, consent shall be requested of the Engineer at the time of the preconstruction meeting according to Article 108.01 of the "Standard Specifications for Road and Bridge Construction." This shall not relieve the Contractor of the foregoing requirement for a responsible individual in his direct employ. The Department will provide the Contractor the name of its representative who will be responsible for the observation of the Traffic Control Plan.

The Contractor shall furnish, erect, maintain and remove all warning signs, flags, barricades and lights according to Article 107.14 and Sections 701 and 703 of the "Standard Specifications for Road and Bridge Construction," the latest edition of the "Manual of Uniform Traffic Control Devices for Construction and Maintenance Operations" and/or as directed by the Engineer.

Any additional cost to the Contractor due to furnishing, erecting, maintaining and removing all warning signs, flags, barricades and lights as required by the Special Provisions, Traffic Control Standards, Articles 107.14 and Sections 701 and 703 of the "Standard Specifications for Road and Bridge Construction," the "Manual of Uniform Traffic Control Devices for Construction and Maintenance Operations," or as directed by the Engineer will be considered incidental to the various items of work involved and no additional compensation will be allowed, except as described herein.

Special attention is called to Articles 107.09 and 107.14 and Sections 701 and 703 of the "Standard Specifications for Road and Bridge Construction" and the following Highway Standards relating to traffic control:

701301

701311

701331

701501

701801

701901

The Contractor shall maintain access for local and emergency vehicles at all times.

In addition, the following special provision(s) will also govern traffic control for this project:

SEQUENCE OF CONSTRUCTION OPERATIONS TRAFFIC CONTROL AND PROTECTION, DETOUR CONTRACTOR ACCESS

#### TRENCH BACKFILL

This work shall be constructed according to Section 208 of the "Standard Specifications for Road and Bridge Construction," except as modified herein:

Article 208.02 "Materials" shall be changed to require the use of Coarse Aggregate only, as specified in Article 1004.05 of the "Standard Specifications for Road and Bridge Construction," and that the coarse aggregate gradation shall be CA 11. Fine Aggregate will not be allowed, except as follows:

Fine aggregate will be required within 2-feet of all gas mains and gas service lines that are exposed during storm sewer construction operations. The fine aggregate gradation shall be FA6 according to Article 1003.04 of the "Standard Specifications for Road and Bridge Construction."

Trench backfill material shall be compacted according to Method 1, as specified in Article 550.07(a) of the "Standard Specifications for Road and Bridge Construction."

This work will be paid for at the contract unit price per cubic yard for TRENCH BACKFILL, measured as specified in Article 208.03 of the "Standard Specifications for Road and Bridge Construction" as modified herein and no additional compensation will be allowed.

#### SEEDING, CLASS 1B

This work shall consist of preparing the seed bed, and furnishing, transporting and placing the seed, fertilizer and mulch required to restore all disturbed earth surfaces according to Sections 250 and 251 of the "Standard Specifications for Road and Bridge Construction."

The Contractor shall guarantee a minimum of 90 percent uniform growth over the entire seeded areas(s). Areas not sustaining 90 percent uniform growth shall be interseeded or reseeded, as determined by the Engineer, at no additional cost.

This work will be measured according to Sections 250 and 251 of the "Standard Specifications for Road and Bridge Construction," except as specified herein and paid for at the contract unit price per acre for SEEDING, CLASS 1B.

#### AGGREGATE FOR TEMPORARY ACCESS

This work is included in the contract for the purpose of providing surfacing for temporary access on either the mainline, side streets, and/or driveway entrances. This item shall only be used when authorized or directed by the Engineer. Said surfacing may be deleted entirely or used on multiple occasions.

The aggregate material for temporary access shall be coarse aggregate, Type B Gradation CA 6 as specified in Section 1004 of the "Standard Specifications for Road and Bridge Construction."

Aggregate for temporary access may be placed by tailgating and blading. Compaction shall be provided to the satisfaction of the Engineer. Included with this item of work shall be any interim maintenance that may be required and as directed by the Engineer. At such time as the aggregate is no longer needed, and when approved by the Engineer, the Contractor shall remove and satisfactorily dispose of the material beyond the limits of construction.

The work, including all labor, equipment and materials necessary to furnish, install, maintain, remove and dispose of the temporary aggregate surface will be paid for at the contract unit price per ton for AGGREGATE FOR TEMPORARY ACCESS based upon weight tickets furnished by the supplier, and no additional compensation will be allowed.

#### INCIDENTAL HOT-MIX ASPHALT SURFACING

This work shall consist of the preparation of the base, the application of bituminous priming material and aggregate, and the construction of hot-mix asphalt (HMA) surface on a prepared base at the locations shown on the plans according to Section 408 the "Standard Specifications for Road and Bridge Construction."

Bituminous prime coat and prime coat aggregate are required, but will not be measured separately for payment.

This work will be paid for at the contract unit price per ton for INCIDENTAL HOT-MIX ASPHALT SURFACING, which price shall include the bituminous priming material and aggregate for covering the prime coat, and no additional compensation will be allowed.

#### HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH

This work shall consist of removing hot-mix asphalt (HMA) surfaces to the limits specified on the plans according to Section 440 of the "Standard Specifications for Road and Bridge Construction," except as modified herein.

The cuttings from the HMA surface removal shall become the property of the Contractor and their salvage value shall be reflected in the contract unit price for HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH.

Concrete patches that have to be partially removed will be paid for as HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH, and no additional compensation will be allowed.

Manholes and valve vaults which are exposed by the HMA surface removal and transverse cuts at the end of the day that are more than 1/2 inch deep shall be tamped with a cold-mix asphalt. The cost of this temporary taper shall be included in the cost of HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH, and no additional compensation will be allowed.

When the removal width of the machine is less than the width of the lane, the operations shall be planned such that after the bituminous surface for a portion of the lane has been removed the remaining portion shall have been removed by the end of the day so that the two passes begin and terminate even with each other.

If the depth of removal is greater than 1/2 inch, the removal shall be tapered at the terminating point at the end of each day's operation when the lane is open to traffic.

All materials, equipment, and labor necessary to complete the work and maintenance of the tapers as specified above will be included in the contract unit bid price for HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH.

After any HMA surface removal operation has been performed, the Contractor shall erect special "ROUGH GROOVED SURFACE" signs, as shown on the attached sheet, in advance of the construction zone in both directions, if applicable. In addition, these signs shall also be erected along major side streets in advance of the construction zone.

These signs shall remain in place until they are no longer applicable as determined by the Engineer. They shall then be removed by the Contractor and become his property.

The cost of furnishing, erecting, maintaining, and removing these signs will not be paid for separately, but shall be considered in the cost of the HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH.

At the end of each day's work, temporary pavement marking line shall be in place on the planed surface according to Section 703 of the "Standard Specifications for Road and Bridge Construction." This work will be paid for at the contract unit price per square yard for HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH, and no additional compensation will be allowed.

### ILLINOIS STANDARD W8-I106



COLOR: LEGEND AND BORDER — BLACK NON-REFLECTORIZED BACKGROUND — CRANGE REFLECTORIZED

SIGN			D	MENS	IONS			
SIZE	A	В	C ·	D	E	F	G	Ħ
36X36	36.0	17.2	2.2	24.3	23.5	5.5	10.5	2.5
48X48	48.0	24.1	3,0	34.0	33.0	5.0	13.0	3.5

07027		SERIES		3547	707	BLANK STD.
SIGN		LINES		MAR- GIN	BOR- DER	
SIZE	1	2	3			
36X36	5C	5C	5C	0.6	0.8	B4-36D
48X48	7C	7C	7C	0.8	1.2	B4-48D

All dimensions in inches.

#### TEMPORARY RAMPS FOR HOT-MIX ASPHALT SURFACE REMOVAL

This work shall consist of constructing, maintaining and removing temporary bituminous ramps at all butt joints and at all other required locations, according to Article 406.08 of the "Standard Specifications for Road and Bridge Construction."

Construction and removal of temporary ramps will not be measured separately for payment. The cost of this work shall be included in the contract unit price per square yard for HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH, which price shall include constructing, maintaining and removing all temporary ramps.

#### WATER MAIN, SIZE SPECIFIED

This item shall consist of constructing water main of the required material and outside diameter according to Section 561 of the "Standard Specifications for Road and Bridge Construction," and Division IV of the "Standard Specifications for Water and Sewer Main Construction in Illinois," as applicable, and as modified herein.

Material for water main shall conform to the requirements of AWWA C900. DR 18 pipe shall be used (pressure class 150). Joints shall be push-on type joints with elastomeric seals conforming to ASTM F477. All rubber shall be synthetic rubber: natural rubber will not be accepted. "Affidavits of Compliance" as outlined in AWWA Standard C900, Section 6.3 are required from each manufacturer of pipe and fittings. The affidavit shall certify the manufacturer's conformity with the applicable AWWA or ASTM standards.

Fittings, including reducers and end caps, shall not be paid for separately, but shall be measured along their centerlines and paid for per foot of WATER MAIN, of the size specified. Fittings shall be ductile iron compact fittings, AWWA C153, Class 350, with mechanical joints with restraining gland couplings. Fittings shall be rodded where indicated in the drawings or in the standard details. Shop plans for the water main pipe and fittings shall be submitted according to the requirements of Article 105.04 of the "Standard Specifications for Road and Bridge Construction."

The water main pipe shall be constructed in a trench. The width of the trench shall be the outside diameter of the pipe plus 18 inches. The trench shall provide a minimum of 4 inches of FA-6 bedding material beneath the pipe. The bedding material shall be well-compacted with a vibratory plate before placing the pipe. After laying the water main pipe, the pipe shall be further bedded with FA-6 to the elevation of the center of the pipe. After well-seating the pipe, the trench shall be initially backfilled with FA-6 to a height of one (1) foot over the top of the pipe. All bedding and initial backfilling of the pipe shall be well compacted before subsequent backfilling.

Where the trench is within two feet of the back of the proposed curb and gutter or within two feet of a pavement, the remainder of the trench shall be backfilled according to Section 208 of the "Standard Specifications for Road and Bridge Construction" as modified herein. Excavations in excess of the widths and depths stated in this special provision shall be backfilled according to Section 208 at the Contractor's expense. Where the trench is outside these limits, the remainder of the trench shall be backfilled with excavation material.

Prior to backfilling operations, a THHN soft drawn solid No. 12 copper tracer wire shall be affixed to all water main pipe. The tracer wire shall be continuous and any breaks in the wire's continuity shall be spliced to the satisfaction of the Engineer. The tracer wire shall be affixed to all valves and hydrants. At all gate valves, the tracer wire shall loop up to the ground surface with an additional one foot of slack left above the valve box as detailed in the plans.

The water main shall be pressure tested and disinfected according to Section 561 of the "Standard Specifications for Road and Bridge Construction." The Contractor shall give the City of Highland Water Department twenty-four hours notice of any testing. The City of Highland will observe all testing and sampling. Water samples shall be tested by an approved laboratory and the results shall be forwarded to the Engineer. The water main shall not be placed into service until the Contractor has secured written authorization from the City of Highland. Disinfecting and testing shall not be paid for separately, but shall be included in the unit price for WATER MAIN, of the size specified.

This work will be paid for at the contract unit price per foot for WATER MAIN, of the size specified, which price shall include all excavation, bedding, initial backfilling to a height of one (1) foot over the top of the pipe, pipe material, fittings, tracer wire, labor necessary to install the water main, disinfecting and testing. Trench backfill above the initial backfill of the pipe shall be measured and paid for according to Section 208 of the "Standard Specifications for Road and Bridge Construction." No additional compensation will be allowed.

#### WATER VALVES, SIZE SPECIFIED

This item shall consist of furnishing and constructing water valves, of the size specified, and valve boxes and lids at the locations indicated in plans. Gate valves shall conform to the latest AWWA C509 standard for resilient seat gate valves. Gate valves shall be nonrising stem type with O-ring stem seals. Valves shall have a solid wedge resilient seat. The stem shall be of high tensile strength bronze or other NSF approved non-corrosive metal. All valves shall open by turning counter clockwise.

Cast iron valve boxes shall be installed over all valves. The valve boxes and lids shall be cast iron, Tyler Series 6850, 5½ inch shaft, screw type valve boxes, or an approved equal. Lids shall be marked "WATER" cast into the lid. Shop plans for the water valves, valve boxes and lids shall be submitted according to the requirements of Article 105.04 of the "Standard Specifications for Road and Bridge Construction."

If the valve and box is being constructed as part of a fire hydrant assembly, the valve, valve box, and lid will not be paid for separately but shall be included in the unit price per each for FIRE HYDRANT AND VALVE (SPECIAL). Otherwise, the valve and box will be paid for at the unit price per each for WATER VALVES, of the size specified, which price shall include all excavation, the gate valve, valve box and lid, thrust blocking, tracer wire, and all other work necessary to install the water valve complete, and no additional compensation will be allowed.

#### **TAPPING VALVES AND SLEEVES 6"**

This item shall consist of installing a 6 inch "hot" tap into an existing 6 inch cast iron (CI) water main. The "hot" tap shall be installed according to Division IV of the "Standard Specifications for Water and Sewer Main Construction in Illinois."

TAPPING VALVE AND SLEEVES 6" shall include one Ford FAST-730-6 tapping sleeve (or approved equal), one tapping valve, one valve box and lid, and all labor, thrust blocking, equipment rentals and other costs required to make the tap. The gate valve shall have a flanged inlet designed to connect to the outlet end of the tapping sleeve. The outlet of the valve shall be designed so as to attach properly to a standard drilling machine. After the drilling operations, the valve outlet shall be connected to an 18" long 6" PVC nipple and then a 10" x 6" reducer. All joints shall be restrained mechanical joints. The tap members shall be thrust blocked to the satisfaction of the Engineer. Shop plans for the tapping sleeve, water valve, valve box and lid, and reducer shall be submitted according to the requirements of Article 105.04 of the "Standard Specifications for Road and Bridge Construction."

This work will be paid for at the contract unit price per each for TAPPING VALVE AND SLEEVES 6," which price shall include all excavation, bedding, initial backfilling to a height of one (1) foot over the top of the pipe, sleeve, valve, valve box and lid materials, fittings, tracer wire, thrust blocking, equipment rentals, labor, disinfecting and testing, and all other costs required to make the tap. Trench backfill above the initial backfill of the pipe will be measured and paid for according to Section 208 of the "Standard Specifications for Road and Bridge Construction." The 6" PVC nipple shall be paid for as WATER MAIN 6". No additional compensation will be allowed

#### WATER SERVICE LINE, 1"

This item shall consist of installing water service lines of the required material and diameter following the successful disinfection of the new water main. The water services shall be constructed according to Section 562 of the "Standard Specifications for Road and Bridge Construction" and Division IV of the "Standard Specifications for Water and Sewer Main Construction in Illinois," as applicable and as modified herein.

All water service lines shall be copper tubing, type "K." The water service lines shall be installed according to Division V, Standard Drawing No. 17 of the "Standard Specifications for Water and Sewer Main Construction in Illinois." The location of each water service shall be determined by the City of Highland. The length of water service line shall be measured from the corporation stop installed on the water main to the curb stop or water meter vault. The service line shall be installed to the satisfaction of the City of Highland Water Department.

Service lines serving properties on the opposite side of the road from the water main shall be directionally bored without open cutting the roadway. Trenches created by the water service line installation shall be backfilled according to Section 208 of the "Standard Specifications for Road and Bridge Construction"; however, this trench backfill shall not be measured separately for payment and the costs shall be included in the unit price for WATER SERVICE LINE, 1."

This work will be paid for at the contract unit price per foot for WATER SERVICE LINE, 1," which price shall include all excavation, pipe, pipe fittings, joint materials, boring, backfilling, and labor necessary to install the water services complete. No additional compensation will be allowed.

#### **CORPORATION STOPS, 1"**

This item shall consist of furnishing and installing water services tapping saddles and corporation stops following the successful disinfection of the new water main. The corporation stops shall be constructed according to Section 562 of the "Standard Specifications for Road and Bridge Construction" and Division IV of the "Standard Specifications for Water and Sewer Main Construction in Illinois," as applicable and as modified herein.

Corporation stops shall be Ford F-600, or approved equal. The tapping saddles shall be either McDonald 3805 10x1 or McDonald 3895 8x1 tapping saddles, or approved equal. The tapping saddles and corporation stops shall be installed according to Division V, Standard Drawing No. 17 of the "Standard Specifications for Water and Sewer Main Construction in Illinois." The location of each corporation stop shall be determined by the City of Highland. The tapping saddle and corporation stop shall be installed to the satisfaction of the City of Highland Water Department. Shop plans for the tapping saddles and corporation stops shall be submitted according to the requirements of Article 105.04 of the "Standard Specifications for Road and Bridge Construction."

This work will be paid for at the contract unit price per each for CORPORATION STOPS 1," which price shall include all excavation, materials, backfilling, and labor necessary to install the tapping sleeves and corporation stops complete. No additional compensation will be allowed.

#### ADJUSTING SANITARY SEWERS, 8-INCH DIAMETER OR LESS

This item shall consist of furnishing and constructing sanitary sewers, 8-inch diameter or less, according to Section 563 of the "Standard Specifications for Road and Bridge Construction" as modified herein.

The sanitary sewer pipe shall conform to the requirements of ASTM D3034. SDR 26 pipe with cell classification 12454-B or 12454-C shall be used. Joints shall be bell-and-spigot type conforming to ASTM D3212 with integral bell and push-on type elastomeric gasket joints. Gaskets shall conform to ASTM F477 using synthetic rubber. Natural rubber will not be accepted. The manufacturer of the pipe shall certify its pipe's conformity with the ASTM standard. Pipe or fittings having either spiral or concentric external reinforcing ribs will not be accepted.

The trench shall provide a minimum of 4 inches of CA-7 bedding material beneath the pipe. The bedding material shall be well compacted with a vibratory plate before placing the pipe. After laying the sanitary sewer pipe, the pipe shall be further bedded with CA-7 to the elevation of the center of the pipe.

The remainder of the trench shall be backfilled according to Section 208 of the Standard Specifications. Backfill material for sanitary sewer construction shall be CA-11. Excavations in excess of the widths and depths stated in this special provision shall be backfilled according to Section 208 at the Contractor's expense.

This work will be paid for at the contract unit price per foot for ADJUSTING SANITARY SEWERS, 8-INCH DIAMETER OR LESS, which price shall include all excavation, bedding, pipe material, and labor necessary to install the sanitary sewer. Trench backfill will be measured and paid for according to Section 208 of the Standard Specifications.

#### FIRE HYDRANT AND VALVE (SPECIAL)

This item shall consist of furnishing and installing fire hydrant and gate valve assemblies as detailed in the plans. The fire hydrant and gate valve assemblies shall be constructed according to Section 564 of the "Standard Specifications for Road and Bridge Construction" and Division IV of the "Standard Specifications for Water and Sewer Main Construction in Illinois," as applicable and as modified herein.

Fire hydrants shall be either a Kennedy K-81D Guardian, Mueller Super 200 Centurion, or Clow Madallion F2545 hydrant, with a 5¼ inch valve opening. The hydrant shall have two 2½ inch discharge nozzles and one 4½ inch steamer nozzle. FIRE HYDRANT AND VALVE (SPECIAL) shall include all pipe, fittings, valves, valve boxes and lids, tie rod connections, fire hydrants, drain fields, excavation and backfilling, and all other appurtenances necessary to install the assemblies according to the details in the plans. Shop plans for the fire hydrants and gate valves shall be submitted according to the requirements of Article 105.04 of the "Standard Specifications for Road and Bridge Construction."

This work will be paid for at the contract unit price per each for FIRE HYDRANT AND VALVE (SPECIAL), which price shall include all work necessary to install the fire hydrant assemblies complete. No additional compensation will be allowed.

#### SEALING EXISTING SEWERS

This item shall consist of all work necessary to abandon existing sewers at the locations shown on the plans and as directed by the Engineer.

Both ends of sewers to be abandoned shall be securely sealed with Class SI Concrete to prevent the inflow of groundwater and backfill material into the remaining sewer system.

This work will not be measured separately for payment. The cost of this work shall be included in the contract unit price for STORM SEWER REMOVAL, and no additional compensation will be allowed.

#### **TYPE 3 FRAME AND GRATE**

This work shall consist of furnishing and installing cast iron frames and grates, together with the necessary inlets and manholes as shown on the plans according to Section 602 of the "Standard Specifications for Road and Bridge Construction," except as modified herein.

All Type 3 Frames and grates shall conform to Highway Standard 604006 except the curb box shall have a single opening extending across the full width of the casting. The Contractor shall submit a shop drawing of the proposed frame and grate to the Engineer for approval according to Article 505.03 of the "Standard Specifications for Road and Bridge Construction."

This work will not be measured separately for payment. The cost of this work shall be included in the contract unit price per each inlet and manhole, of the type and diameter specified, and no additional compensation will be allowed.

#### MANHOLES, SPECIAL, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID

This work shall consist of constructing a precast manhole over an existing storm sewer pipe as shown on the plans, together with the necessary cast iron frame and lid, according to Section 602 of the "Standard Specifications for Road and Bridge Construction."

The manhole shall be constructed according to Highway Standard 602401 except the bottom section of the manhole shall be a "set-over" type section. The existing sewer shall be cleanly cut and a sufficient length removed so the finished manhole shall conform to the highway standard. The bottom of the manhole shall be poured in place. The Contractor shall submit shop drawings to the Engineer for approval according to Articles 1042.03(b) and 105.04 of the "Standard Specifications for Road and Bridge Construction."

This work will be paid for at the contract unit price per each for MANHOLES, SPECIAL, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID, which price shall include furnishing and installing the required manhole sections, frame and grate, cast-in place concrete, all excavation and backfill, connecting and grouting the storm sewers, pouring the concrete invert, and no additional compensation will be allowed.

#### INLETS, TYPE A, WITH SALVAGED GRATE

This work shall consist of constructing a Type A inlet and using a salvaged grate for a cover. The inlet shall be constructed as shown on the plans and according to Section 602 of the "Standard Specifications for Road and Bridge Construction."

The salvaged grate shall be removed from the existing inlet at Station 32+17 RT and set on the new inlet.

This work will be paid for at the contract unit price per each for INLETS, TYPE A, WITH SALVAGED GRATE, which price shall include furnishing and installing the inlet, all excavation and backfill, connecting and grouting the proposed storm sewers, pouring the concrete invert, and no additional compensation will be allowed.

#### INLETS, SPECIAL, NUMBER SPECIFIED

This work shall consist of constructing precast inlets as shown on the plans, together with the necessary cast iron frames and lids according to Section 602 of the "Standard Specifications for Road and Bridge Construction."

Each structure shall have a precast reinforced concrete flat slab top. The Contractor shall submit shop drawings to the Engineer for approval according to Articles 1042.03(b) and 105.04 of the "Standard Specifications for Road and Bridge Construction."

The required casting to be set into the precast concrete lid shall be a light-duty manhole frame and solid lid, such as a Neenah Standard R-1737, or approved equal.

This work will be paid for at the contract unit price per each for INLETS, SPECIAL, number specified, which price shall include furnishing and installing the required frame and grate, all excavation and backfill, connecting and grouting the proposed storm sewers, pouring the concrete invert, and no additional compensation will be allowed.

#### JUNCTION CHAMBER, NUMBER SPECIFIED

This work shall consist of constructing precast junction chambers as shown on the plans, together with the necessary cast iron frames and lids according to Section 602 of the "Standard Specifications for Road and Bridge Construction."

Each structure shall have a precast reinforced concrete flat slab top. The Contractor shall submit shop drawings to the Engineer for approval according to Articles 1042.03(b) and 105.04 of the "Standard Specifications for Road and Bridge Construction."

This work will be paid for at the contract unit price per each for JUNCTION CHAMBER, number specified, which price shall include furnishing and installing the required frame and lid, all excavation and backfill, connecting and grouting the proposed storm sewers, pouring the concrete invert, and no additional compensation will be allowed.

#### MANHOLES TO BE ADJUSTED (SPECIAL)

This work shall consist of reconstructing the upper two feet of the manhole at Station 27+58 RT. The existing frame and lid shall be removed and a new Type 1 frame and closed lid shall be constructed onto the existing manhole riser section. The Type 1 frame and lid shall be set to the final roadway grade and sealed to be water tight. The manhole shall be reconstructed to the satisfaction of the City of Highland Sewer Department.

This work will be paid for at the contract unit price per each for MANHOLES TO BE ADJUSTED (SPECIAL), which price shall include furnishing and installing the required frame and lid, all excavation and backfill, and no additional compensation will be allowed.

#### **CLASS SI CONCRETE (OUTLET)**

This item shall consist of constructing outlets for Combination Concrete Curb and Gutter, Type B-6.24, as detailed in the plans according to Section 606 of the "Standard Specifications for Road and Bridge Construction."

The outlet shall conform to Highway Standard 606006 for a Type 1 outlet. The grate shall be constructed according to the highway standard.

This work will be paid for at the contract unit price per cubic yard for CLASS SI CONCRETE (OUTLET), as specified in Section 606 except the grate shall not be paid for separately but shall be included in the contract unit price for CLASS SI CONCRETE (OUTLET), and no additional compensation will be allowed.

#### **CONCRETE GUTTER (SPECIAL)**

This work shall consist of constructing concrete gutter according to Section 606 of the "Standard Specifications for Road and Bridge Construction."

The gutter along the radius returns at the intersections of IL Route 160 (Sycamore Street) and Main Street and at IL 160 and Poplar Street shall match the existing shape and section as the existing gutter on IL 160. Transitions from combination concrete curb and gutter Type B-6.24 to CONCRETE GUTTER (SPECIAL) shall be measured and paid for as COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24.

This work shall be paid for at the contract unit price per foot for CONCRETE GUTTER (SPECIAL) which price shall include furnishing and placing all concrete, tie bars and joints, and all labor necessary to complete the work.

#### COMBINATION CONCRETE CURB AND GUTTER, (SPECIAL)

This item shall consist of constructing combination concrete curb and gutter within the roundabout splitter islands according to Section 606 of the "Standard Specifications for Road and Bridge Construction."

The curb and gutter shall consist of a six-inch barrier curb and a variable width gutter as shown in the plans.

This work will be paid for at the contract unit price per foot for COMBINATION CONCRETE CURB AND GUTTER, SPECIAL, regardless of the gutter width, and no additional compensation will be allowed.

#### **CONCRETE CURB, GUTTER, OR CURB & GUTTER TRANSITIONS**

This work shall consist of constructing concrete curb, concrete gutter and combination concrete curb and gutter according to Section 606 of the "Standard Specifications for Road and Bridge Construction."

At various locations, it may be necessary to transition proposed curb, gutter or combination curb and gutter to meet existing curbs or gutters. The minimum length of transitional curb, gutter or combination curb and gutter shall be 10 feet, unless directed otherwise by the Engineer.

This work shall be paid for at the contract unit price per foot for CONCRETE CURB; CONCRETE GUTTER, or COMBINATION CONCRETE CURB AND GUTTER, of the type specified, including all transitional curb, gutter and combination curb and gutter, which price shall include furnishing and placing all concrete, tie bars and joints, and all labor necessary to complete the work.

#### TRAFFIC CONTROL AND PROTECTION (DETOUR, NUMBER SPECIFIED)

This item shall consist of furnishing, installing, maintaining and removing all traffic control devices for traffic control and protection for designated detours as shown in the plans according to Section 701 of the "Standard Specifications for Road and Bridge Construction," as directed by the Engineer, and as specified herein.

Two detour routes are planned:

Detour 1 – IL Route 160

Close IL Route 160 on Poplar Street from Broadway to Main Street as detailed in the plans. IL Route 160 traffic will be detoured onto US Route 40 and Hemlock Street.

Detour 2 - Poplar Street

Close Poplar Street from Poplar Drive to Broadway. Poplar Street traffic will be detoured onto Lindenthal Avenue, Washington Street, Broadway, Cypress Street, and 6<sup>th</sup> Street.

Two weeks prior to closing a road and detouring traffic, the Contractor shall submit a completed "Road Construction Information" form (OPER 2410) to the following:

Illinois Department of Transportation Bureau of Operations, District 8 1102 Eastport Plaza Drive Collinsville, Illinois 62234 City of Highland Public Works Department 2610 Plaza Drive Highland, Illinois 62249

The Highland News Leader 1 Woodcrest Drive Highland, Illinois 62249

The information shall be updated and the form resubmitted as necessary.

Prior to closing the road, the Contractor shall erect all detour signs to the satisfaction of the Engineer. Barricade placement and sign spacing may be adjusted by the Engineer to suit field conditions. Temporary lane lines on Broadway shall be painted as detailed in the plans. Signing and paint pavement markings, and their removal, associated with the detours and roundabout construction shall not be paid for separately, but shall be included in the lump sum price.

This work shall be furnished, installed, maintained, measured and paid for at the contract lump sum price for TRAFFIC CONTROL AND PROTECTION (DETOUR, number specified), which price shall include all work as specified herein and any other provision required by law for the protection and safety of property and individuals in a construction zone, and no additional compensation will be allowed.

#### TRAFFIC CONTROL AND PROTECTION

This work shall consist of furnishing, installing, maintaining and removing all traffic control devices for traffic control and protection as shown on Highway Standards 701001, 701006, 701011, 701301, 701311, 701501, 701801, and 701901 included in the plans, according to the TRAFFIC CONTROL PLAN, according to Section 701 of the "Standard Specifications for Road and Bridge Construction," as directed by the Engineer and as specified herein.

Prior to beginning work on the project, the Contractor shall furnish and install Type III barricades and advance warning signs as shown on the TRAFFIC CONTROL PLAN and as detailed in the applicable Highway Standards. Barricade placement and sign spacing may be adjusted by the Engineer to suit field conditions.

Throughout the construction period, all material piles, equipment, open excavations or other obstructions or hazards to motorists or pedestrians shall be enclosed by fences or protected by barricades and proper lighting.

Traffic Control Surveillance as described in Article 701.10 of the "Standard Specifications for Road and Bridge Construction" will not be required. Also disregard Articles 701.19(d) and 701.20(g) concerning measurement and payment for Traffic Control Surveillance.

Traffic Control and Protection required for the successful completion of this project will be furnished, installed, maintained, measured and paid for at the contract lump sum price for TRAFFIC CONTROL AND PROTECTION, which price shall include all work as specified herein and any other provision required by law for the protection and safety of property and individuals in a construction zone, and no additional compensation will be allowed.

#### **CONTRACTOR ACCESS**

At road closure locations, where Type III barricades are installed in a manner that will not allow Contractor access to the project without relocation of one or more of the barricades, the arrangement of the barricades at the beginning of each work day may be relocated, when approved by the Engineer, in the manner shown on Highway Standard 701901. At the end of each work day, the barricades shall be returned to the proper overnight position.

The cost incurred by the Contractor in complying with this requirement shall be considered included in the contract unit prices bid for the various items of traffic control work involved and no additional compensation will be allowed.

#### SIGN PANEL, TYPE SPECIFIED (SPECIAL)

This item shall consist of furnishing and erecting sign panels as indicate in the plans. Signs shall be fabricated according to Section 720 of the "Standard Specifications for Road and Bridge Construction" as modified herein. The shape, size and configuration of the signs shall conform to the details in the plans. All sign faces, sign legends, and supplemental panels shall be reflectorized and of the color specified in the details. All Federal and State route panels within the Advanced Destination Guide Signs shall be as shown in the details.

Type 1 and Type 2 sign panels shall be fabricated of sheet aluminum. Type 3 sign panels shall be fabricated of bolted aluminum extrusions.

Type AZ reflective sheeting will not be allowed for either the sign face or the sign legends.

This work shall be paid for at the contract unit price per square foot for SIGN PANEL, TYPE 1 (SPECIAL), SIGN PANEL, TYPE 2 (SPECIAL), or SIGN PANEL, TYPE 3 (SPECIAL). The contract unit price shall include all work, material, supporting channels, and hardware necessary to furnish and install the sign at the locations noted in the plans. No additional compensation will be allowed.

#### TUBULAR STEEL SIGN SUPPORT - BREAKAWAY

This item shall consist of furnishing and erecting tubular steel sign supports for sign installation according to Section 727 of the "Standard Specifications for Road and Bridge Construction" as modified herein.

The tubular steel sign supports shall be fabricated according to the details shown in the plans.

This work shall be measured for payment in pounds calculated as the product of the length of the sign support including the embedment stub length multiplied by the weight per lineal foot for the size of tubular steel given in the construction details. End plates, base plates, sign connection channels, and all miscellaneous hardware shall not be measured for payment but shall be included in the cost of TUBULAR STEEL SIGN SUPPORT – BREAKAWAY.

This work shall be paid for at the contract unit price per pound for TUBULAR STEEL SIGN SUPPORT – BREAKAWAY. The contract unit price shall include all base plates, end plates, sign connection plates, and all other miscellaneous hardware, No additional compensation will be allowed.

#### **CONCRETE FOUNDATIONS**

This item shall consist of constructing concrete foundations for subsequent sign installation according to Section 734 of the "Standard Specifications for Road and Bridge Construction" as modified herein.

Concrete foundations shall be built to conform to the details in the plans. See the construction details for the appropriate dimensions for the post material used at the particular sign installation location.

Reinforcing bars shall be furnished and placed according to Section 508 of the "Standard Specifications for Road and Bridge Construction" as modified herein.

The top of foundations shall be the same elevation as the top of the adjacent curb.

Prior to any fabrication, the contractor shall submit shop drawings to the Engineer for approval.

This work shall be paid for at the contract unit price per cubic yard for CONCRETE FOUNDATIONS which price shall include all work necessary to construct the foundations as detailed in the plans. The unit price for CONCRETE FOUNDATIONS shall include furnishing and placing all reinforcing bars. No additional compensation will be allowed for reinforcing materials. Embedded post stub shall be paid for as TUBULAR STEEL SIGN SUPPORT – BREAKAWAY.

#### REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT

This work shall consist of removing the existing traffic signal equipment at the location shown on the plans according to Section 895 of the "Standard Specifications for Road and Bridge Construction."

The existing traffic signal system shall be maintained as long as possible. Non-conflicting traffic signal construction work shall be completed prior to disconnecting the existing system. Upon approval of the Engineer, the Contractor shall remove the following traffic signal equipment:

TS 2325	D MAA & P	2 each: SH 1 F 3S BM 2 each: SH 1 F 5S BM 2 each: PED SH 1F BM 2 each: PED PUSH-BUTTON
TS 2326	TS Post	2 each: PED SH 1F BM 2 each: PED PUSH-BUTTON
TS 2327	D MAA & P	2 each: SH 1 F 3S BM 2 each: SH 1 F 5S BM 2 each: PED SH 1F BM 2 each: PED PUSH-BUTTON
TS 2328	TS Post	2 each: PED SH 1F BM 2 each: PED PUSH-BUTTON

Controller cabinet, controller, master controller telephone modem & inductive loop detectors. All equipment shall be preserved and delivered to the IDOT Traffic and Maintenance Building at 9601 St. Clair Avenue, Fairview Heights, Illinois, and as directed by the Engineer. This equipment shall then become the property of the Illinois Department of Transportation. The Contractor shall contact Mr. David Walker, IDOT, at (618) 346-3100, at least 24 hours prior to delivery of the equipment.

This work will be paid for at the contract unit price per each intersection for REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT, which price shall be payment in full for completing all work specified herein, and no additional compensation will be allowed.

### REMOVE EXISTING HANDHOLE

This work shall consist of the removal of existing concrete handholes at the locations shown on the plans, according to Section 895 of the "Standard Specifications for Road and Bridge Construction." The entire handhole structure shall be removed.

This work will be paid for at the contract unit price per each for REMOVE EXISTING HANDHOLE, which price shall include the work as specified herein and no additional compensation will be allowed.

### REMOVE EXISTING CONCRETE FOUNDATION

This work shall consist of the removal of existing traffic signal foundations at the locations shown on the plans according to Section 895 of the "Standards Specifications for Road and Bridge Construction."

Removal shall be as described in Article 895.05(c) of the Standard Specifications.

This work shall be paid for at the contract unit price per each for REMOVE EXISTING CONCRETE FOUNDATION, which price shall include all work as specified herein and no additional compensation will be allowed.

### PAINT PAVEMENT MARKING CURB

This work shall consist of painting the top and face of the concrete curbs in the vicinity of the roundabout as detailed in the plans and according to Section 780 of the "Standards Specifications for Road and Bridge Construction."

This work shall be paid for at the contract unit price per foot for PAINT PAVEMENT MARKING CURB, which price shall include all work as specified herein and no additional compensation will be allowed.

### **CASING PIPE**

This work shall consist of constructing casing pipe for water main at locations indicated in the plans. The casing pipe shall be furnished and installed according to Division IV of the "Standard Specifications for Water and Sewer Main Construction in Illinois."

The casing pipe shall be 20-inch steel casing with a minimum wall thickness of 0.375 inches. The water main pipe shall be supported within the casing pipe by "RACI" plastic spacers or an approved equal. The ends of the casing pipe shall be sealed to the satisfaction of the City of Highland.

Shop plans for the casing pipe and spacers shall be submitted for approval according to Articles 1042.03(b) and 105.04 of the "Standard Specifications for Road and Bridge Construction."

This work shall be paid for at the contract unit price per foot for CASING PIPE, which price shall include all material and labor necessary to install the casing pipe complete, with pipe support fittings and end sealing and no additional compensation will be allowed.

### **CONCRETE STEP REMOVAL**

This item shall consist of removing the existing concrete steps at Station 31+59 RT. The steps and any subbase material shall be removed entirely.

This work will be paid for at the contract unit price per lump sum for CONCRETE STEP REMOVAL, which price shall include all excavation, removal and disposal of the existing steps and subbase material, and all other work necessary to remove the steps. No additional compensation will be allowed.

### **SANITARY CLEANOUT 6"**

This item shall consist of furnishing and constructing sanitary sewer cleanouts at locations shown in the plans according to Section 563 of the "Standard Specifications for Road and Bridge Construction" as modified herein. The material shall be the same as outlined in ADJUSTING SANITARY SEWERS, 8-INCH DIAMETER OR LESS. The cleanout shall consist of a 6" sanitary tee with a 6" riser, a sufficient length of 6" riser pipe, and a 6" cleanout adaptor and threaded cap.

This work will be paid for at the contract unit price per each for SANITARY CLEANOUT 6," which price shall include all excavation, material and all other work necessary to install the cleanout. No additional compensation will be allowed.

### **CONCRETE PAVER PAVEMENT**

This item shall consist of furnishing and constructing precast concrete pavers on a hot-mix asphalt base as shown in the plans according to the "Standard Specifications for Road and Bridge Construction" and Check Sheet LRS14 as modified herein. The elevation of the hot-mix asphalt base course will be determined after the paver is chosen. The pavers shall be terra cotta or earthy-red in color. Color samples shall be submitted to the Engineer prior to submitting the full size markup sample required by Check Sheet LRS 14.

This work will be paid for at the contract unit price per square yard for CONCRETE PAVER PAVEMENT which price shall include all material and all other work necessary to install the pavers. No additional compensation will be allowed.

### LOCATING UNDERGROUND UTILITY

This work shall consist of determining the exact locations of underground utilities that potentially conflict with proposed construction items.

Prior to the fabrication of any precast drainage structures, the Contractor shall excavate and expose those existing underground utilities determined by the Engineer to be in possible conflict with the proposed storm sewer. After the utilities are exposed, the Engineer will verify their location and elevation. If a conflict is confirmed, the Engineer will modify the storm sewer design or direct the utility owner to make the necessary adjustments. After the Engineer verifies the location and elevation of the utility, the Contractor shall immediately backfill the trench.

Trenches shall be backfilled according to Article 550.07 of the "Standard Specifications for Road and Bridge Construction" and as specified in the special provisions for TRENCH BACKFILL.

Removal of improved surfaces, such as sidewalk, curb and pavement will be measured and paid for separately as provided elsewhere in the contract. Temporary surfacing consisting of cold-mix asphalt patching material shall be used to maintain vehicular traffic until such time as the permanent surface can be restored.

This work will be paid for at the contract unit price per each for LOCATING UNDERGROUND UTILITY, which price shall include locating each utility and protecting it from damage during location and construction operations, backfilling the trench and temporarily restoring the surface as specified herein. Payment will not be made for any locating work performed by the utility owner. Payment will not be made for any work necessary to repair damages to the underground utilities caused by the Contractor. Trench backfill will not be measured and paid separately, but shall be included in the contract unit price for LOCATING UNDERGROUND UTILITY.

### STORM SEWER REMOVAL

This item shall consist of removing existing storm sewer at locations shown on the plans according to Section 551 of the "Standard Specifications for Road and Bridge Construction," as modified herein.

This work will be paid for at the contract unit price per foot for STORM SEWER REMOVAL, which price shall include all excavation, removal and disposal of the existing storm sewer regardless of size, sealing the ends of the storm sewer that will remain, backfill, and all other work necessary to remove the storm sewer. No additional compensation will be allowed.

### **CURB STOPS 1"**

This item shall consist of furnishing and installing curb valves and curb boxes at locations designated by the Engineer. The curb valves and boxes shall be constructed according to Section 562 of the "Standard Specifications for Road and Bridge Construction" and Division IV of the "Standard Specifications for Water and Sewer Main Construction in Illinois," as applicable and as modified herein.

The one inch curb valves shall be either a Mueller H-25204, Ford B22-444, or McDonald 6100 B-1 ball curb valve. The curb boxes shall be Mueller H-10306 or an approved equal. Shop plans for the curb valves and boxes shall be submitted according to the requirements of Article 105.04 of the "Standard Specifications for Road and Bridge Construction."

This work will be paid for at the contract unit price per each for CURB STOPS 1," which price shall include all excavation, the curb valve and box, connecting to the water service lines, backfilling, and all other work necessary to install the curb stops complete. No additional compensation will be allowed.

### STATUS OF UTILITIES TO BE ADJUSTED

Name & Address of Utility	<u>Type</u>	Location	Relocation Completed
Charter Communications 210 West Division Maryville, IL 62026	Cable Television	Entire length of project Facilities to be relocated.	February 28, 2008
Verizon Communications 111 East State Street Mascoutah, IL 62258	Telephone	Entire length of project - Facilities to be relocated.	February 28, 2008
City of Highland 2610 Plaza Drive Highland, IL 62249	Electric Water Sanitary Sewer	Entire length of project Entire length of project Entire length of project	February 28, 2008 Adjustments part of this contract
Illinois Power Company 1050 West Boulevard Belleville, IL 62221	Electric	6th Street to CSXT RR	No adjustments anticipated
Illinois Power Company 1050 West Boulevard Belleville, IL 62221	Gas	Entire length of project	February 28, 2008

The above represents the best information of the Department and is only included for the convenience of the bidder. The applicable provisions of Articles 102, 105.07, and 107.20 of the "Standard Specifications for Road and Bridge Construction" shall apply.

If any utility adjustment or removal has not been completed when required by the Contractor's operation, the Contractor should notify the Engineer in writing. A request for an extension of time will be considered to the extent the Contractor's operations were affected.

### REQUIRED CONTRACT PROVISIONS ALL CONTRACTS

### PAYROLLS and PROCEDURES

EFFECTIVE 2/5/I975, REVISED 11/7/I986, 1/14/1994, and June 2001

The <u>prime contractor and each subcontractor</u> shall submit a weekly certified original and one copy of their company's payroll directly to the District Engineer.

Payrolls must be received within seven days of the payroll ending period.

Payroll data shall be submitted on Payroll Form RE 48 or an approved facsimile.


Every person paid by a contractor or subcontractor in any manner for his or her labor in the construction, prosecution, completion, or repair of this public work is **employed** and receiving "wages," regardless of any contractual relationship alleged to exist between him or her and the real employer.

Payroll data shall include all persons employed on the job site.

The following employee codes are to be used to identify each individual on the payroll:

A.	Gender:	M - Male	F - Female	
B.	Ethnic Group: 4 - American Indian/Ala	1 - White skan Native	2 - Black 5 - Asian/Pacific Islande	3 - Hispanic er
C.	Work Classification: CL - Clerical TD - Truck Drivers EL - Electricians OT - Other	OF - Officials CA - Carpenters IW - Ironworkers PP - Pipefitters	SU - Supervisors EO - Operators PA - Painters TE - Technical	FO – Foremen ME - Mechanics CM - Cement Masons LA – Laborers
D.	Employee Status:	O - Owner Operator A - Apprentice	J - Journeyman T - Trainee	C - Company

Payroll data shall be submitted by the prime contractor and each subcontractor for each consecutive week, from the start to the completion of their work. When there has been no activity during a work week, a payroll is still required to be sent to the District Engineer, with the appropriate box ("No Work," "Suspended," "Completed") checked at the bottom of the Payroll Form RE 48. Do Not check any of these boxes when payroll data is being reported on the payroll.



# Required Contract Provisions All Contracts Monthly Labor Summary and Activity Reporting System

Effective: 1-1-1995 Revised June 2001

### I. Monthly Labor Summary Report, Form SBE 148

The <u>prime contractor and each first and second tier sub-contractor</u>, (hereinafter referred to as "subcontractor") shall submit a certified Monthly Labor Summary Report directly to the District Engineer.

This report is in lieu of submittal of the Monthly Workforce Analysis Report, Form SBE 956.

This report must be received in District Eight no later than the tenth day of the next month.

This Report shall be submitted by the prime contractor and each subcontractor, for each consecutive month, from the start, to the completion of their work on the contract.

The data source for this Report will be a summation of all personnel and hours worked on each subject contract for the month based on weekly payrolls for that month.

The Monthly Labor Summary Report is required to be submitted in one of the following formats:

- a.). For contractors having IDOT contracts valued in the aggregate at \$250,000 or less, the report may be typed or clearly handwritten using Form SBE 148 for submittal to the District Engineer for District Eight.
- b.) For contractors having IDOT contracts valued in the aggregate at more than \$250,000, the report must be submitted in a specific "Fixed Length Comma Delimited ASCII Text File Format." The subject file format is detailed on the next page. Submittal of this file may be by 3.5 inch disk, modem, or by e-mail.

### II. Monthly Contract Activity Report, Form SBE 248

The prime contractor and each subcontractor shall submit a monthly report directly to the District Engineer, reflecting their contract activity on all Illinois Department of Transportation contracts they have in force in District Eight.

This report shall be submitted for each consecutive month, from the start, to the completion of all contracts in District Eight.

The report must be received in the District Office no later than the tenth day of the next month.

Monthly Labor Summary and Activity Reporting System Codes and Formats

Indicated below for your reference are the Employee Codes and File Formats required for this system.

### I.) Monthly Labor Summary Report, Form SBE 148

The following employee codes are to be used to identify each individual on the Summary Report:

Gender: 1.

M - Male

F - Female

Ethnic Group: 2.

3.

4.

1 - White

2 - Black

3 - Hispanic

4 - American Indian/Alaskan Native

5 - Asian/Pacific Islander

Work Classification:

OF - Official

SU - Supervisor FO - Foremen

CL - Clerical

CA - Carpenter

EO - Operator

ME - Mechanic

TD - Truck Driver

IW - Ironworker

PA - Painter

OT - Other

EL - Electrician

PP - Pipefitter

TE - Technical

LA - Laborer -

CM -Cement Mason

O - Owner Operator

J - Journeyman C - Company

**Employee Status:** 

A - Apprentice

T - Trainee

Specific "Fixed Length Comma Delimited ASCII File Format"

Order	Field Name	Type	Size
1	Contractor Number	Α	4
2	Contractor Reference Number	Α	6
3	Contract Number	Α	5
4	Period (07/28/2000)	D	10
5	SSN (111-11-1111)	Α	11
6	Name	Α	40
7	Gender	Α	1
8	Ethnic Group	Α	1
9	Work Classification	Α	1
10	Employee Status	Α	1
11	Total Hours (0000060.00)	N	10

File Name Conventions:

(Contractor Number + Report Month/Year).Txt i.e. 20001298.Txt

### II.) Monthly Contract Activity Report, Form SBE 248

The following activity codes are to be used to identify the contractors contract status each month on the Monthly Activity Report, Form SBE 248:

Α.

Contract Status: 1 - Not Started 2 - Active

3 - No Work

4 - Suspended 5- Complete

Failure to comply with this special provision may result in the withholding of payments to the contractor, and/or cancellation, termination, or suspension of the contract in whole or part.

Compliance with this Special Provision shall be considered incidental to the cost of the contract and no additional compensation will be allowed for any costs incurred.

All prime and subcontractors having contracts in the aggregate exceeding \$250,000 must provide a "Fixed Length Comma Delimited ASCII File" for approval prior to the start of construction.

This Special Provision must be included in each subcontract agreement.

monitor/molassp2



Street Address

#### **Contractor Certification Statement**

City/State/ZIP

This certification statement is part of the Storm Water Pollution Prevention Plan for the project described below, in accordance with NPDES Permit No. ILR10 issued by the Illinois Environmental Protection Agency on May 30, 2003. Marked Rt. IL Route 160 FAP 690, FAU 8852 (Poplar) Route Project No. Section 05-00056-00-WR Contract No. County Madison I certify under penalty of law that I understand the terms of the general National Pollutant Discharge Elimination System (NPDES) permit (ILR 10) that authorizes the storm water discharges associated with industrial activity from the construction site identified as part of this certification. I have read and understand all of the information and requirements stated in the Storm Water Pollution Prevention Plan for the above mentioned project. I have provided all documentation required to be in compliance with the ILR10 and Storm Water Pollution Prevention Plan and will provide timely updates to these documents as necessary. ☐ Contractor □ Sub-Contractor Signature Print Name Date Title Telephone Name of Firm

## ILLINOIS ENVIRONMENTAL PROTECTION AGENCY NOTICE OF INTENT (NOI)

### GENERAL PERMIT TO DISCHARGE STORM WATER CONSTRUCTION SITE ACTIVITIES

OWNER	INFORMATION										
NAME:	City of Highland, Illino		MIDDLE	(OR COMPAN	NY NAME	)   0	)WNEF	C	ity		
MAILING ADDRESS:	1115 Broadway										
CITY:	Highland				5	STATE:	IL	ZIP:	62249		
CONTACT PERSON:	Joe Gillespie, Directo	r of Public Works			1	PHONE		AREA COD		BER -7511	
CONTR	ACTOR INFOR	MATION									
NAME:		RST MIDDL	E	(OR COMPANY NAME)		EPHONE IBER:		AREA COD	E NUME	BER	
MAILING ADDRESS:		CIT	Y:				S	TATE:	ZIF	P:	
CONST	RUCTION SITE	INFORMATIO	N								
SELECT ONE:	☑ New Site ☐ CH	ANGE OF INFORMATIO	N TO PE	RMIT NO. ILR10	_						
FACILITY NAME:	Poplar Street Widenin	g & Resurfacing, Ph	nase 2	OTHER NPDES PERMIT NOS.:							
FACILITY LOCATION:	Poplar Street from Bro	padway to 6th Street	ts			EPHONE (BER:		AREA COL		BER -7511	<u> </u>
CITY: High	land	ST: IL ZIP:	62249	LATITUDE: 38	44	33	LC	ONGITUD	E: 89	40	17
COUNTY:	Madison		Si	ECTION: 32	то	WNSHIP	): 41	V	RANGE:	5\	/
APPROX. CO	03 / 15 / 08	APPROX. CONSTRUEND DATE:		06 / 30 / 09	SITE	AL SIZE	RES:			5.6 a	ic
STORM WAT construction.)	ER POLLUTION PREVENTI	ON PLAN COMPLETED	<b></b> ✓ YES	NO (If no, separa	ate notif	ication re	quire	d to Ager	ncy prior to	5	
· · · · · · · · · · · · · · · · · · ·	F CONSTRUCT										
Transportat		scription of project: ace Poplar Street an	d Broa	dway Avenue fron	n Broa	adway t	to 6t	h Street	ts.		
•	RIC PRESERVA										
HAS THIS PE	ROJECT SATISFIED APPLIC	ABLE REQUIREMENTS	FOR CO	MPLIANCE WITH ILL	INOIS	LAW ON	1:				
	ENDANGERED SPEC	CIES 🗹 Y	ES	□ NO							<u> </u>
RECEI\	<u> </u>	<b>FORMATION</b>			**						
	STORM WATER DISCHAR OF THE STATE OR	GE DIRECTLY TO:  STORM SEWER		R OF STORM SEWE  Highland (applic		ГЕМ:					
NAME OF CL	OSEST RECEIVING WATE	R: Lindenthal Cree	k								
designed to a manage this belief, true, a imprisonmen	penalty of law that this docu issure that qualified personn system, or those persons di ccurate, and complete. I am i. In addition, I certify that the conitoring program plan, will be	el properly gather and evectly responsible for gat a aware that there are sign provisions of the permi	valuate the hering the anificant	ne information submitte e information, the info penalties for submittin	ed. Bas irmation no faise	sed on m submitte informat	ny inq ed is, tion, i	uiry of the to the be ncluding t	e person ( est of my the possib	or pers knowle bility of	ons who dge and fine and
OWNER SIG	NATURE:			DATE:				<del></del>	<del></del>		
						F	OR C	OFFICE U	SE ONLY		
MAIL COMP	ETED FORM TO:	ILLINOIS ENVIRONME DIVISION OF WATER			Y	LO	G:				
(DO NOT SI	BMIT ADDITIONAL	ATTN: PERMIT SECTI POST OFFICE BOX 19	ON			PE	RMIT	NO. ILR	10		
	ATION UNLESS	SPRINGFIELD, ILLING www.epa.state.il.us		4-9276		DA.	TE:		<u>.,</u>		***

Information required by this form must be provided to comply with 415 ILCS 5/39 (1996). Failure to do so may prevent this form from being processed and could result in your application being denied. This form has been approved by the Forms Management Center.

### INSTRUCTIONS FOR COMPLETION OF CONSTRUCTION ACTIVITY NOTICE OF INTENT (NOI) FORM

Please adhere to the following instructions:

Submit original, photocopy or facsimile copies. Facsimile and/or photo copies should be followed-up with an original signature copy as soon as possible. Please write "copy" under the "For Office Use Only" box in the lower right hand corner.

•••• Submit completed forms to:

Illinois Environmental Protection Agency Division of Water Pollution Control Permit Section Post Office Box 19276 Springfield, Illinois 62794-9276 or call (217)782-0610 www.epa.state.il.us

- Reports must be typed or printed legibly and signed.
- Any facility that is not presently covered by the ILR10 Construction Activity Storm Water Discharge General Permit is considered a new facility.
- •••• If this is a change in your facility information, renewal, etc., please fill in your permit number on the appropriate line.
- NOTE: FACILITY LOCATION IS NOT NECESSARILY THE FACILITY MAILING ADDRESS, BUT SHOULD DESCRIBE WHERE THE FACILITY IS LOCATED.
- ••• Use the formats given in the following examples for correct form completion.

	Example	Format
SECTION	12	1 or 2 numerical digits
TOWNSHIP	12N	1 or 2 numerical digits followed by "N" or "S"
RANGE	12W	1 or 2 numerical digits followed by "E" or "W"

- For the Name of Closest Receiving Waters, do not use terms such as ditch or channel. For unnamed tributaries, use terms which include at least a named main tributary such as "Unnamed Tributary to Sugar Creek to Sangamon River."
- Submit a fee of \$500 prior to the Notice of Intent being considered complete for coverage by the ILR10 General Permits. Please make checks payable to: Illinois EPA



#### DEPARTMENT OF THE ARMY ST. LOUIS DISTRICT, CORPS OF ENGINEERS 1222 SPRUCE STREET ST. LOUIS, MISSOURI 63103-2833

October 10, 2007

RECEIVED OCT 1 2007

REPLY TO ATTENTION OF:

Regulatory Branch

File Number: MVS-2006-424

Mr. Joe Gillespie 1115 Broadway P.O. Box 218 Highland, Illinois 62249

Dear Mr. Gillespie:

We have reviewed your request dated October 3, 2007, submitted on your behalf by Larry D. Thomason, Oates Associates, Inc., to reissue permit MVS 2006-424. This letter reauthorizes the installation of rip rap at the outlet of a proposed 36" storm sewer discharging into Lindenthal Creek, Highland, Madison County, Illinois. Lindenthal Creek is a tributary to the Kaskaskia River. More specifically, the project is located in the Southeast ¼ of the Northwest ¼ of Section 04, Township 03 North, Range 05 West of the 3<sup>rd</sup> Principal Meridian.

Based upon a review of the U.S. Geological Survey 7.5-minute topographical map, we determined that the Lindenthal Creek would possess an ordinary high water mark at this location and would be considered jurisdictional waters of the United States. Therefore, the placement of fill material below the ordinary high water elevation requires a permit from this office.

The Corps of Engineers has determined that this activity will have no affect on endangered species, and is authorized under Section 404 of the Clean Water Act by an existing Department of the Army nationwide permits for outfall structures associated intake structures, and bank stabilization as described in the March 12, 2007, Federal Register, Reissuance of Nationwide Permits; Notice (72 FR 11182), Appendix A (B)(7) and (72 FR 11183), Appendix A (B)13. This permit verification is valid until March 18, 2012. Enclosed is a copy of the nationwide permit and conditions and management practices with which you must comply.

In accordance with General Condition number 26 of the Nationwide Permit, a compliance certification (Attachment A of this package) must be completed within 30 days of project completion or the permit issuance will be revoked and considered null and void.

The Illinois Environmental Protection Agency (IEPA) has issued Section 401 water quality certification for all projects which qualify for outfall structures and associated intake structures nationwide permit. Therefore, individual certification is not required.

The Illinois Environmental Protection Agency (IEPA) has issued Section 401 water quality certification for a bank stabilization permit subject to the following conditions:

- a. The bank stabilization activities shall not exceed 500 linear feet.
- b. Asphalt, bituminous material and concrete with protruding material such as reinforcing bars or mesh shall not be:
  - 1. used for backfill;
  - 2. placed on shorelines/streambanks; or
  - 3. placed in waters of the State.
- c. Any spoil material excavated, dredged or otherwise produced must not be returned to the waterway but must be deposited in a self-contained area in compliance with all state statues, as determined by the Illinois EPA.
- d. Any backfilling must be done with clean material and placed in a manner to prevent violation of applicable water quality standards.
- e. The applicant shall consider installing bioengineering practices in lieu of structural practices of bank stabilization to minimize impacts to the lake, pond, river or stream and enhance aquatic habitat. Bioengineering techniques may include, but are not limited to:
  - 1. adequately sized riprap or A-Jack structures keyed into the toe of the slope with native plantings on the banks above;
  - vegetated geogrids;
  - 3. coconut fiber (coir) logs;
  - 4. live, woody vegetative cuttings, fascines or stumps;
  - 5. brush layering; and
  - 6. soil lifts.

Furthermore, to ensure projects authorized by this Nationwide Permit will result in minimal adverse effects to the aquatic environment, the following Regional Conditions were developed for projects proposed within the state of Illinois:

- 1. Bank stabilization projects involving armoring of the streambank with riprap or the construction of retaining walls within High Value Subwatersheds exceeding 250 feet will require a PCN to the Corps of Engineers in accordance with General Condition No. 27.
- 2. A proposed activity to be authorized under Nationwide Permits 12 or 14 within the Cache River Wetlands Areas (Alexander and Pulaski Counties), Kaskaskia River (Clinton, St. Clair, and Washington Counties), or Wabash River (Gallatin and White Counties) will require a PCN to the Corps of Engineers in accordance with General Condition No. 27.
- 3. Stormwater management facilities shall not be located within an intermittent stream, except of NWPs 21,49 or 50.
- 4. For newly constructed channels through areas that are unvegetated, native grass filter strips, or a riparian buffer with native trees or shrubs a minimum of 25 feet wide from the top of bank must be planted along both sides of the new channel.

This determination is applicable only to the permit program administered by the Corps of Engineers. It does not eliminate the need to obtain other federal, state or local approvals before beginning work.

You are reminded that the **permit** is based on submitted plans. Variations from these plans shall constitute a violation of Federal law and may result in the revocation of the permit. If this nationwide permit is modified, reissued, or revoked during this period, the provisions described at 33 CFR 330.6 (b) will apply.

This letter contains an approved jurisdictional determination for your project. If you object to this determination, you may request an administrative appeal under Corps regulations at 33 CFR Part 331. Enclosed you will find a Notification of Appeal Process (NAP) fact sheet and Request for Appeal (RFA) form.

If you request to appeal this determination you must submit a completed RFA form to the Mississippi Valley Division Office at the following address:

James B. Wiseman, Jr.

Administrative Appeals Review Officer

Mississippi Valley Division

P.O. Box 80 (1400 Walnut Street)

Vicksburg, MS 39181-0080

Phone (601) 634-5820 Fax(601) 634-5816

In order for an RFA to be accepted by the Corps, the Corps must determine that it is complete, that it meets the criteria for appeal under 33 CFR part 331.5, and that it has been received by the Division Office within 60 days of the date of the NAP. Should you decide to submit an RFA form, it must be received at the above address by **December 11, 2007**.

The jurisdictional determination is valid for a period of five years from the date of this letter unless new information warrants revision of this determination before the expiration date.

If you have any questions please contact Chuck Crocker at (314) 331-8584. Please refer to file number MVS-2006-424.

Sincerely,

ALAN R. EDMONDSON

Alan Edmondson Project Manager Illinois Permits Region

Enclosures

Copies Furnished: (w/out enclosures)

Mauer, IDNR Allison, IEPA

Mr. Larry D. Thomason Oates Associates, Inc. Eastport Business Center 1 100 Lanter Court, Suite 1 Collinsville, Illinois 62234

### ATTACHMENT A

### COMPLETED WORK CERTIFICATION

Date of Issuance: October 10, 2007

File Number: MVS-2006-424

Name of Permittee: Joe Gillespie, City of Highland

River Basin/County/State: Kaskaskia/Madison/Illinois

Project Manager: Alan Edmondson

Upon completion of this activity authorized by this permit and any mitigation required by the permit, sign this certification and return it to the following address:

U.S. Army Corps of Engineers Attn: Regulatory Branch (OD-F) 1222 Spruce Street St. Louis, Missouri 63103-2833

(Please note that your permitted activity is subject to a compliance inspection by a U.S. Army Corps of Engineers representative. If you fail to comply with this permit, you are subject to permit suspension, modification or revocation.)

I hereby certify that the work authorized by the above referenced permit has been completed in accordance with the terms and conditions of the said permit, and required mitigation was completed in accordance with the permit conditions.

Si	gna	ture	of	Perm:	Lt	te	е
----	-----	------	----	-------	----	----	---

Date

## State of Illinois Department of Transportation Bureau of Local Roads and Streets

## SPECIAL PROVISION FOR COOPERATION WITH UTILITIES

Effective: January 1, 1999 Revised: January 1, 2007

All references to Sections or Articles in this specification shall be construed to mean specific Section or Article of the Standard Specifications for Road and Bridge Construction, adopted by the Department of Transportation.

Replace Article 105.07 of the Standard Specifications with the following:

"105.07 Cooperation with Utilities. The adjustment of utilities consists of the relocation, removal, replacement, rearrangements, reconstruction, improvement, disconnection, connection, shifting, new installation or altering of an existing utility facility in any manner.

When the plans or special provisions include information pertaining to the location of underground utility facilities, such information represents only the opinion of the Department as to the location of such utilities and is only included for the convenience of the bidder. The Department assumes no responsibility in respect to the sufficiency or the accuracy of the information shown on the plans relative to the location of the underground utility facilities.

Utilities which are to be adjusted shall be adjusted by the utility owner or the owner's representative or by the Contractor as a contract item. Generally, arrangements for adjusting existing utilities will be made by the Department prior to project construction; however, utilities will not necessarily be adjusted in advance of project construction and, in some cases, utilities will not be removed from the proposed construction limits. When utility adjustments must be performed in conjunction with construction, the utility adjustment work will be shown on the plans and/or covered by Special Provisions.

When the Contractor discovers a utility has not been adjusted by the owner or the owner's representative as indicated in the contract documents, or the utility is not shown on the plans or described in the Special Provisions as to be adjusted in conjunction with construction, the Contractor shall not interfere with said utility, and shall take proper precautions to prevent damage or interruption of the utility and shall promptly notify the Engineer of the nature and location of said utility.

All necessary adjustments, as determined by the Engineer, of utilities not shown on the plans or not identified by markers, will be made at no cost to the Contractor except traffic structures, light poles, etc., that are normally located within the proposed construction limits as hereinafter defined will not be adjusted unless required by the proposed improvement.

- (a) Limits of Proposed Construction for Utilities Paralleling the Roadway. For the purpose of this Article, limits of proposed construction for utilities extending in the same longitudinal direction as the roadway, shall be defined as follows:
  - (1) The horizontal limits shall be a vertical plane, outside of, parallel to, and 600 mm (2 ft) distant at right angles from the plan or revised slope limits.
  - In cases where the limits of excavation for structures are not shown on the plans, the horizontal limits shall be a vertical plane 1.2 m (4 ft) outside the edges of structure footings or the structure where no footings are required.
  - (2) The upper vertical limits shall be the regulations governing the roadbed clearance for the specific utility involved.
  - (3) The lower vertical limits shall be the top of the utility at the depth below the proposed grade as prescribed by the governing agency or the limits of excavation, whichever is less.
- (b) Limits of Proposed Construction for Utilities Crossing the Roadway. For the purpose of this Article, limits of proposed construction for utilities crossing the roadway in a generally transverse direction shall be defined as follows:
  - (1) Utilities crossing excavations for structures that are normally made by trenching such as sewers, underdrains, etc. and all minor structures such as manholes, inlets, foundations for signs, foundations for traffic signals, etc., the limits shall be the space to be occupied by the proposed permanent construction unless otherwise required by the regulations governing the specific utility involved.
  - (2) For utilities crossing the proposed site of major structures such as bridges, sign trusses, etc., the limits shall be as defined above for utilities extending in the same general direction as the roadway.

The Contractor may make arrangements for adjustment of utilities outside of the limits of proposed construction provided the Contractor furnishes the Department with a signed agreement with the utility owner covering the adjustments to be made. The cost of any adjustments made outside the limits of proposed construction shall be the responsibility of the Contractor unless otherwise provided.

The Contractor shall request all utility owners to field locate their facilities according to Article 107.31. The Engineer may make the request for location from the utility after receipt of notice from the Contractor. On request, the Engineer will make an inspection to verify that the utility company has field located its facilities, but will not assume responsibility for the accuracy of such work. The Contractor shall be responsible for maintaining the excavations or markers provided by the utility owners. This field location procedure may be waived if the utility owner has stated in writing to the Department it is satisfied the construction plans are sufficiently accurate. If the utility owner does not submit such statement to the Department, and they do not field locate their facilities in both horizontal and vertical alignment, the Engineer will authorize the Contractor in writing to proceed to locate the facilities in the most economical and reasonable manner, subject to the approval of the Engineer, and be paid according to Article 109.04.

The Contractor shall coordinate with any planned utility adjustment or new installation and the Contractor shall take all precautions to prevent disturbance or damage to utility facilities. Any failure on the part of the utility owner, or their representative, to proceed with any planned utility adjustment or new installation shall be reported promptly by the Contractor to the Engineer orally and in writing.

The Contractor shall take all necessary precautions for the protection of the utility facilities. The Contractor shall be responsible for any damage or destruction of utility facilities resulting from neglect, misconduct, or omission in the Contractor's manner or method of execution or nonexecution of the work, or caused by defective work or the use of unsatisfactory materials. Whenever any damage or destruction of a utility facility occurs as a result of work performed by the Contractor, the utility company will be immediately notified. The utility company will make arrangements to restore such facility to a condition equal to that existing before any such damage or destruction was done.

It is understood and agreed that the Contractor has considered in the bid all of the permanent and temporary utilities in their present and/or adjusted positions.

No additional compensation will be allowed for any delays, inconvenience, or damage sustained by the Contractor due to any interference from the said utility facilities or the operation of relocating the said utility facilities.

## State of Illinois Department of Transportation Bureau of Local Roads and Streets

### SPECIAL PROVISION FOR INSURANCE

Effective: February 1, 2007 Revised: August 1, 2007

All references to Sections or Articles in this specification shall be construed to mean specific Section or Article of the Standard Specifications for Road and Bridge Construction, adopted by the Department of Transportation.

The Contractor shall name the following entities as additional insured under the Contractor's general liability insurance policy in accordance with Article 107.27:

City of Highland, Illinois

Oates Associates, Inc.

The entities listed above and their officers, employees, and agents shall be indemnified and held harmless in accordance with Article 107.26.

### BITUMINOUS MATERIALS COST ADJUSTMENTS (BDE) (RETURN FORM WITH BID)

Effective: November 2, 2006 Revised: January 2, 2007

<u>Description</u>. For projects with at least 1200 tons (1100 metric tons) of work involving applicable bituminous materials, cost adjustments will be made to provide additional compensation to the Contractor, or credit to the Department, for fluctuations in the cost of bituminous materials when optioned by the Contractor. The adjustments shall apply to permanent and temporary hot-mix asphalt (HMA) mixtures, bituminous surface treatments (cover and seal coats), and pavement preservation type surface treatments. The adjustments shall not apply to bituminous prime coats, tack coats, crack filling/sealing, or joint filling/sealing.

The bidder shall indicate on the attached form whether or not this special provision will be part of the contract and submit the completed form with his/her bid. Failure to submit the form, or failure to fill out the form completely, shall make this contract exempt of bituminous materials cost adjustments.

Method of Adjustment. Bituminous materials cost adjustments will be computed as follows.

 $CA = (BPI_P - BPI_L) \times (\%AC_V / 100) \times Q$ 

Where: CA = Cost Adjustment, \$.

BPI<sub>P</sub> = Bituminous Price Index, as published by the Department for the month the work is performed. \$/ton (\$/metric ton).

BPI<sub>L</sub> = Bituminous Price Index, as published by the Department for the month prior to the letting, \$/ton (\$/metric ton).

 $\% AC_V = \text{Percent of virgin Asphalt Cement in the Quantity being adjusted.}$  For HMA mixtures, the % AC $_V$  will be determined from the adjusted job mix formula. For bituminous materials applied, a performance graded or cutback asphalt will be considered to be 100% AC $_V$  and undiluted emulsified asphalt will be considered to be 65% AC $_V$ .

Q = Authorized construction Quantity, tons (metric tons) (see below).

For HMA mixtures measured in square yards: Q, tons = A x D x ( $G_{mb}$  x 46.8) / 2000. For HMA mixtures measured in square meters: Q, metric tons = A x D x ( $G_{mb}$  x 24.99) / 1000. When computing adjustments for full-depth HMA pavement, separate calculations will be made for the binder and surface courses to account for their different  $G_{mb}$  and %  $AC_{V}$ .

For bituminous materials measured in gallons: Q, tons =  $V \times 8.33$  lb/gal  $\times SG / 2000$  Q, metric tons =  $V \times 1.0$  kg/L  $\times SG / 1000$ 

Where: A = Area of the HMA mixture, sq yd (sq m).

D = Depth of the HMA mixture, in. (mm).

G<sub>mb</sub> = Average bulk specific gravity of the mixture, from the approved mix design.

V = Volume of the bituminous material, gal (L).

SG = Specific Gravity of bituminous material as shown on the bill of lading.

<u>Basis of Payment</u>. Bituminous materials cost adjustments may be positive or negative but will only be made when there is a difference between the BPI<sub>L</sub> and BPI<sub>P</sub> in excess of five percent, as calculated by:

Percent Difference =  $\{(BPI_L - BPI_P) \div BPI_L\} \times 100$ 

Bituminous materials cost adjustments will be calculated for each calendar month in which applicable bituminous material is placed; and will be paid or deducted when all other contract requirements for the items of work are satisfied. The adjustments shall not apply during contract time subject to liquidated damages for completion of the entire contract.

#### Return With Bid

### ILLINOIS DEPARTMENT OF TRANSPORTATION

### OPTION FOR BITUMINOUS MATERIALS COST ADJUSTMENTS

The bidder shall submit this completed form with his/her bid. Failure to submit the form, or failure to fill out the form completely, shall make this contract exempt of bituminous materials cost adjustments. After award, this form, when submitted, shall become part of the contract.

Contract No.:						
Company Nar	me:					
Contractor's	Optio	<u>n</u> :				
ls your compa	ny opt	ing to inclu	de this spe	cial provisio	n as part of the contract?	
	Yes		No			
Signature:	·	· · · · · · · · · · · · · · · · · · ·			Date:	
80173						

#### **CEMENT (BDE)**

Effective: January 1, 2007 Revised: November 1, 2007

Revise Section 1001 of the Standard Specifications to read:

#### **"SECTION 1001. CEMENT**

1001.01 Cement Types. Cement shall be according to the following.

(a) Portland Cement. Acceptance of portland cement shall be according to the current Bureau of Materials and Physical Research's Policy Memorandum, "Portland or Blended Cement Acceptance Procedure for Qualified and Non-Qualified Plants".

Portland cement shall be according to ASTM C 150, and shall meet the standard physical and chemical requirements. Type I or Type II may be used for cast-in-place, precast, and precast prestressed concrete. Type III may be used according to Article 1020.04, or when approved by the Engineer. All other cements referenced in ASTM C 150 may be used when approved by the Engineer.

The total of all organic processing additions shall be a maximum of 1.0 percent by weight (mass) of the cement and the total of all inorganic processing additions shall be a maximum of 4.0 percent by weight (mass) of the cement. Organic processing additions shall be limited to grinding aids that improve the flowability of cement, reduce pack set, and improve grinding efficiency. Inorganic processing additions shall be limited to granulated blast-furnace slag according to the chemical requirements of AASHTO M 302 and Class C fly ash according to the chemical requirements of AASHTO M 295.

(b) Portland-Pozzolan Cement. Acceptance of portland-pozzolan cement shall be according to the current Bureau of Materials and Physical Research's Policy Memorandum, "Portland or Blended Cement Acceptance Procedure for Qualified and Non-Qualified Plants".

Portland-pozzolan cement shall be according to ASTM C 595 and shall meet the standard physical and chemical requirements. Type IP or I(PM) may be used for cast-in-place, precast, and precast prestressed concrete, except when Class PP concrete is used. The pozzolan constituent for Type IP shall be a maximum of 21 percent of the weight (mass) of the portland-pozzolan cement. All other cements referenced in ASTM C 595 may be used when approved by the Engineer.

For cast-in-place construction, portland-pozzolan cements shall not be used in concrete mixtures when the air temperature is below 40 °F (4 °C) without permission of the Engineer. If permission is given, the mix design strength requirement may require the Contractor to increase the cement or eliminate the cement factor reduction for a water-

reducing or high range water-reducing admixture which is permitted according to Article 1020.05(b).

The total of all organic processing additions shall be a maximum of 1.0 percent by weight (mass) of the cement. Organic processing additions shall be limited to grinding aids as defined in (a) above. Inorganic processing additions shall not be used.

(c) Portland Blast-Furnace Slag Cement. Acceptance of portland blast-furnace slag cement shall be according to the current Bureau of Materials and Physical Research's Policy Memorandum, "Portland or Blended Cement Acceptance Procedure for Qualified and Non-Qualified Plants".

Portland blast-furnace slag cement shall be according to ASTM C 595 and shall meet the standard physical and chemical requirements. Type I(SM) slag-modified portland cement may be used for cast-in-place, precast, and precast prestressed concrete, except when Class PP concrete is used. All other cements referenced in ASTM C 595 may be used when approved by the Engineer.

For cast-in-place construction, portland blast-furnace slag cements shall not be used in concrete mixtures when the air temperature is below 40 °F (4 °C) without permission of the Engineer. If permission is given, the mix design strength requirement may require the Contractor to increase the cement or eliminate the cement factor reduction for a water-reducing or high range water-reducing admixture which is permitted according to Article 1020.05(b).

The total of all organic processing additions shall be a maximum of 1.0 percent by weight (mass) of the cement. Organic processing additions shall be limited to grinding aids as defined in (a) above. Inorganic processing additions shall not be used.

- (d) Rapid Hardening Cement. Rapid hardening cement shall be used according to Article 1020.04 or when approved by the Engineer. The cement shall be on the Department's current "Approved List of Packaged, Dry, Rapid Hardening Cementitious Materials for Concrete Repairs", and shall be according to the following.
  - (1) The cement shall have a maximum final set of 25 minutes, according to Illinois Modified ASTM C 191.
  - (2) The cement shall have a minimum compressive strength of 2000 psi (13,800 kPa) at 3.0 hours, and 4000 psi (27,600 kPa) at 24.0 hours, according to Illinois Modified ASTM C 109.
  - (3) The cement shall have a maximum drying shrinkage of 0.050 percent at seven days, according to Illinois Modified ASTM C 596.
  - (4) The cement shall have a maximum expansion of 0.020 percent at 14 days, according to Illinois Modified ASTM C 1038.

- (5) The cement shall have a minimum 80 percent relative dynamic modulus of elasticity; and shall not have a weight (mass) gain in excess of 0.15 percent or a weight (mass) loss in excess of 1.0 percent, after 100 cycles, according to Illinois Modified AASHTO T 161, Procedure B. At 100 cycles, the specimens are measured and weighed at 73 °F (23 °C).
- (e) Calcium Aluminate Cement. Calcium aluminate cement shall be used when specified by the Engineer. The cement shall meet the standard physical requirements for Type I cement according to ASTM C 150, except the time of setting shall not apply. The chemical requirements shall be determined according to ASTM C 114 and shall be as follows: minimum 38 percent aluminum oxide (Al<sub>2</sub>O<sub>3</sub>), maximum 42 percent calcium oxide (CaO), maximum 1 percent magnesium oxide (MgO), maximum 0.4 percent sulfur trioxide (SO<sub>3</sub>), maximum 1 percent loss on ignition, and maximum 3.5 percent insoluble residue.
- **1001.02 Uniformity of Color.** Cement contained in single loads or in shipments of several loads to the same project shall not have visible differences in color.
- 1001.03 Mixing Brands and Types. Different brands or different types of cement from the same manufacturing plant, or the same brand or type from different plants shall not be mixed or used alternately in the same item of construction unless approved by the Engineer.
- 1001.04 Storage. Cement shall be stored and protected against damage, such as dampness which may cause partial set or hardened lumps. Different brands or different types of cement from the same manufacturing plant, or the same brand or type from different plants shall be kept separate."

80166

### DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE)

Effective: September 1, 2000 Revised: January 1, 2007

<u>FEDERAL OBLIGATION</u>. The Department of Transportation, as a recipient of federal financial assistance, is required to take all necessary and reasonable steps to ensure nondiscrimination in the award and administration of contracts. Consequently, the federal regulatory provisions of 49 CFR part 26 apply to this contract concerning the utilization of disadvantaged business enterprises. For the purposes of this Special Provision, a disadvantaged business enterprise (DBE) means a business certified by the Department in accordance with the requirements of 49 CFR part 26 and listed in the DBE Directory or most recent addendum.

STATE OBLIGATION. This Special Provision will also be used by the Department to satisfy the requirements of the Business Enterprise for Minorities, Females, and Persons with Disabilities Act, 30 ILCS 575. When this Special Provision is used to satisfy state law requirements on 100 percent state-funded contracts, the federal government has no involvement in such contracts (not a federal-aid contract) and no responsibility to oversee the implementation of this Special Provision by the Department on those contracts. DBE participation on 100 percent state-funded contracts will not be credited toward fulfilling the Department's annual overall DBE goal required by the US Department of Transportation to comply with the federal DBE program requirements.

<u>CONTRACTOR ASSURANCE</u>. The Contractor makes the following assurance and agrees to include the assurance in each subcontract that the Contractor signs with a subcontractor:

The Contractor, subrecipient, or subcontractor shall not discriminate on the basis of race, color, national origin, or sex in the performance of this contract. The Contractor shall carry out applicable requirements of 49 CFR part 26 in the award and administration of contracts funded in whole or in part with federal or state funds. Failure by the Contractor to carry out these requirements is a material breach of this contract, which may result in the termination of this contract or such other remedy as the recipient deems appropriate.

OVERALL GOAL SET FOR THE DEPARTMENT. As a requirement of compliance with 49 CFR part 26, the Department has set an overall goal for DBE participation in its federally assisted contracts. That goal applies to all federal-aid funds the Department will expend in its federally assisted contracts for the subject reporting fiscal year. The Department is required to make a good faith effort to achieve the overall goal. The dollar amount paid to all approved DBE firms performing work called for in this contract is eligible to be credited toward fulfillment of the Department's overall goal.

CONTRACT GOAL TO BE ACHIEVED BY THE CONTRACTOR. This contract includes a specific DBE utilization goal established by the Department. The goal has been included because the Department has determined that the work of this contract has subcontracting opportunities that may be suitable for performance by DBE companies. This determination is based on an assessment of the type of work, the location of the work, and the availability of

DBE companies to do a part of the work. The assessment indicates that, in the absence of unlawful discrimination, and in an arena of fair and open competition, DBE companies can be expected to perform 15.0% of the work. This percentage is set as the DBE participation goal for this contract. Consequently, in addition to the other award criteria established for this contract, the Department will award this contract to a bidder who makes a good faith effort to meet this goal of DBE participation in the performance of the work. A bidder makes a good faith effort for award consideration if either of the following is done in accordance with the procedures set forth in this Special Provision:

- (a) The bidder documents that firmly committed DBE participation has been obtained to meet the goal; or
- (b) The bidder documents that a good faith effort has been made to meet the goal, even though the effort did not succeed in obtaining enough DBE participation to meet the goal.

<u>DBE LOCATOR REFERENCES</u>. Bidders may consult the DBE Directory as a reference source for DBE companies certified by the Department. In addition, the Department maintains a letting and item specific DBE locator information system whereby DBE companies can register their interest in providing quotes on particular bid items advertised for letting. Information concerning DBE companies willing to quote work for particular contracts may be obtained by contacting the Department's Bureau of Small Business Enterprises at telephone number (217)785-4611, or by visiting the Department's web site at www.dot.il.gov.

BIDDING PROCEDURES. Compliance with the bidding procedures of this Special Provision is required prior to the award of the contract and the failure of the as-read low bidder to comply will render the bid not responsive.

(a) In order to assure the timely award of the contract, the as-read low bidder shall submit a Disadvantaged Business Utilization Plan on Department form SBE 2026 within seven working days after the date of letting. To meet the seven day requirement, the bidder may send the Plan by certified mail or delivery service within the seven working day period. If a question arises concerning the mailing date of a Plan, the mailing date will be established by the U.S. Postal Service postmark on the original certified mail receipt from the U.S. Postal Service or the receipt issued by a delivery service. It is the responsibility of the bidder to ensure that the postmark or receipt date is affixed within the seven working days if the bidder intends to rely upon mailing or delivery to satisfy the submission day requirement. The Plan is to be submitted to the Department of Transportation, Bureau of Small Business Enterprises, Contract Compliance Section. 2300 South Dirksen Parkway, Room 319, Springfield, Illinois 62764 (Telefax: (217)785-1524). It is the responsibility of the bidder to obtain confirmation of telefax delivery. The Department will not accept a Utilization Plan if it does not meet the seven day submittal requirement and the bid will be declared not responsive. In the event the bid is declared not responsive due to a failure to submit a Plan or failure to comply with the bidding procedures set forth herein, the Department may elect to cause the forfeiture of the penal sum of the bidder's proposal guaranty, and may deny authorization to bid the project if re-advertised for bids. The Department reserves the right to invite any other bidder to submit a Utilization Plan at any time for award consideration or to extend the time for award.

- (b) The Utilization Plan shall indicate that the bidder either has obtained sufficient DBE participation commitments to meet the contract goal or has not obtained enough DBE participation commitments in spite of a good faith effort to meet the goal. The Utilization Plan shall further provide the name, telephone number, and telefax number of a responsible official of the bidder designated for purposes of notification of plan approval or disapproval under the procedures of this Special Provision.
- (c) The Utilization Plan shall include a DBE Participation Commitment Statement, Department form SBE 2025, for each DBE proposed for the performance of work to achieve the contract goal. The signatures on these forms must be original signatures. All elements of information indicated on the said form shall be provided, including but not limited to the following:
  - (1) The name and address of each DBE to be used;
  - (2) A description, including pay item numbers, of the commercially useful work to be done by each DBE;
  - (3) The price to be paid to each DBE for the identified work specifically stating the quantity, unit price, and total subcontract price for the work to be completed by the DBE. If partial pay items are to be performed by the DBE, indicate the portion of each item, a unit price where appropriate and the subcontract price amount;
  - (4) A commitment statement signed by the bidder and each DBE evidencing availability and intent to perform commercially useful work on the project; and
  - (5) If the bidder is a joint venture comprised of DBE firms and non-DBE firms, the plan must also include a clear identification of the portion of the work to be performed by the DBE partner(s).
- (d) The contract will not be awarded until the Utilization Plan submitted by the bidder is approved. The Utilization Plan will be approved by the Department if the Plan commits sufficient commercially useful DBE work performance to meet the contract goal. The Utilization Plan will not be approved by the Department if the Plan does not commit sufficient DBE performance to meet the contract goal unless the bidder documents that it made a good faith effort to meet the goal. The good faith procedures of Section VIII of this special provision apply. If the Utilization Plan is not approved because it is deficient in a technical matter, unless waived by the Department, the bidder will be notified and will be allowed no less than a five working day period in order to cure the deficiency.

<u>CALCULATING DBE PARTICIPATION</u>. The Utilization Plan values represent work anticipated to be performed and paid for upon satisfactory completion. The Department is only able to

count toward the achievement of the overall goal and the contract goal the value of payments made for the work actually performed by DBE companies. In addition, a DBE must perform a commercially useful function on the contract to be counted. A commercially useful function is generally performed when the DBE is responsible for the work and is carrying out its responsibilities by actually performing, managing, and supervising the work involved. The Department and Contractor are governed by the provisions of 49 CFR part 26.55(c) on questions of commercially useful functions as it affects the work. Specific counting guidelines are provided in 49 CFR part 26.55, the provisions of which govern over the summary contained herein.

- (a) DBE as the Contractor: 100 percent goal credit for that portion of the work performed by the DBE's own forces, including the cost of materials and supplies. Work that a DBE subcontracts to a non-DBE firm does not count toward the DBE goals.
- (b) DBE as a joint venture Contractor: 100 percent goal credit for that portion of the total dollar value of the contract equal to the distinct, clearly defined portion of the work performed by the DBE's own forces.
- (c) DBE as a subcontractor: 100 percent goal credit for the work of the subcontract performed by the DBE's own forces, including the cost of materials and supplies, excluding the purchase of materials and supplies or the lease of equipment by the DBE subcontractor from the prime Contractor or its affiliates. Work that a DBE subcontractor in turn subcontracts to a non-DBE firm does not count toward the DBE goal.
- (d) DBE as a trucker: 100 percent goal credit for trucking participation provided the DBE is responsible for the management and supervision of the entire trucking operation for which it is responsible. At least one truck owned, operated, licensed, and insured by the DBE must be used on the contact. Credit will be given for the full value of all such DBE trucks operated using DBE employed drivers. Goal credit will be limited to the value of the reasonable fee or commission received by the DBE if trucks are leased from a non-DBE company.
- (e) DBE as a material supplier:
  - (1) 60 percent goal credit for the cost of the materials or supplies purchased from a DBE regular dealer.
  - (2) 100 percent goal credit for the cost of materials or supplies obtained from a DBE manufacturer.
  - (3) 100 percent credit for the value of reasonable fees and commissions for the procurement of materials and supplies if not a regular dealer or manufacturer.

GOOD FAITH EFFORT PROCEDURES. If the bidder cannot obtain sufficient DBE commitments to meet the contract goal, the bidder must document in the Utilization Plan the good faith efforts made in the attempt to meet the goal. This means that the bidder must show

that all necessary and reasonable steps were taken to achieve the contract goal. Necessary and reasonable steps are those which could reasonably be expected to obtain sufficient DBE participation. The Department will consider the quality, quantity, and intensity of the kinds of efforts that the bidder has made. Mere *pro forma* efforts are not good faith efforts; rather, the bidder is expected to have taken those efforts that would be reasonably expected of a bidder actively and aggressively trying to obtain DBE participation sufficient to meet the contract goal.

- (a) The following is a list of types of action that the Department will consider as part of the evaluation of the bidder's good faith efforts to obtain participation. These listed factors are not intended to be a mandatory checklist and are not intended to be exhaustive. Other factors or efforts brought to the attention of the Department may be relevant in appropriate cases, and will be considered by the Department.
  - (1) Soliciting through all reasonable and available means (e.g. attendance at pre-bid meetings, advertising and/or written notices) the interest of all certified DBE companies that have the capability to perform the work of the contract. The bidder must solicit this interest within sufficient time to allow the DBE companies to respond to the solicitation. The bidder must determine with certainty if the DBE companies are interested by taking appropriate steps to follow up initial solicitations.
  - (2) Selecting portions of the work to be performed by DBE companies in order to increase the likelihood that the DBE goals will be achieved. This includes, where appropriate, breaking out contract work items into economically feasible units to facilitate DBE participation, even when the prime Contractor might otherwise prefer to perform these work items with its own forces.
  - (3) Providing interested DBE companies with adequate information about the plans, specifications, and requirements of the contract in a timely manner to assist them in responding to a solicitation.
  - (4) a. Negotiating in good faith with interested DBE companies. It is the bidder's responsibility to make a portion of the work available to DBE subcontractors and suppliers and to select those portions of the work or material needs consistent with the available DBE subcontractors and suppliers, so as to facilitate DBE participation. Evidence of such negotiation includes the names, addresses, and telephone numbers of DBE companies that were considered; a description of the information provided regarding the plans and specifications for the work selected for subcontracting; and evidence as to why additional agreements could not be reached for DBE companies to perform the work.
    - b. A bidder using good business judgment would consider a number of factors in negotiating with subcontractors, including DBE subcontractors, and would take a firm's price and capabilities as well as contract goals into consideration. However, the fact that there may be some additional costs involved in finding and using DBE companies is not in itself sufficient reason for a bidder's failure to meet the contract DBE goal, as long as such costs are reasonable. Also, the

ability or desire of a bidder to perform the work of a contract with its own organization does not relieve the bidder of the responsibility to make good faith efforts. Bidders are not, however, required to accept higher quotes from DBE companies if the price difference is excessive or unreasonable.

- (5) Not rejecting DBE companies as being unqualified without sound reasons based on a thorough investigation of their capabilities. The bidder's standing within its industry, membership in specific groups, organizations, or associations and political or social affiliations (for example union vs. non-union employee status) are not legitimate causes for the rejection or non-solicitation of bids in the bidder's efforts to meet the project goal.
- (6) Making efforts to assist interested DBE companies in obtaining bonding, lines of credit, or insurance as required by the recipient or Contractor.
- (7) Making efforts to assist interested DBE companies in obtaining necessary equipment supplies, materials, or related assistance or services.
- (8) Effectively using the services of available minority/women community organizations; minority/women contractors' groups; local, state, and federal minority/women business assistance offices; and other organizations as allowed on a case-by-case basis to provide assistance in the recruitment and placement of DBE companies.
- (b) If the Department determines that the bidder has made a good faith effort to secure the work commitment of DBE companies to meet the contract goal, the Department will award the contract provided that it is otherwise eligible for award. If the Department determines that a good faith effort has not been made, the Department will notify the bidder of that preliminary determination by contacting the responsible company official designated in the Utilization Plan. The preliminary determination shall include a statement of reasons why good faith efforts have not been found, and may include additional good faith efforts that the bidder could take. The notification will designate a five working day period during which the bidder shall take additional efforts. The bidder is not limited by a statement of additional efforts, but may take other action beyond any stated additional efforts in order to obtain additional DBE commitments. The bidder shall submit an amended Utilization Plan if additional DBE commitments to meet the contract goal are secured. If additional DBE commitments sufficient to meet the contract goal are not secured, the bidder shall report the final good faith efforts made in the time allotted. All additional efforts taken by the bidder will be considered as part of the bidder's good faith efforts. If the bidder is not able to meet the goal after taking additional efforts, the Department will make a pre-final determination of the good faith efforts of the bidder and will notify the designated responsible company official of the reasons for an adverse determination.
- (c) The bidder may request administrative reconsideration of a pre-final determination adverse to the bidder within the five working days after the notification date of the determination by delivering the request to the Department of Transportation, Bureau of

Small Business Enterprises, Contract Compliance Section, 2300 South Dirksen Parkway, Room 319, Springfield, Illinois 62764 (Telefax: (217)785-1524). Deposit of the request in the United States mail on or before the fifth business day shall not be deemed delivery. The pre-final determination shall become final if a request is not made and delivered. A request may provide additional written documentation and/or argument concerning the issue of whether an adequate good faith effort was made to meet the contract goal. In addition, the request shall be considered a consent by the bidder to The request will be forwarded to the Department's extend the time for award. Reconsideration Officer. The Reconsideration Officer will extend an opportunity to the bidder to meet in person in order to consider all issues of whether the bidder made a good faith effort to meet the goal. After the review by the Reconsideration Officer, the bidder will be sent a written decision within ten working days after receipt of the request for reconsideration, explaining the basis for finding that the bidder did or did not meet the goal or make adequate good faith efforts to do so. A final decision by the Reconsideration Officer that a good faith effort was made shall approve the Utilization Plan submitted by the bidder and shall clear the contract for award. A final decision that a good faith effort was not made shall render the bid not responsive.

CONTRACT COMPLIANCE. Compliance with this Special Provision is an essential part of the contract. The Department is prohibited by federal regulations from crediting the participation of a DBE included in the Utilization Plan toward either the contract goal or the Department's overall goal until the amount to be applied toward the goals has been paid to the DBE. The following administrative procedures and remedies govern the compliance by the Contractor with the contractual obligations established by the Utilization Plan. After approval of the Plan and award of the contract, the Utilization Plan and individual DBE Participation Statements become part of the contract. If the Contractor did not succeed in obtaining enough DBE participation to achieve the advertised contract goal, and the Utilization Plan was approved and contract awarded based upon a determination of good faith, the total dollar value of DBE work calculated in the approved Utilization Plan as a percentage of the awarded contract value shall become the amended contract goal.

- (a) No amendment to the Utilization Plan may be made without prior written approval from the Department's Bureau of Small Business Enterprises. All requests for amendment to the Utilization Plan shall be submitted to the Department of Transportation, Bureau of Small Business Enterprises, Contract Compliance Section, 2300 South Dirksen Parkway, Room 319, Springfield, Illinois 62764. Telephone number (217) 785-4611. Telefax number (217) 785-1524.
- (b) All work indicated for performance by an approved DBE shall be performed, managed, and supervised by the DBE executing the Participation Statement. The Contractor shall not terminate for convenience a DBE listed in the Utilization Plan and then perform the work of the terminated DBE with its own forces, those of an affiliate or those of another subcontractor, whether DBE or not, without first obtaining the written consent of the Bureau of Small Business Enterprises to amend the Utilization Plan. If a DBE listed in the Utilization Plan is terminated for reasons other than convenience, or fails to complete its work on the contract for any reason, the Contractor shall make good faith efforts to

find another DBE to substitute for the terminated DBE. The good faith efforts shall be directed at finding another DBE to perform at least the same amount of work under the contract as the DBE that was terminated, but only to the extent needed to meet the contract goal or the amended contract goal. The Contractor shall notify the Bureau of Small Business Enterprises of any termination for reasons other than convenience, and shall obtain approval for inclusion of the substitute DBE in the Utilization Plan. If good faith efforts following a termination of a DBE for cause are not successful, the Contractor shall contact the Bureau and provide a full accounting of the efforts undertaken to obtain substitute DBE participation. The Bureau will evaluate the good faith efforts in light of all circumstances surrounding the performance status of the contract, and determine whether the contract goal should be amended.

- (c) The Contractor shall maintain a record of payments for work performed to the DBE participants. The records shall be made available to the Department for inspection upon request. After the performance of the final item of work or delivery of material by a DBE and final payment therefor to the DBE by the Contractor, but not later than thirty calendar days after payment has been made by the Department to the Contractor for such work or material, the Contractor shall submit a DBE Payment Report on Department form SBE 2115 to the Regional Engineer. If full and final payment has not been made to the DBE, the Report shall indicate whether a disagreement as to the payment required exists between the Contractor and the DBE or if the Contractor believes that the work has not been satisfactorily completed. If the Contractor does not have the full amount of work indicated in the Utilization Plan performed by the DBE companies indicated in the Plan, the Department will deduct from contract payments to the Contractor the amount of the goal not achieved as liquidated and ascertained damages.
- (d) The Department reserves the right to withhold payment to the Contractor to enforce the provisions of this Special Provision. Final payment shall not be made on the contract until such time as the Contractor submits sufficient documentation demonstrating achievement of the goal in accordance with this Special Provision or after liquidated damages have been determined and collected.
- (e) Notwithstanding any other provision of the contract, including but not limited to Article 109.09 of the Standard Specifications, the Contractor may request administrative reconsideration of a decision to deduct the amount of the goal not achieved as liquidated damages. A request to reconsider shall be delivered to the Contract Compliance Section and shall be handled and considered in the same manner as set forth in paragraph (c) of "Good Faith Effort Procedures" of this Special Provision, except a final decision that a good faith effort was not made during contract performance to achieve the goal agreed to in the Utilization Plan shall be the final administrative decision of the Department.

80029

60

### **DOWEL BARS (BDE)**

Effective: April 1, 2007 Revised: January 1, 2008

Revise the fifth and sixth sentences of Article 1006.11(b) of the Standard Specifications to read:

"The bars shall be epoxy coated according to AASHTO M 284, except the thickness of the epoxy shall be 7 to 12 mils (0.18 to 0.30 mm) and patching of the ends will not be required. The epoxy coating applicator shall be certified according to the current Bureau of Materials and Physical Research Policy Memorandum, "Epoxy Coating Plant Certification Procedure". The Department will maintain an approved list."

80178

### **EQUIPMENT RENTAL RATES (BDE)**

Effective: August 2, 2007 Revised: January 2, 2008

Replace the second and third paragraphs of Article 105.07(b)(4)a. of the Standard Specifications with the following:

"Equipment idled which cannot be used on other work, and which is authorized to standby on the project site by the Engineer, will be paid for according to Article 109.04(b)(4)."

Replace Article 109.04(b)(4) of the Standard Specifications with the following:

- "(4) Equipment. Equipment used for extra work shall be authorized by the Engineer. The equipment shall be specifically described, be of suitable size and capacity for the work to be performed, and be in good operating condition. For such equipment, the Contractor will be paid as follows.
  - a. Contractor Owned Equipment. Contractor owned equipment will be paid for by the hour using the applicable FHWA hourly rate from the "Equipment Watch Rental Rate Blue Book" (Blue Book) in effect when the force account work begins. The FHWA hourly rate is calculated as follows.

FHWA hourly rate = (monthly rate/176) x (model year adj.) x (Illinois adj.) + EOC

Where: EOC = Estimated Operating Costs per hour (from the Blue Book)

The time allowed will be the actual time the equipment is operating on the extra work. For the time required to move the equipment to and from the site of the extra work and any authorized idle (standby) time, payment will be made at the following hourly rate:  $0.5 \times (FHWA \text{ hourly rate} - EOC)$ .

All time allowed shall fall within the working hours authorized for the extra work.

The rates above include the cost of fuel, oil, lubrication, supplies, small tools, necessary attachments, repairs, overhaul and maintenance of any kind, depreciation, storage, overhead, profits, insurance, and all incidentals. The rates do not include labor.

The Contractor shall submit to the Engineer sufficient information for each piece of equipment and its attachments to enable the Engineer to determine the proper equipment category. If a rate is not established in the Blue Book for a particular piece of equipment, the Engineer will establish a rate for that piece of equipment that is consistent with its cost and use in the industry.

b. Rented Equipment. Whenever it is necessary for the Contractor to rent equipment to perform extra work, the rental and transportation costs of the equipment plus five percent for overhead will be paid. In no case shall the rental rates exceed those of established distributors or equipment rental agencies.

All prices shall be agreed to in writing before the equipment is used."

#### **EROSION AND SEDIMENT CONTROL DEFICIENCY DEDUCTION (BDE)**

Effective: April 1, 2007

Revise Article 105.03(a) of the Standard Specifications to read:

"(a) Erosion and Sediment Control Deficiency Deduction. When the Engineer is notified or determines an erosion and/or sediment control deficiency(s) exists, he/she will notify and direct the Contractor to correct the deficiency within a specified time. The specified time, which begins upon notification to the Contractor, will be from 1/2 hour to 1 week based on the urgency of the situation and the nature of the deficiency. The Engineer will be the sole judge.

A deficiency may be any lack of repair, maintenance, or implementation of erosion and/or sediment control devices included in the contract, or any failure to comply with the conditions of the National Pollutant Discharge Elimination System (NPDES) Storm Water Permit for Construction Site Activities. A deficiency may also be applied to situations where corrective action is not an option such as the failure to participate in a jobsite inspection of the project, failure to install required measures prior to initiating earth moving operations, disregard of concrete washout requirements, or other disregard of the NPDES permit.

If the Contractor fails to correct a deficiency within the specified time, a daily monetary deduction will be imposed for each calendar day or fraction thereof the deficiency exists. The calendar day(s) will begin with notification to the Contractor and end with the Engineer's acceptance of the correction. The daily monetary deduction will be either \$1000.00 or 0.05 percent of the awarded contract value, whichever is greater. For those deficiencies where corrective action was not an option, the monetary deduction will be immediate and will be valued at one calendar day."

#### PAYMENTS TO SUBCONTRACTORS (BDE)

Effective: June 1, 2000 Revised: January 1, 2006

Federal regulations found at 49 CFR §26.29 mandate the Department to establish a contract clause to require Contractors to pay subcontractors for satisfactory performance of their subcontracts and to set the time for such payments.

State law also addresses the timing of payments to be made to subcontractors and material suppliers. Section 7 of the Prompt Payment Act, 30 ILCS 540/7, requires that when a Contractor receives any payment from the Department, the Contractor shall make corresponding, proportional payments to each subcontractor and material supplier performing work or supplying material within 15 calendar days after receipt of the Department payment. Section 7 of the Act further provides that interest in the amount of two percent per month, in addition to the payment due, shall be paid to any subcontractor or material supplier by the Contractor if the payment required by the Act is withheld or delayed without reasonable cause. The Act also provides that the time for payment required and the calculation of any interest due applies to transactions between subcontractors and lower-tier subcontractors and material suppliers throughout the contracting chain.

This Special Provision establishes the required federal contract clause, and adopts the 15 calendar day requirement of the State Prompt Payment Act for purposes of compliance with the federal regulation regarding payments to subcontractors. This contract is subject to the following payment obligations.

When progress payments are made to the Contractor according to Article 109.07 of the Standard Specifications, the Contractor shall make a corresponding payment to each subcontractor and material supplier in proportion to the work satisfactorily completed by each subcontractor and for the material supplied to perform any work of the contract. The proportionate amount of partial payment due to each subcontractor and material supplier throughout the contracting chain shall be determined by the quantities measured or otherwise determined as eligible for payment by the Department and included in the progress payment to the Contractor. Subcontractors and material suppliers shall be paid by the Contractor within 15 calendar days after the receipt of payment from the Department. The Contractor shall not hold retainage from the subcontractors. These obligations shall also apply to any payments made by subcontractors and material suppliers to their subcontractors and material suppliers; and to all payments made to lower tier subcontractors and material suppliers throughout the contracting chain. Any payment or portion of a payment subject to this provision may only be withheld from the subcontractor or material supplier to whom it is due for reasonable cause.

This Special Provision does not create any rights in favor of any subcontractor or material supplier against the State or authorize any cause of action against the State on account of any payment, nonpayment, delayed payment, or interest claimed by application of the State Prompt Payment Act. The Department will not approve any delay or postponement of the 15 day requirement except for reasonable cause shown after notice and hearing pursuant to Section

7(b) of the State Prompt Payment Act. State law creates other and additional remedies available to any subcontractor or material supplier, regardless of tier, who has not been paid for work properly performed or material furnished. These remedies are a lien against public funds set forth in Section 23(c) of the Mechanics Lien Act, 770 ILCS 60/23(c), and a recovery on the Contractor's payment bond according to the Public Construction Bond Act, 30 ILCS 550.

#### PRECAST CONCRETE HANDLING HOLES (BDE)

with the following:

Effective: January 1, 2007 Add the following to Article 540.02 of the Standard Specifications: "(g) Handling Hole Plugs ......1042.16" Add the following paragraph after the sixth paragraph of Article 540.06 of the Standard Specifications: "Handling holes shall be filled with a precast concrete plug and sealed with mastic or mortar, or filled with a polyethylene plug. The plug shall not project beyond the inside surface after installation. When metal lifting inserts are used, their sockets shall be filled with mastic or mortar." Add the following to Article 542.02 of the Standard Specifications: "(ee) Handling Hole Plugs ......1042.16" Revise the fifth paragraph of Article 542.04(d) of the Standard Specifications to read: "Handling holes in concrete pipe shall be filled with a precast concrete plug and sealed with mastic or mortar; or filled with a polyethylene plug. The plug shall not project beyond the inside surface after installation." Add the following to Article 550.02 of the Standard Specifications: "(o) Handling Hole Plugs ......1042.16" Replace the fourth sentence of the fifth paragraph of Article 550.06 of the Standard Specifications with the following: "Handling holes in concrete pipe shall be filled with a precast concrete plug and sealed with mastic or mortar; or filled with a polyethylene plug. The plug shall not project beyond the inside surface after installation." Add the following to Article 602.02 of the Standard Specifications: Replace the fifth sentence of the first paragraph of Article 602.07 of the Standard Specifications "Handling holes shall be filled with a precast concrete plug and sealed with mastic or mortar. The plug shall not project beyond the inside surface after installation. When metal lifting inserts are used, their sockets shall be filled with mastic or mortar."

Add the following to Section 1042 of the Standard Specifications:

"1042.16 Handling Hole Plugs. Plugs for handling holes in precast concrete products shall be as follows.

- (a) Precast Concrete Plug. The precast concrete plug shall have a tapered shape and shall have a minimum compressive strength of 3000 psi (20,700 kPa) at 28 days.
- (b) Polyethylene Plug. The polyethylene plug shall have a "mushroom" shape with a flat round top and a stem with three different size ribs. The plug shall fit snuggly and cover the handling hole.

The plug shall be according to the following.

Mechanical Properties	Test Method	Value (min.)
Flexural Modulus	ASTM D 790	3300 psi (22,750 kPa)
Tensile Strength (Break)	ASTM D 638	1600 psi (11,030 kPa)
Tensile Strength (Yield)	ASTM D 638	1200 psi (8270 kPa)

Thermal Properties	Test Method	Value (min.)
Brittle Temperature	ASTM D 746	-49 °F (-45 °C)
Vicat Softening Point	ASTM D 1525	194 °F (90 °C)"

#### RECLAIMED ASPHALT PAVEMENT (RAP) (BDE)

Effective: January 1, 2007 Revised: August 1, 2007

In Article 1030.02(g), delete the last sentence of the first paragraph in (Note 2).

Revise Section 1031 of the Standard Specifications to read:

#### **"SECTION 1031. RECLAIMED ASPHALT PAVEMENT**

**1031.01 Description.** Reclaimed asphalt pavement (RAP) is reclaimed asphalt pavement resulting from cold milling or crushing of an existing dense graded hot-mix asphalt (HMA) pavement. The Contractor shall supply written documentation that the RAP originated from routes or airfields under federal, state, or local agency jurisdiction.

1031.02 Stockpiles. The Contractor shall construct individual, sealed RAP stockpiles meeting one of the following definitions. No additional RAP shall be added to the pile after the pile has been sealed. Stockpiles shall be sufficiently separated to prevent intermingling at the base. Stockpiles shall be identified by signs indicating the type as listed below (i.e. "Homogeneous Surface").

Prior to milling, the Contractor shall request the District to provide verification of the quality of the RAP to clarify appropriate stockpile.

- (a) Homogeneous. Homogeneous RAP stockpiles shall consist of RAP from Class I, Superpave (High ESAL), HMA (High ESAL), or equivalent mixtures and represent: 1) the same aggregate quality, but shall be at least C quality; 2) the same type of crushed aggregate (either crushed natural aggregate, ACBF slag, or steel slag); 3) similar gradation; and 4) similar asphalt binder content. If approved by the Engineer, combined single pass surface/binder millings may be considered "homogenous" with a quality rating dictated by the lowest coarse aggregate quality present in the mixture.
- (b) Conglomerate 5/8. Conglomerate 5/8 RAP stockpiles shall consist of RAP from Class I, Superpave (High ESAL), HMA (High ESAL), or equivalent mixtures. The coarse aggregate in this RAP shall be crushed aggregate and may represent more than one aggregate type and/or quality but shall be at least C quality. This RAP may have an inconsistent gradation and/or asphalt binder content prior to processing. All conglomerate 5/8 RAP shall be processed prior to testing by crushing to where all RAP shall pass the 5/8 in. (16 mm) or smaller screen. Conglomerate 5/8 RAP stockpiles shall not contain steel slag or other expansive material as determined by the Department.
- (c) Conglomerate 3/8. Conglomerate 3/8 RAP stockpiles shall consist of RAP from Class I, Superpave (High ESAL), HMA (High ESAL), or equivalent mixtures. The coarse aggregate in this RAP shall be crushed aggregate and may represent more than one aggregate type and/or quality but shall be at least B quality. This RAP may have an

inconsistent gradation and/or asphalt binder content prior to processing. All conglomerate 3/8 RAP shall be processed prior to testing by crushing to where all RAP shall pass the 3/8 in. (9.5 mm) or smaller screen. Conglomerate 3/8 RAP stockpiles shall not contain steel slag or other expansive material as determined by the Department.

- (d) Conglomerate "D" Quality (DQ). Conglomerate DQ RAP stockpiles shall consist of RAP from Class I, Superpave (High or Low ESAL), HMA (High or Low ESAL), or equivalent mixtures. The coarse aggregate in this RAP may be crushed or round but shall be at least D quality. This RAP may have an inconsistent gradation and/or asphalt binder content. Conglomerate DQ RAP stockpiles shall not contain steel slag or other expansive material as determined by the Department.
- (e) Non-Quality. RAP stockpiles that do not meet the requirements of the stockpile categories listed above shall be classified as "Non-Quality".

RAP containing contaminants, such as earth, brick, sand, concrete, sheet asphalt, bituminous surface treatment (i.e. chip seal), pavement fabric, joint sealants, etc., will be unacceptable unless the contaminants are removed to the satisfaction of the Engineer. Sheet asphalt shall be stockpiled separately.

1031.03 Testing. When used in HMA, the RAP shall be sampled and tested either during or after stockpiling.

For testing during stockpiling, washed extraction samples shall be run at the minimum frequency of one sample per 500 tons (450 metric tons) for the first 2000 tons (1800 metric tons) and one sample per 2000 tons (1800 metric tons) thereafter. A minimum of five tests shall be required for stockpiles less than 4000 tons (3600 metric tons).

For testing after stockpiling, the Contractor shall submit a plan for approval to the District proposing a satisfactory method of sampling and testing the RAP pile either in-situ or by restockpiling. The sampling plan shall meet the minimum frequency required above and detail the procedure used to obtain representative samples throughout the pile for testing.

Before extraction, each field sample shall be split to obtain two samples of test sample size. One of the two test samples from the final split shall be labeled and stored for Department use. The Contractor shall extract the other test sample according to Department procedure. The Engineer reserves the right to test any sample (split or Department-taken) to verify Contractor test results.

(a) Testing Conglomerate 3/8. In addition to the requirements above, conglomerate 3/8 RAP shall be tested for maximum theoretical specific gravity ( $G_{mm}$ ) at a frequency of one sample per 500 tons (450 metric tons) for the first 2000 tons (1800 metric tons) and one sample per 2000 tons (1800 metric tons) thereafter. A minimum of five tests shall be required for stockpiles less than 4000 tons (3600 metric tons).

(b) Evaluation of Test Results. All of the extraction results shall be compiled and averaged for asphalt binder content and gradation and, when applicable G<sub>mm</sub>. Individual extraction test results, when compared to the averages, will be accepted if within the tolerances listed below.

Parameter	Homogeneous / Conglomerate	Conglomerate "D" Quality
1 in. (25 mm)		±5%
1/2 in. (12.5 mm)	±8%	± 15 %
No. 4 (4.75 mm)	±6%	± 13 %
No. 8 (2.36 mm)	± 5 %	
No. 16 (1.18 mm)		± 15 %
No. 30 (600 μm)	± 5 %	
No. 200 (75 μm)	± 2.0 %	± 4.0 %
Asphalt Binder	± 0.4 % <sup>1/</sup>	± 0.5 %
G <sub>mm</sub>	± 0.02 2/	

- 1/ The tolerance for conglomerate 3/8 shall be  $\pm\,0.3$  %.
- 2/ Applies only to conglomerate 3/8. When variation of the  $G_{mm}$  exceeds the  $\pm~0.02$  tolerance, a new conglomerate 3/8 stockpile shall be created which will also require an additional mix design.

If more than 20 percent of the individual sieves are out of the gradation tolerances, or if more than 20 percent of the asphalt binder content test results fall outside the appropriate tolerances, the RAP shall not be used in HMA unless the RAP representing the failing tests is removed from the stockpile. All test data and acceptance ranges shall be sent to the District for evaluation.

With the approval of the Engineer, the ignition oven may be substituted for extractions according to the Illinois Test Procedure, "Calibration of the Ignition Oven for the Purpose of Characterizing Reclaimed Asphalt Pavement (RAP)".

1031.04 Quality Designation of Aggregate in RAP. The quality of the RAP shall be set by the lowest quality of coarse aggregate in the RAP stockpile and are designated as follows.

- (a) RAP from Class I, Superpave (High ESAL), or HMA (High ESAL) surface mixtures are designated as containing Class B quality coarse aggregate.
- (b) RAP from Superpave (Low ESAL)/HMA (Low ESAL) IL-19.0L binder and IL-9.5L surface mixtures are designated as Class D quality coarse aggregate.
- (c) RAP from Class I, Superpave (High ESAL), or HMA (High ESAL) binder mixtures, bituminous base course mixtures, and bituminous base course widening mixtures are designated as containing Class C quality coarse aggregate.

(d) RAP from bituminous stabilized subbase and BAM shoulders are designated as containing Class D quality coarse aggregate.

#### 1031.05 Use of RAP in HMA. The use of RAP in HMA shall be as follows.

- (a) Coarse Aggregate Size. The coarse aggregate in all RAP shall be equal to or less than the nominal maximum size requirement for the HMA mixture to be produced.
- (b) Steel Slag Stockpiles. RAP stockpiles containing steel slag or other expansive material, as determined by the Department, shall be homogeneous and will be approved for use in HMA (High ESAL and Low ESAL) surface mixtures only.
- (c) Use in HMA Surface Mixtures (High and Low ESAL). RAP stockpiles for use in HMA surface mixtures (High and Low ESAL) shall be either homogeneous or conglomerate 3/8, in which the coarse aggregate is Class B quality or better.
- (d) Use in HMA Binder Mixtures (High and Low ESAL), HMA Base Course, and HMA Base Course Widening. RAP stockpiles for use in HMA binder mixtures (High and Low ESAL), HMA base course, and HMA base course widening shall be homogeneous, conglomerate 5/8, or conglomerate 3/8, in which the coarse aggregate is Class C quality or better.
- (e) Use in Shoulders and Subbase. RAP stockpiles for use in HMA shoulders and stabilized subbase (HMA) shall be homogeneous, conglomerate 5/8, conglomerate 3/8, or conglomerate DQ.
- (f) The use of RAP shall be a contractor's option when constructing HMA in all contracts. When the contractor chooses the RAP option, the percentage of RAP shall not exceed the amounts indicated in the table for a given N Design.

#### Max RAP Percentage

HMA MIXTURES 1/, 3/	MAXIMUM % RAP					
Ndesign	Binder/Leveling Binder	Surface	Polymer Modified			
30	30	30	10			
50	25	15	10			
70	15 / 25 <sup>2/</sup>	10 / 15 <sup>2/</sup>	10			
90	10	10	10			
105	10	10	10			

- 1/ For HMA Shoulder and Stabilized Sub-Base (HMA) N-30, the amount of RAP shall not exceed 50% of the mixture.
- 2/ Value of Max % RAP if 3/8 RAP is utilized.

3/ When RAP exceeds 20%, the high & low virgin asphalt binder grades shall each be reduced by one grade (i.e. 25% RAP would require a virgin asphalt binder grade of PG64-22 to be reduced to a PG58-28).

**1031.06 HMA Mix Designs.** At the Contractor's option, HMA mixtures may be constructed utilizing RAP material meeting the above detailed requirements.

RAP designs shall be submitted for volumetric verification. If additional RAP stockpiles are tested and found that no more than 20 percent of the results, as defined under "Testing" herein, are outside of the control tolerances set for the original RAP stockpile and HMA mix design, and meets all of the requirements herein, the additional RAP stockpiles may be used in the original mix design at the percent previously verified.

**1031.07 HMA Production.** The coarse aggregate in all RAP used shall be equal to or less than the nominal maximum size requirement for the HMA mixture being produced.

To remove or reduce agglomerated material, a scalping screen, crushing unit, or comparable sizing device approved by the Engineer shall be used in the RAP feed system to remove or reduce oversized material. If material passing the sizing device adversely affects the mix production or quality of the mix, the sizing device shall be set at a size specified by the Engineer.

If the RAP control tolerances or QC/QA test results require corrective action, the Contractor shall cease production of the mixture containing RAP and either switch to the virgin aggregate design or submit a new RAP design. When producing mixtures containing conglomerate 3/8 RAP, a positive dust control system shall be utilized.

HMA plants utilizing RAP shall be capable of automatically recording and printing the following information.

- (a) Dryer Drum Plants.
  - (1) Date, month, year, and time to the nearest minute for each print.
  - (2) HMA mix number assigned by the Department.
  - (3) Accumulated weight of dry aggregate (combined or individual) in tons (metric tons) to the nearest 0.1 ton (0.1 metric ton).
  - (4) Accumulated dry weight of RAP in tons (metric tons) to the nearest 0.1 ton (0.1 metric ton).
  - (5) Accumulated mineral filler in revolutions, tons (metric tons), etc. to the nearest 0.1 unit.

- (6) Accumulated asphalt binder in gallons (liters), tons (metric tons), etc. to the nearest 0.1 unit.
- (7) Residual asphalt binder in the RAP material as a percent of the total mix to the nearest 0.1 percent.
- (8) Aggregate and RAP moisture compensators in percent as set on the control panel. (Requied when accumulated or individual aggregate and RAP are printed in wet condition.)
- (b) Batch Plants.
  - (1) Date, month, year, and time to the nearest minute for each print.
  - (2) HMA mix number assigned by the Department.
  - (3) Individual virgin aggregate hot bin batch weights to the nearest pound (kilogram).
  - (4) Mineral filler weight to the nearest pound (kilogram).
  - (5) RAP weight to the nearest pound (kilogram).
  - (6) Virgin asphalt binder weight to the nearest pound (kilogram).
  - (7) Residual asphalt binder in the RAP material as a percent of the total mix to the nearest 0.1 percent.

The printouts shall be maintained in a file at the plant for a minimum of one year or as directed by the Engineer and shall be made available upon request. The printing system will be inspected by the Engineer prior to production and verified at the beginning of each construction season thereafter.

1031.08 RAP in Aggregate Surface Course and Aggregate Shoulders. The use of RAP in aggregate surface course and aggregate shoulders shall be as follows.

- (a) Stockpiles and Testing. RAP stockpiles may be any of those listed in Article 1031.02, except "Other". The testing requirements of Article 1031.03 shall not apply.
- (b) Gradation. One hundred percent of the RAP material shall pass the 1 1/2 in. (37.5 mm) sieve. The RAP material shall be reasonably well graded from coarse to fine. RAP material that is gap-graded or single sized will not be accepted."

#### REFLECTIVE SHEETING ON CHANNELIZING DEVICES (BDE)

Effective: April 1, 2007

Revise the seventh paragraph of Article 1106.02 of the Standard Specifications to read:

"At the time of manufacturing, the retroreflective prismatic sheeting used on channelizing devices shall meet or exceed the initial minimum coefficient of retroreflection as specified in the following table. Measurements shall be conducted according to ASTM E 810, without averaging. Sheeting used on cones, drums and flexible delineators shall be reboundable as tested according to ASTM D 4956. Prestriped sheeting for rigid substrates on barricades shall be white and orange.

Initial Minimum Coefficient of Retroreflection candelas/foot candle/sq ft (candelas/lux/sq m) of material						
Observation Angle (deg.)	Entrance Angle (deg.)	White	Orange	Fluorescent Orange		
0.2	-4	365	160	150		
0.2	+30	175	80	70		
0.5	-4	245	100	95		
0.5	+30	100	50	40"		

Revise the first sentence of the first paragraph of Article 1106.02(c) of the Standard Specifications to read:

"Barricades and vertical panels shall have alternating white and orange stripes sloping downward at 45 degrees toward the side on which traffic will pass."

Revise the third sentence of the first paragraph of Article 1106.02(d) of the Standard Specifications to read:

"The bottom panels shall be 8 x 24 in.  $(200 \times 600 \text{ mm})$  with alternating white and orange stripes sloping downward at 45 degrees toward the side on which traffic will pass."

#### REINFORCEMENT BARS (BDE)

Effective: November 1, 2005 Revised: January 2, 2008

Revise Article 1006.10(a) of the Standard Specifications to read:

- " (a) Reinforcement Bars. Reinforcement bars will be accepted according to the current Bureau of Materials and Physical Research Policy Memorandum, "Reinforcement Bar and/or Dowel Bar Plant Certification Procedure". The Department will maintain an approved list of producers.
  - (1) Reinforcement Bars (Non-Coated). Reinforcement bars shall be according to ASTM A 706 (A 706M), Grade 60 (420) for deformed bars and the following.
    - a. For straight bars furnished in cut lengths and with a well-defined yield point, the yield point shall be determined as the elastic peak load, identified by a halt or arrest of the load indicator before plastic flow is sustained by the bar and dividing it by the nominal cross-sectional area of the bar.
    - b. For bars without a well-defined yield point, including bars straightened from coils, the yield strength shall be determined by taking the corresponding load at 0.005 strain as measured by an extensometer (0.5% elongation under load) and dividing it by the nominal cross-sectional area of the bar.
    - c. For bars straightened from coils or bars bent from fabrication, there shall be no upper limit on yield strength; and for bar designation Nos. 3 6 (10 19), the elongation after rupture shall be at least 9%.
    - d. Heat Numbers. Bundles or bars at the construction site shall be marked or tagged with heat identification numbers of the bar producer.
    - e. Guided Bend Test. Bars may be subject to a guided bend test across two pins which are free to rotate, where the bending force shall be centrally applied with a fixed or rotating pin of a certain diameter as specified in Table 3 of ASTM A 706 (A 706M). The dimensions and clearances of this guided bend test shall be according to ASTM E 190.
    - f. Spiral Reinforcement. Spiral reinforcement shall be deformed or plain bars conforming to the above requirements or cold-drawn steel wire conforming to AASHTO M 32.
  - (2) Epoxy Coated Reinforcement Bars. Epoxy coated reinforcement bars shall be according to Article 1006.10(a)(1) and shall be epoxy coated according to AASHTO M 284 (M 284M) and the following.

- a. Certification. The epoxy coating applicator shall be certified according to the current Bureau of Materials and Physical Research Policy Memorandum, "Epoxy Coating Plant Certification Procedure". The Department will maintain an approved list.
- b. Coating Thickness. The thickness of the epoxy coating shall be 7 to 12 mils (0.18 to 0.30 mm). When spiral reinforcement is coated after fabrication, the thickness of the epoxy coating shall be 7 to 20 mils (0.18 to 0.50 mm).
- c. Cutting Reinforcement. Reinforcement bars may be sheared or sawn to length after coating, providing the end damage to the coating does not extend more than 0.5 in. (13 mm) back and the cut is patched before any visible rusting appears. Flame cutting will not be permitted."

# RETROREFLECTIVE SHEETING, NONREFLECTIVE SHEETING, AND TRANSLUCENT OVERLAY FILM FOR HIGHWAY SIGNS (BDE)

Effective: April 1, 2007

<u>General</u>. This special provision covers retroreflective sheeting and translucent overlay films intended for application on new or refurbished aluminum. The sheeting serves as the reflectorized background for sign messages and as cutout legends and symbols applied to the reflectorized background. Messages may be applied in opaque black or transparent colors.

This special provision also covers nonreflective sheeting for application on new or refurbished aluminum, and as material for cutout legends and symbols applied to the reflectorized background.

All material furnished under this specification shall have been manufactured within 18 months of the delivery date. All material shall be supplied by the same manufacturer.

Retroreflective Sheeting Properties. Retroreflective sheeting shall consist of a flexible, colored, prismatic, or glass lens elements adhered to a synthetic resin, encapsulated by a flexible, transparent plastic having a smooth outer surface and shall meet the following requirements.

Only suppliers whose products have been tested and approved in the Department's periodic Sheeting Study will be eligible to supply material. All individual batches and or lots of material shall be tested and approved by the Department. The Department reserves the right to sample and test delivered materials according to Federal Specification LS-300.

- (a) Adhesive. The sheeting shall have a Class 1, pre-coated, pressure sensitive adhesive according to ASTM D 4956. The adhesive shall have a protective liner that is easily removed when tested according to ASTM D 4956. The adhesive shall be capable of being applied to new or refurbished aluminum and reflectorized backgrounds without additional adhesive.
- (b) Color. The sheeting shall be uniform in color and devoid of streaks throughout the length of each roll. The color shall conform to the latest appropriate standard color tolerance chart issued by the U.S. Department of Transportation, Federal Highway Administration and to the daytime and nighttime color requirements of ASTM D 4956. Sheeting used for side by side overlay applications shall have a Hunter Lab Delta E of less than 3.
- (c) Coefficient of Retroreflection. When tested according to ASTM E 810, without averaging, the sheeting shall have a minimum coefficient of retroreflection as shown in the following tables. The brightness of the sheeting when totally wet shall be a minimum of 90 percent of the values shown when tested according to the standard rainfall test specified in Section 7.10.1 of AASHTO M 268-84.

Type A Sheeting
Minimum Coefficient of Retroreflection
candelas/foot candle/sq ft (candelas/lux/sq m) of material

Type A

							<del>,                                     </del>	
Observation	Entrance				ł			
Angle (deg.)	Angle (deg.)	White	Yellow	Orange	Red	Green	Blue	Brown
0.2	-4	250	170	100	45	45	20	12
0.2	+30	150	100	60	25	25	12	8.5
0.5	-4	95	65	30	15	15	8	5
0.5	+30	75	50	25	10	10	5	3.5

# Type AA Sheeting Minimum Coefficient of Retroreflection candelas/foot candle/sq ft (candelas/lux/sq m) of material

Type AA (0 and 90 degree rotation)

	•	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	(				
Observation Angle (deg.)	Entrance Angle (deg.)	White	Yellow	Red	Green	Blue	FO
0.2	-4	800	660	215	80	43	200
0.2	+30	400	340	100	35	20	120
0.5	-4	200	160	45	20	9.8	80
0.5	+30	100	85	26	10	5.0	50

Type AA (45 degree rotation)

		- 14.4 17	
Observation Angle (deg.)	Entrance Angle (deg.)	Yellow	FO
0.2	-4	550	165
0.2	+30	130	45
0.5	-4	145	70
0.5	+30	70	40

# Type AP Sheeting Minimum Coefficient of Retroreflection candelas/foot candle/sq ft (candelas/lux/sq m) of material

Type AP

Observation Angle (deg.)	Entrance Angle (deg.)	White	Yellow	Red	Green	Blue	Brown	FO
0.2	-4	550	425	100	75	50	30	275
0.2	+30	200	150	40	35	25	15	90
0.5	-4	300	250	60	35	25	20	150
0.5	+30	100	70	20	20	10	5	50

# Type AZ Sheeting Minimum Coefficient of Retroreflection candelas/foot candle/sq ft (candelas/lux/sq m) of material

Type AZ (0 degree rotation)

Observation	Entrance	.,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	_ (+ 5					
Angle (deg.)	Angle (deg.)	White	Yellow	Red	Green	Blue	FYG	FY
0.2	-4	430	350	110	45	20	325	240
0.2	+30	235	140	60	24	11	200	150
0.5	-4	250	200	60	25	10	235	165
0.5	+30	170	135	40	19	7	105	75
1.0	-4	70	45	10	10	4	70	30
1.0	+30	30	20	7	5	2.5	45	15

Type AZ (90 degree rotation)

Observation	Entrance							
Angle (deg.)	Angle (deg.)	White	Yellow	Red	Green	Blue	FYG	FY
0.2	-4	320	250	100	45	20	300	220
0.2	+30	235	140	40	24	11	200	150
0.5	-4	240	200	60	25	10	235	165
0.5	+30	100	85	20	10	7	80	75
1.0	-4	30	30	7	5	4	65	20
1.0	+30	15	15	5	2	2	30	10

- (d) Gloss. The sheeting surface shall exhibit a minimum 85 degree gloss-meter rating of 50 when tested according to ASTM D 523.
- (e) Durability. When processed and applied, the sheeting shall be weather resistant.

Accelerated weathering testing will be performed for 1000 hours (300 hours for orange/FO) according to ASTM G 151. The testing cycle will consist of 8 hours of light at 140 °F (60 °C), followed by 4 hours of condensation at 104 °F (40 °C). Following accelerated weathering, the sheeting shall exhibit a minimum of 80 percent of its initial minimum coefficient of retroreflection as listed in the previous tables.

Outdoor weathering will entail an annual evaluation of material placed in an outdoor rack with a 45 degree angle and a southern sun exposure. The sheeting will be evaluated for five years. Following weathering, the test specimens will be cleaned by immersing them in a five percent hydrochloric acid solution for 45 seconds, then rinsed with water and blotted dry with a soft clean cloth. Following cleaning, the applied sheeting shall show no appreciable discoloration, cracking, streaking, crazing, blistering, or dimensional change. The sheeting shall exhibit a Hunter Lab Delta E of 5 or less when compared to the original.

- (f) Shrinkage. When tested according to ASTM D 4956, the sheeting shall not shrink in any dimension more than 1/32 in. (0.8 mm) in ten minutes and not more than 1/8 in. (3 mm) in 24 hours.
- (g) Workability. The sheeting shall show no cracking, scaling, pitting, blistering, edge lifting, inter-film splitting, curling, or discoloration when processed and applied using mutually acceptable processing and application procedures.
- (h) Splices. A single roll of sheeting shall contain a maximum of four splices per 50 yd (45 m) length. The sheeting shall be overlapped a minimum of 3/16 in. (5 mm) at each splice.
- (i) Adhesive Bond. The sheeting shall form a durable bond to smooth, corrosion and weather-resistant surfaces and adhere securely when tested according to ASTM D 4956.
- (j) Positionability. Sheeting, with ASTM D 4956 Class 3 adhesive, used for manufacturing cutout legends and borders shall provide sufficient positionability during the fabrication process to permit removal and reapplication without damage to either the legend or sign background and shall have a plastic liner suitable for use on bed cutting machines. Thereafter, all other adhesive and bond requirements contained in the specification shall apply.

Positionablility shall be verified by cutting 4 in. (100 mm) letters E, I, K, M, S, W, and Y out of the positionable material. The letters shall then be applied to a sheeted aluminum blank using a single pass of a two pound roller. The letters shall sit for five minutes and then a putty knife shall be used to lift a corner. The thumb and fore finger shall be used to slowly pull the lifted corner to lift letters away from the sheeted aluminum. The letters shall not tear or distort when removed.

- (k) Thickness. The thickness of the sheeting without the protective liner shall be less than or equal to 0.015 in. (0.4 mm), or 0.025 in. (0.6 mm) for prismatic material.
- (I) Processing. The sheeting shall permit cutting and color processing according to the sheeting manufacturer's specifications at temperatures of 60 to 100 °F (15 to 38 °C) and within a relative humidity range of 20 to 80 percent. The sheeting shall be heat resistant and permit forced curing without staining the applied or unapplied sheeting at temperatures recommended by the manufacturer. The sheeting shall be solvent resistant and capable of being cleaned with VM&P naptha, mineral spirits, and turpentine.

Transparent color and opaque black inks shall be single component and low odor. The inks shall dry within eight hours and not require clear coating. After color processing on white sheeting, the sheeting shall show no appreciable discoloration, cracking, streaking, crazing, blistering, or dimensional change when tested for durability (e). The ink on the weathered, prepared panel shall exhibit a Hunter Lab Delta E of 5 or less when compared to the original.

Transparent color electronic cutting films shall be acrylic. After application to white sheeting, the films shall show no appreciable discoloration, cracking, streaking, crazing, blistering, or dimensional change when tested for durability (e). The films on the weathered, prepared panel shall exhibit a Hunter Lab Delta E of 5 or less when compared to the original.

Transparent colors screened, or transparent acrylic electronic cutting films, on white sheeting, shall have a minimum initial coefficient of retroreflection values of 50 percent for yellow and red, and a minimum 70 percent for green, blue, and brown of the 0.2 degree observation angle/-4.0 degree entrance angle values as listed in the previous tables for the color being applied. After durability testing, the colors shall retain a minimum 80 percent of the initial coefficient of retroreflection.

- (m) Identification. The sheeting shall have a distinctive overall pattern in the sheeting unique to the manufacturer. If material orientation is required for optimum retroreflectivity, permanent orientation marks shall be incorporated into the face of the sheeting. Neither the overall pattern nor the orientation marks shall interfere with the reflectivity of the sheeting.
- (n) Packaging. Both ends of each box shall be clearly labeled with the sheeting type, color, adhesive type, manufacturer's lot number, date of manufacture, and supplier's name. Material Safety Data Sheets and technical bulletins for all materials shall be furnished to the Department with each shipment.

Nonreflective Sheeting Properties. Nonreflective sheeting shall consist of a flexible, pigmented cast vinyl film having a smooth, flat outer surface and shall meet the following requirements.

The Department reserves the right to sample and test delivered materials according to Federal Specification LS-300.

- (a) Adhesive. The sheeting shall have a Class 1, pre-coated, pressure sensitive adhesive according to ASTM D 4956. The adhesive shall have a protective liner that is easily removed when tested according to ASTM D 4956. The adhesive shall be capable of being applied to new or refurbished aluminum and reflectorized backgrounds without additional adhesive.
- (b) Color. The sheeting shall be uniform in color and devoid of streaks throughout the length of each roll.
- (c) Gloss. The sheeting shall exhibit a minimum 85 degree gloss-meter rating of 40 when tested according to ASTM D 523.
- (d) Durability. Applied sheeting that has been vertically exposed to the elements for seven years shall show no appreciable discoloration, cracking, crazing, blistering, delamination, or loss of adhesion. A slight amount of chalking is permitted but the sheeting shall not support fungus growth.

- (e) Testing. Test panels shall be prepared by applying the sheeting to 6 1/2 x 6 1/2 in. (165 x 165 mm) pieces of aluminum according to the manufacturer's specifications. The edges of the panel shall be trimmed evenly and aged 48 hours at 70 to 90 °F (21 to 32 °C). Shrinkage and immersion testing shall be as follows.
  - (1) Shrinkage. The sheeting shall not shrink more then 1/64 in. (0.4 mm) from any panel edge when subjected to a temperature of 150 °F (66 °C) for 48 hours and shall be sufficiently heat resistant to retain adhesion after one week at 150 °F (66 °C).
  - (2) Immersion Testing. The sheeting shall show no appreciable decrease in adhesion, color, or general appearance when examined one hour after being immersed to a depth of 2 or 3 in. (50 or 75 mm) in the following solutions at 70 to 90 °F (21 to 32 °C) for specified times.

Solution	Immersion Time (hours)
Reference Fuel (M I L-F-8799A) (15 parts xylol and 85 parts mineral spirits by weight)	1
Distilled Water	24
SAE No. 20 Motor Oil	24
Antifreeze (1/2 ethylene glycol, 1/2 distilled water)	24

- (f) Adhesive Bond: The sheeting shall form a durable bond to smooth, corrosion and weather-resistant surfaces and adhere securely when tested according to ASTM D 4956.
- (g) Thickness. The thickness of the sheeting without the protective liner shall be a maximum of 0.005 in. (0.13 mm).
- (h) Cutting. Material used on bed cutting machines shall have a smooth plastic liner.
- (i) Identification. The sheeting shall have a distinctive overall pattern in the sheeting unique to the manufacturer. If material orientation is required for optimum retroreflectivity, permanent orientation marks shall be incorporated into the face of the sheeting. Neither the overall pattern nor the orientation marks shall interfere with the reflectivity of the sheeting.
- (j) Packaging. Both ends of each box shall be clearly labeled with the sheeting type, color, adhesive type, manufacturer's lot number, date of manufacture, and supplier's name. Material Safety Data Sheets and technical bulletins for all materials shall be furnished to the Department with each shipment.

### SEEDING (BDE)

Effective: July 1, 2004 Revised: August 1, 2007

Revise the following seeding mixtures shown in Table 1 of Article 250.07 of the Standard Specifications to read:

-	"Tab	ole 1 - SEEDING MIXTURES		
Class – Type		Seeds	lb/acre (kg/hectare)	
2	Roadside Mixture 7/	Tall Fescue (Inferno, Tarheel II, Quest, Blade Runner, or Falcon IV)	100 (110)	
		Perennial Ryegrass	50 (55)	
		Creeping Red Fescue	40 (50)	
		Red Top	10 (10)	
2A	Salt Tolerant Roadside Mixture 7/	Tall Fescue (Inferno, Tarheel II, Quest, Blade Runner, or Falcon IV)	60 (70)	
		Perennial Ryegrass	20 (20)	
		Red Fescue (Audubon, Sea Link, or Epic)	30 (20)	
		Hard Fescue (Rescue 911, Spartan II, or Reliant IV)	30 (20)	
		Fults Salt Grass 1/	60 (70)"	

Revise Table II of Article 1081.04(c)(6) of the Standard Specifications to read:

		TAI	BLE II			
Variety of Seeds	Hard Seed % Max.	Purity % Min.	Pure Live Seed % Min.	Weed % Max.	Secondary * Noxious Weeds No. per oz (kg) Max. Permitted	Notes
Alfalfa	20	92	89	0.50	6 (211)	1/
Clover, Alsike	15	92	87	0.30	6 (211)	2/
Red Fescue, Audubon	0	97	82	0.10	3 (105)	-
Red Fescue, Creeping	_	97	82	1.00	6 (211)	-
Red Fescue, Epic	-	98	83	0.05	1 (35)	-
Red Fescue, Sea Link	-	98	83	0.10	3 (105)	-
Tall Fescue, Blade Runner	-	98	83	0.10	2 (70)	-
Tall Fescue, Falcon IV	-	98	83	0.05	1 (35)	-
Tall Fescue, Inferno	0	98	83	0.10	2 (70)	-
Tall Fescue, Tarheel II	_	97	82	1.00	6 (211)	-
Tall Fescue, Quest	0	98	83	0.10	2 (70)	
Fults Salt Grass	0	98	85	0.10	2 ( 70)	-
Kentucky Bluegrass	-	97	80	0.30	7 (247)	4/
Oats	-	92	88	0.50	2 ( 70)	3/
Redtop	-	90	78	1.80	5 (175)	3/

TABLE II						
Variety of Seeds	Hard Seed % Max.	Purity % Min.	Pure Live Seed % Min.	Weed % Max.	Secondary * Noxious Weeds No. per oz (kg) Max. Permitted	Notes
Ryegrass, Perennial, Annual	-	97	85	0.30	5 (175)	3/
Rye, Grain, Winter	-	92	83	0.50	2 ( 70)	3/
Hard Fescue, Reliant IV	-	98	83	0.05	1 (35)	-
Hard Fescue, Rescue 911	0	• 97	82	0.10	3 (105)	-
Hard Fescue, Spartan II	-	98	83	0.10	3 (105)	-
Timothy	-	92	84	0.50	5 (175)	3/
Wheat, hard Red Winter	-	92	89	0.50	2 ( 70)	3/"

Revise the first sentence of the first paragraph of Article 1081.04(c)(7) of the Standard Specifications to read:

"The seed quantities indicated per acre (hectare) for Prairie Grass Seed in Classes 3, 3A, 4, 4A, 6, and 6A in Article 250.07 shall be the amounts of pure, live seed per acre (hectare) for each species listed."

#### SELF-CONSOLIDATING CONCRETE FOR PRECAST PRODUCTS (BDE)

Effective: July 1, 2004 Revised: January 1, 2007

<u>Definition</u>. Self-consolidating concrete is a flowable mixture that does not require mechanical vibration for consolidation.

Usage. Self-consolidating concrete may be used for precast concrete products.

Materials. Materials shall be according to Section 1021 of the Standard Specifications.

Mix Design Criteria. The mix design criteria shall be as follows:

- (a) The minimum cement factor shall be according to Article 1020.04 of the Standard Specifications. If the maximum cement factor is not specified, it shall not exceed 7.05 cwt/cu yd (418 kg/cu m).
- (b) The maximum allowable water/cement ratio shall be according to Article 1020.04 of the Standard Specifications or 0.44, whichever is lower.
- (c) The slump requirements of Article 1020.04 of the Standard Specifications shall not apply.
- (d) The coarse aggregate gradations shall be CA 13, CA 14, CA 16, or a blend of these gradations. CA 11 may be used when the Contractor provides satisfactory evidence to the Engineer that the mix will not segregate. The fine aggregate proportion shall be a maximum 50 percent by weight (mass) of the total aggregate used.
- (e) The slump flow range shall be ±2 in. (±50 mm) of the Contractor target value, and within the overall Department range of 20 in. (510 mm) minimum to 28 in. (710 mm) maximum.
- (f) The visual stability index shall be a maximum of 1.
- (g) The J-ring value shall be a maximum of 4 in. (100 mm). The Contractor may specify a lower maximum in the mix design.
- (h) The L-box blocking ratio shall be a minimum of 60 percent. The Contractor may specify a higher minimum in the mix design.
- (i) The column segregation index shall be a maximum 15 percent.
- (j) The hardened visual stability index shall be a maximum of 1.

<u>Placing and Consolidating</u>. The maximum distance of horizontal flow from the point of deposit shall be 25 ft (7.6 m), unless approved otherwise by the Engineer.

Concrete shall be rodded with a piece of lumber, conduit, or vibrator if the material has lost its fluidity prior to placement of additional concrete. The vibrator shall be the pencil head type with a maximum diameter or width of 1 in. (25 mm). Any other method for restoring the fluidity of the concrete shall be approved by the Engineer.

Mix Design Approval. The Contractor shall obtain mix design approval according to the Department's Policy Memorandum "Quality Control/Quality Assurance Program for Precast Concrete Products".

#### **SILT FILTER FENCE (BDE)**

Effective: January 1, 2008

For silt filter fence fabric only, revise Article 1080.02 of the Standard Specifications to read:

"1080.02 Geotextile Fabric. The fabric for silt filter fence shall be a woven fabric meeting the requirements of AASHTO M 288 for unsupported silt fence with less than 50 percent geotextile elongation."

Replace the last sentence of Article 1081.15(b) of the Standard Specifications with the following:

"Silt filter fence stakes shall be a minimum of 4 ft (1.2 m) long and made of either wood or metal. Wood stakes shall be 2 in. x 2 in. (50 mm x 50 mm). Metal stakes shall be a standard T or U shape having a minimum weight (mass) of 1.32 lb/ft (600 g/300 mm)."

### **STONE GRADATION TESTING (BDE)**

Effective: November 1, 2007

Revise the first sentence of note 1/ of the Erosion Protection and Sediment Control Gradations table of Article 1005.01(c)(1) of the Standard Specifications to read:

"A maximum of 15 percent of the total test sample by weight may be oversize material."

#### SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE)

Effective: April 2, 2005

To account for the preparatory work and operations necessary for the movement of subcontractor personnel, equipment, supplies, and incidentals to the project site and for all other work or operations that must be performed or costs incurred when beginning work approved for subcontracting in accordance with Article 108.01 of the Standard Specifications, the Contractor shall make a mobilization payment to each subcontractor.

This mobilization payment shall be made at least 14 days prior to the subcontractor starting work. The amount paid shall be equal to 3 percent of the amount of the subcontract reported on form BC 260A submitted for the approval of the subcontractor's work.

This provision shall be incorporated directly or by reference into each subcontract approved by the Department.

#### **TEMPORARY EROSION CONTROL (BDE)**

Effective: November 1, 2002 Revised: January 1, 2008

Revise the third paragraph of Article 280.03 of the Standard Specifications to read:

"Erosion control systems shall be installed prior to beginning any activities which will potentially create erodible conditions. Erosion control systems for areas outside the limits of construction such as storage sites, plant sites, waste sites, haul roads, and Contractor furnished borrow sites shall be installed prior to beginning soil disturbing activities at each area. These offsite systems shall be designed by the Contractor and be subject to the approval of the Engineer."

Add the following paragraph after the third paragraph of Article 280.03 of the Standard Specifications:

"The temporary erosion and sediment control systems shown on the plans represent the minimum systems anticipated for the project. Conditions created by the Contractor's operations, or for the Contractor's convenience, which are not covered by the plans, shall be protected as directed by the Engineer at no additional cost to the Department. Revisions or modifications of the erosion and sediment control systems shall have the Engineer's written approval."

Add the following paragraph after the ninth paragraph of Article 280.07 of the Standard Specifications:

"Temporary or permanent erosion control systems required for areas outside the limits of construction will not be measured for payment."

Delete the tenth (last) paragraph of Article 280.08 of the Standard Specifications.

#### THERMOPLASTIC PAVEMENT MARKINGS (BDE)

Effective: January 1, 2007

Revise Article 1095.01(a) (2) of the Standard Specifications to read:

"(2) Pigment. The pigment used for the white thermoplastic compound shall be a high-grade pure (minimum 93 percent) titanium dioxide (Ti0<sub>2</sub>). The white pigment content shall be a minimum of ten percent by weight and shall be uniformly distributed throughout the thermoplastic compound.

The pigments used for the yellow thermoplastic compound shall not contain any hazardous materials listed in the Environmental Protection Agency Code of Federal Regulations (CFR) 40, Section 261.24, Table 1. The combined total of RCRA listed heavy metals shall not exceed 100 ppm when tested by X-ray fluorescence spectroscopy. The pigments shall also be heat resistant, UV stable and color-fast yellows, golds, and oranges, which shall produce a compound which shall match Federal Standard 595 Color No. 33538. The pigment shall be uniformly distributed throughout the thermoplastic compound."

Revise Article 1095.01(b) (1)e. of the Standard Specifications to read:

"e. Daylight Reflectance and Color. The thermoplastic compound after heating for four hours  $\pm$  five minutes at 425  $\pm$  3 °F (218.3  $\pm$  2 °C) and cooled at 77 °F (25 °C) shall meet the following requirements for daylight reflectance and color, when tested, using a color spectrophotometer with 45 degree circumferential/zero degree geometry, illuminant C, and two degree observer angle. The color instrument shall measure the visible spectrum from 380 to 720 nm with a wavelength measurement interval and spectral bandpass of 10 nm.

White: Daylight Reflectance .....75 percent min. \*Yellow: Daylight Reflectance .....45 percent min.

\*Shall meet the coordinates of the following color tolerance chart.

x 0.490 0.475 0.485 0.530 y 0.470 0.438 0.425 0.456"

Revise Article 1095.01(b) (1)k. of the Standard Specifications to read:

"k. Accelerated Weathering. After heating the thermoplastic for four hours ± five minutes at 425 ± 3 °F (218.3 ± 2 °C) the thermoplastic shall be applied to a steel wool abraded aluminum alloy panel (Federal Test Std. No. 141, Method 2013) at a film thickness of 30 mils (0.70 mm) and allowed to cool for 24 hours at room temperature. The coated panel shall be subjected to accelerated weathering

using the light and water exposure apparatus (fluorescent UV - condensation type) for 75 hours according to ASTM G 53 (equipped with UVB-313 lamps).

The cycle shall consist of four hours UV exposure at 122  $^{\circ}$ F (50  $^{\circ}$ C) followed by four hours of condensation at 104  $^{\circ}$ F (40  $^{\circ}$ C). UVB 313 bulbs shall be used. At the end of the exposure period, the panel shall not exceed 10 Hunter Lab Delta E units from the original material."

## WORKING DAYS (BDE)

Effective: January 1, 2002

The Contractor shall complete the work within **//o** working days.

# REQUIRED CONTRACT PROVISIONS FEDERAL-AID CONSTRUCTION CONTRACTS

		Page
l.	General	1
II.	Nondiscrimination	1
III.	Nonsegregated Facilities	3
IV.	Payment of Predetermined Minimum Wage	3
V.	Statements and Payrolls	6
VI.	Record of Materials, Supplies, and Labor	7
VIII.	Safety: Accident Prevention	7
IX.	False Statements Concerning Highway Projects	7
Χ.	Implementation of Clean Air Act and Federal	
	Water Pollution Control Act	8
XI.	Certification Regarding Debarment, Suspension,	
	Ineligibility, and Voluntary Exclusion	8
XII.	Certification Regarding Use of Contract Funds for	
	Lobbying	9

#### **ATTACHMENTS**

A. Employment Preference for Appalachian Contracts (included in Appalachian contracts only)

#### I. GENERAL

- 1. These contract provisions shall apply to all word performed on the contract by the contractor's own organization and with the assistance of workers under the contractor's immediate superintendence and to all work performed on the contract by piecework, station work, or by subcontract.
- 2. Except as otherwise provided for in each section, the contractor shall insert in each subcontract all of the stipulations contained in these Required Contract Provisions, and further require their inclusion in any lower tier subcontract or purchase order that may in turn be made. The Required Contract Provisions shall not be incorporated by reference in any case. The prime contractor shall be responsible for compliance by any subcontractor or lower tier subcontractor with these Required Contract Provisions.
- A breach of any of the stipulations contained in these Required Contract Provisions shall be sufficient grounds for termination of the contract.
- 4. A breach of the following clauses of the Required Contract Provisions may also be grounds for debarment as provided in 29 CFR 5.12:

Section I, paragraph 2; Section IV, paragraphs 1, 2, 3, 4 and 7; Section V, paragraphs 1 and 2a through 2g.

- 5. Disputes arising out of the labor standards provisions of Section IV (except paragraph 5) and Section V of these Required Contract Provisions shall not be subject to the general disputes clause of this contract. Such disputes shall be resolved in accordance with the procedures of the U.S. Department of Labor (DOL) as set forth in 29 CFR 5, 6 and 7. Disputes within the meaning of this clause include disputes between the contractor (or any of its subcontractors) and the contracting agency, the DOL, or the contractor's employees or their representatives.
- 6. Selection of Labor: During the performance of this contract, the contractor shall not:
  - a. Discriminate against labor from any other State, possession, or territory of the United States (except for employment preference for Appalachian contracts, when applicable, as specified in Attachment A), or
- b. Employ convict labor for any purpose within the limits of the project unless it is labor performed by convicts who are on parole, supervised release, or probation.

(Applicable to all Federal-aid construction contracts and to all related subcontracts of \$10,000 or more.)

- 1. Equal Employment Opportunity: Equal employment opportunity (EEO) requirements not to discriminate and to take affirmative action to assure equal opportunity as set forth under laws, executive orders, rules, regulations (28 CFR 35, 29 CFR 1630 and 41 CFR 60 (and orders of the Secretary of Labor as modified by the provisions prescribed herein, and imposed pursuant to 23 U.S.C. 140 shall constitute the EEO and specific affirmative action standards for the contractor's project activities under this contract. The Equal Opportunity Construction Contract Specifications set forth under 41 CFR 60-4.3 and the provisions of the American Disabilities Act of 1990 (42 U.S.C. 12101 et seg.) set forth under 28 CFR 35 and 29 CFR 1630 are incorporated by reference in this contract. In the execution of this contract, the contractor agrees to comply with the following minimum specific requirement activities of FFO:
  - a. The contractor will work with the State highway agency (SHA) and the Federal Government in carrying out EEO obligations and in their review of his/her activities under the contract.
  - b. The contractor will accept as his operating policy the following statement:

"It is the policy of this Company to assure that applicants are employed, and that employees are treated during employment, without regard to their race, religion, sex, color, national origin, age or disability. Such action shall include: employment, upgrading, demotion, or transfer; recruitment or recruitment advertising; layoff or termination; rates of pay or other forms of compensation; and selection for training, including apprenticeship, preapprenticeship, and/or on-the-job-training."

- 2. EEO Officer: The contractor will designate and make known to the SHA contracting officers an EEO Officer who will have the responsibility for an must be capable of effectively administering and promoting an active contractor program of EEO and who must be assigned adequate authority and responsibility to do so.
- 3. Dissemination of Policy: All members of the contractor's staff who are authorized to hire, supervise, promote, and discharge employees, or who recommend such action, or who are substantially involved in such action, will be made fully cognizant of, and will implement, the contractor's EEO policy and contractual responsibilities to provide EEO in each grade and classification of employment. To ensure that the above

Page 1

agreement will be met, the following actions will be taken as a minimum:

- a. Periodic meetings of supervisory and personnel office employees will be conducted before the start of work and then not less often than once every six months, at which time the contractor's EEO policy and its implementation will be reviewed and explained. The meetings will be conducted by the EEO Officer.
- b. All new supervisory or personnel office employees will be given a thorough indoctrination by the EEO Officer, covering all major aspects of the contractor's EEO obligations within thirty days following their reporting for duty with the contractor.
- c. All personnel who are engaged in direct recruitment for the project will be instructed by the EEO Officer in the contractor's procedures for locating and hiring minority group employees.
- d. Notices and posters setting forth the contractor's EEO policy will be placed in areas readily accessible to employees, applicants for employment and potential employees.
- e. The contractor's EEO policy and the procedures to implement such policy will be brought to the attention of employees by means of meetings, employee handbooks, or other appropriate means.
- 4. Recruitment: When advertising for employees, the contractor will include in all advertisements for employees the notation: "An Equal Opportunity Employer." All such advertisements will be placed in publications having a large circulation among minority groups in the area from which the project work force would normally be derived.
  - a. The contractor will, unless precluded by a valid bargaining agreement, conduct systematic and direct recruitment through public and private employees referral sources likely to yield qualified minority group applicants. To meet this requirement, the contractor will identify sources of potential minority group employees, and establish which such identified sources procedures whereby minority group applicants may be referred to the contractor for employment consideration.
  - b. In the event the contractor has a valid bargaining agreement providing for exclusive hiring hall referrals, he is expected to observe the provisions of that agreement to the extent that the system permits the contractor's compliance with EEO contract provisions. (The DOL has held that where implementation of such agreements have the effect of discriminating against minorities or women, or obligates the contractor to do the same, such implementation violates Executive Order 11246, as amended.)
  - c. The contractor will encourage his present employees to refer minority group applicants for employment. Information and procedures with regard to referring minority group applicants will be discussed with employees.
- 5. Personnel Actions: Wages, working conditions, and employee benefits shall be established and administered, and personnel actions of every type, including hiring, upgrading, promotion, transfer, demotion, layoff, and termination, shall be taken without regard to race, color, religion, sex, national origin, age or disability. The following procedures shall be followed:
  - a. The contractor will conduct periodic inspections of project sites to insure that working conditions and employee facilities do not indicate discriminatory treatment of project site personnel.
  - b. The contractor will periodically evaluate the spread of wages paid within each classification to determine any

paid within each classification to deter

evidence of discriminatory wage practices.

- c. The contractor will periodically review selected personnel actions in depth to determine whether there is evidence of discrimination. Where evidence is found, the contractor will promptly take corrective action. If the review indicates that the discrimination may extend beyond the actions reviewed, such corrective action shall include all affected persons.
- d. The contractor will promptly investigate all complaints of alleged discrimination made to the contractor in connection with his obligations under this contract, will attempt to resolve such complaints, and will take appropriate corrective action within a reasonable time. If the investigation indicates that the discrimination may affect persons other than the complainant, such corrective action shall include such other persons. Upon completion of each investigation, the contractor will inform every complainant of all of his avenues of appeal.

#### 6. Training and Promotion:

- a. The contractor will assist in locating, qualifying, and increasing the skills of minority group and women employees, and applicants for employment.
- b. Consistent with the contractor's work force requirements and as permissible under Federal and State regulations, the contractor shall make full use of training programs, i.e., apprenticeship, and on-the-job training programs for the geographical area of contract performance. Where feasible, 25 percent of apprentices or trainees in each occupation shall be in their first year of apprenticeship or training. In the event a special provision for training is provided under this contract, this subparagraph will be superseded as indicated in the special provision.
- c. The contractor will advise employees and applicants for employment of available training programs and entrance requirements for each.
- d. The contractor will periodically review the training and promotion potential of minority group and women employees and will encourage eligible employees to apply for such training and promotion.
- 7. Unions: If the contractor relies in whole or in part upon unions as a source of employees, the contractor will use his/her best efforts to obtain the cooperation of such unions to increase opportunities for minority groups and women within the unions, and to effect referrals by such unions of minority and female employees. Actions by the contractor either directly or through a contractor's association acting as agent will include the procedures set forth below:
  - a. The contractor will use best efforts to develop, in cooperation with the unions, joint training programs aimed toward qualifying more minority group members and women for membership in the unions and increasing the skills of minority group employees and women so that they may qualify for higher paying employment.
  - b. The contractor will use best efforts to incorporate an EEO clause into each union agreement to the end that such union will be contractually bound to refer applicants without regard to their race, color, religion, sex, national origin, age or disability.
  - c. The contractor is to obtain information as to the referral practices and policies of the labor union except that to the extent such information is within the exclusive possession of the labor union and such labor union refuses to furnish such information to the contractor, the contractor shall so certify to

the SHA and shall set forth what efforts have been made to obtain such information.

- d. In the event the union is unable to provide the contractor with a reasonable flow of minority and women referrals within the time limit set forth in the collective bargaining agreement, the contractor will, through independent recruitment efforts, fill the employment vacancies without regard to race, color, religion, sex, national origin, age or disability; making full efforts to obtain qualified and/or qualifiable minority group persons and women. (The DOL has held that it shall be no excuse that the union with which the contractor has a collective bargaining agreement providing for exclusive referral failed to refer minority employees.) In the event the union referral practice prevents the contractor from meeting the obligations pursuant to Executive Order 11246, as amended, and these special provisions, such contractor shall immediately notify the SHA.
- 8. Selection of Subcontractors, Procurement of Materials and Leasing of Equipment: The contractor shall not discriminate on the grounds of race, color, religion, sex, national origin, age or disability in the selection and retention of subcontractors, including procurement of materials and leases of equipment.
  - a. The contractor shall notify all potential subcontractors and suppliers of his/her EEO obligations under this contract.
  - b. Disadvantaged business enterprises (DBE), as defined in 49 CFR 23, shall have equal opportunity to compete for and perform subcontracts which the contractor enters into pursuant to this contract. The contractor will use his best efforts to solicit bids from and to utilize DBE subcontractors or subcontractors with meaningful minority group and female representation among their employees. Contractors shall obtain lists of DBE construction firms from SHA personnel.
  - c. The contractor will use his best efforts to ensure subcontractor compliance with their EEO obligations.
- 9. Records and Reports: The contractor shall keep such records as necessary to document compliance with the EEO requirements. Such records shall be retained for a period of three years following completion of the contract work and shall be available at reasonable times and places for inspection by authorized representatives of the SHA and the FHWA.
  - a. The records kept by the contractor shall document the following:
  - (1) The number of minority and non-minority group members and women employed in each work classification on the project:
  - (2) The progress and efforts being made in cooperation with unions, when applicable, to increase employment opportunities for minorities and women;
  - (3) The progress and efforts being made in locating, hiring, training, qualifying, and upgrading minority and female employees; and
  - (4) The progress and efforts being made in securing the services of DBE subcontractors or subcontractors with meaningful minority and female representation among their employees.

b. The contractors will submit an annual report to the SHA each July for the duration of the project, indicating the number of minority, women, and non-minority group employees currently engaged in each work classification required by the contract work. This information is to be reported on Form FHWA-1391. If on-the-job training is being required by special provision, the contractor will be required to collect and report training data.

#### **III. NONSEGREGATED FACILITIES**

(Applicable to all Federal-aid construction contracts and to all related subcontracts of \$10,000 or more.)

- a. By submission of this bid, the execution of this contract or subcontract, or the consummation of this material supply agreement or purchase order, as appropriate, the bidder, Federal-aid construction contractor, subcontractor, material supplier, or vendor, as appropriate, certifies that the firm does not maintain or provide for its employees any segregated facilities at any of its establishments, and that the firm does not permit its employees to perform their services at any location, under its control, where segregated facilities are maintained. The firm agrees that a breach of this certification is a violation of the EEO provisions of this contract. The firm further certifies that no employee will be denied access to adequate facilities on the basis of sex or disability.
- b. As used in this certification, the term "segregated facilities" means any waiting rooms, work areas, restrooms and washrooms, restaurants and other eating areas, timeclocks, locker rooms, and other storage or dressing areas, parking lots, drinking fountains, recreation or entertainment areas, transportation, and housing facilities provided for employees which are segregated by explicit directive, or are, in fact, segregated on the basis of race, color, religion, national origin, age or disability, because of habit, local custom, or otherwise. The only exception will be for the disabled when the demands for accessibility override (e.g. disabled parking).
- c. The contractor agrees that it has obtained or will obtain identical certification from proposed subcontractors or material suppliers prior to award of subcontracts or consummation of material supply agreements of \$10,000 or more and that it will retain such certifications in its files.

#### IV. PAYMENT OF PREDETERMINED MINIMUM WAGE

(Applicable to all Federal-aid construction contracts exceeding \$2,000 and to all related subcontracts, except for projects located on roadways classified as local roads or rural minor collectors, which are exempt.)

#### 1. General:

a. All mechanics and laborers employed or working upon the site of the work will be paid unconditionally and not less often than once a week and without subsequent deduction or rebate on any account [except such payroll deductions as are permitted by regulations (29 CFR 3) issued by the Secretary of Labor under the Copeland Act (40 U.S.C. 276c)] the full amounts of wages and bona fide fringe benefits (or cash equivalents thereof) due at time of payment. The payment shall be computed at wage rates not less than those contained in the wage determination of the Secretary of Labor (hereinafter "the wage determination") which is attached hereto and made a part hereof, regardless of any contractual relationship which may be alleged to exist between the

contractor or its subcontractors and such laborers and mechanics. The wage determination (including any additional classifications and wage rates conformed under paragraph 2 of this Section IV and the DOL poster (WH-1321) or Form FHWA-1495) shall be posted at all times by the contractor and its subcontractors at the site of the work in a prominent and accessible place where it can be easily seen by the workers. For the purpose of this Section, contributions made or costs reasonably anticipated for bona fide fringe benefits under Section 1(b)(2) of the Davis-Bacon Act (40 U.S.C. 276a) on behalf of laborers or mechanics are considered wages paid to such laborers or mechanics, subject to the provisions of Section IV, paragraph 3b, hereof. Also, for the purpose of this Section, regular contributions made or costs incurred for more than a weekly period (but not less often than quarterly) under plans, funds, or programs, which cover the particular weekly period, are deemed to be constructively made or incurred during such weekly period. Such laborers and mechanics shall be paid the appropriate wage rate and fringe benefits on the wage determination for the classification of work actually performed, without regard to skill, except as provided in paragraphs 4 and 5 of this Section IV.

- b. Laborers or mechanics performing work in more than one classification may be compensated at the rate specified for each classification for the time actually worked therein, provided, that the employer's payroll records accurately set forth the time spent in each classification in which work is performed.
- c. All rulings and interpretations of the Davis-Bacon Act and related acts contained in 29 CFR 1, 3, and 5 are herein incorporated by reference in this contract.

#### 2. Classification:

- a. The SHA contracting officer shall require that any class of laborers or mechanics employed under the contract, which is not listed in the wage determination, shall be classified in conformance with the wage determination.
- b. The contracting officer shall approve an additional classification, wage rate and fringe benefits only when the following criteria have been met:
- (1) the work to be performed by the additional classification requested is not performed by a classification in the wage determination;
- (2) the additional classification is utilized in the area by the construction industry:
- (3) the proposed wage rate, including any bona fide fringe benefits, bears a reasonable relationship to the wage rates contained in the wage determination; and
- (4) with respect to helpers, when such a classification prevails in the area in which the work is performed.
- c. If the contractor or subcontractors, as appropriate, the laborers and mechanics (if known) to be employed in the additional classification or their representatives, and the contracting officer agree on the classification and wage rate (including the amount designated for fringe benefits where appropriate), a report of the action taken shall be sent by the contracting officer to the DOL, Administrator of the Wage and Hour Division, Employment Standards Administration, Washington, D.C. 20210. The Wage and Hour Administrator, or an authorized representative, will approve, modify, or

disapprove every additional classification action within 30 days of receipt and so advise the contracting officer or will notify the contracting officer within the 30-day period that additional time is necessary.

- d. In the event the contractor or subcontractors, as appropriate, the laborers or mechanics to be employed in the additional classification or their representatives, and the contracting officer do not agree on the proposed classification and wage rate (including the amount designated for fringe benefits, where appropriate), the contracting officer shall refer the question, including the views of all interested parties and the recommendation of the contracting officer, to the Wage and Hour Administrator for determination. Said Administrator, or an authorized representative, will issue a determination within 30 days of receipt and so advised the contracting officer or will notify the contracting officer within the 30-day period that additional time is necessary.
- e. The wage rate (including fringe benefits where appropriate) determined pursuant to paragraph 2c or 2d of this Section IV shall be paid to all workers performing work in the additional classification from the first day on which work is performed in the classification.

#### 3. Payment of Fringe Benefits:

- a. Whenever the minimum wage rate prescribed in the contract for a class of laborers or mechanics includes a fringe benefit which is not expressed as an hourly rate, the contractor or subcontractors, as appropriate, shall either pay the benefit as stated in the wage determination or shall pay another bona fide fringe benefit or an hourly case equivalent thereof.
- b. If the contractor or subcontractor, as appropriate, does not make payments to a trustee or other third person, he/she may consider as a part of the wages of any laborer or mechanic the amount of any cost reasonably anticipated in providing bona fide fringe benefits under a plan or program, provided that the Secretary of Labor has found, upon the written request of the contractor, that the applicable standards of the Davis-Bacon Act have been met. The Secretary of Labor may require the contractor to set aside in a separate account assets for the meeting of obligations under the plan or program.
- 4. Apprentices and Trainees (Programs of the U.S. DOL) and Helpers:

#### a. Apprentices:

- (1) Apprentices will be permitted to work at less than the predetermined rate for the work they performed when they are employed pursuant to and individually registered in a bona fide apprenticeship program registered with the DOL, Employment and Training Administration, Bureau of Apprenticeship and Training, or with a State apprenticeship agency recognized by the Bureau, or if a person is employed in his/her first 90 days of probationary employment as an apprentice in such an apprenticeship program, who is not individually registered in the program, but who has been certified by the Bureau of Apprenticeship and Training or a State apprenticeship agency (where appropriate) to be eligible for probationary employment as an apprentice.
- (2) The allowable ratio of apprentices to journeyman-level employees on the job site in any craft classification shall not

be greater than the ratio permitted to the contractor as to the entire work force under the registered program. Any employee listed on a payroll at an apprentice wage rate, who is not registered or otherwise employed as stated above, shall be paid not less than the applicable wage rate listed in the wage determination for the classification of work actually performed. In addition, any apprentice performing work on the job site in excess of the ratio permitted under the registered program shall be paid not less than the applicable  $\,$ wage rate on the wage determination for the work actually performed. Where a contractor or subcontractor is performing construction on a project in a locality other than that in which its program is registered, the ratios and wage rates (expressed in percentages of the journeyman-level hourly rate) specified in the contractor's or subcontractor's registered program shall be observed.

- (3) Every apprentice must be paid at not less than the rate specified in the registered program for the apprentice's level of progress, expressed as a percentage of the journeyman-level hourly rate specified in the applicable wage determination. Apprentices shall be paid fringe benefits in accordance with the provisions of the apprenticeship program. If the apprenticeship program does not specify fringe benefits, apprentices must be paid the full amount of fringe benefits listed on the wage determination for the applicable classification. If the Administrator for the Wage and Hour Division determines that a different practice prevails for the applicable apprentice classification, fringes shall be paid in accordance with that determination.
- (4) In the event the Bureau of Apprenticeship and Training, or a State apprenticeship agency recognized by the Bureau, withdraws approval of an apprenticeship program, the contractor or subcontractor will no longer be permitted to utilize apprentices at less than the applicable predetermined rate for the comparable work performed by regular employees until an acceptable program is approved.

#### b. Trainees:

- (1) Except as provided in 29 CFR 5.16, trainees will not be permitted to work at less than the predetermined rate for the work performed unless they are employed pursuant to and individually registered in a program which has received prior approval, evidenced by formal certification by the DOL, Employment and Training Administration.
- (2) The ratio of trainees to journeyman-level employees on the job site shall not be greater than permitted under the plan approved by the Employment and Training Administration. Any employee listed on the payroll at a trainee rate who is not registered and participating in a training plan approved by the Employment and Training Administration shall be paid not less than the applicable wage rate on the wage determination for the classification of work actually performed. In addition, any trainee performing work on the job site in excess of the ratio permitted under the registered program shall be paid not less than the applicable wage rate on the wage determination for the work actually performed.
- (3) Every trainee must be paid at not less than the rate specified in the approved program for his/her level of progress, expressed as a percentage of the journeyman-level hourly rate specified in the applicable wage determination. Trainees shall be paid fringe benefits in accordance with the provisions of the trainee program. If the trainee program does not mention fringe benefits, trainees shall be paid the full amount of fringe benefits

Wage and Hour Division determines that there is an apprenticeship program associated with the corresponding journeyman-level wage rate on the wage determination which provides for less than full fringe benefits for apprentices, in which cases such trainees shall receive the same fringe benefits as apprentices.

(4) In the event the Employment and Training Administration withdraws approval of a training program, the contractor or subcontractor will no longer be permitted to utilize trainees at less than the applicable predetermined rate for the work performed until an acceptable program is approved.

#### c. Helpers:

Helpers will be permitted to work on a project if the helper classification is specified and defined on the applicable wage determination or is approved pursuant to the conformance procedure set forth in Section IV. 2. Any worker listed on a payroll at a helper wage rate, who is not a helper under a approved definition, shall be paid not less than the applicable wage rate on the wage determination for the classification of work actually performed.

#### 5. Apprentices and Trainees (Programs of the U.S. DOT):

Apprentices and trainees working under apprenticeship and skill training programs which have been certified by the Secretary of Transportation as promoting EEO in connection with Federal-aid highway construction programs are not subject to the requirements of paragraph 4 of this Section IV. The straight time hourly wage rates for apprentices and trainees under such programs will be established by the particular programs. The ratio of apprentices and trainees to journeymen shall not be greater than permitted by the terms of the particular program.

#### 6. Withholding:

The SHA shall upon its own action or upon written request of an authorized representative of the DOL withhold, or cause to be withheld, from the contractor or subcontractor under this contract or any other Federal contract with the same prime contractor or any other Federallyassisted contract subject to Davis-Bacon prevailing wage requirements which is held by the same prime contractor, as much of the accrued payments or advances as may be considered necessary to pay laborers and mechanics, including apprentices, trainee's and helpers, employed by the contractor or any subcontractor the full amount of wages required by the contract. In the event of failure to pay any laborer or mechanic, including any apprentice, trainee, or helper, employed or working on the site of the work, all or part of the wages required by the contract, the SHA contracting officer may, after written notice to the contractor, take such action as may be necessary to cause the suspension of any further payment, advance, or guarantee of funds until such violations have ceased.

#### 7. Overtime Requirements:

No contractor or subcontractor contracting for any part of the contract work which may require or involve the employment of laborers, mechanics, watchmen, or guards (including apprentices, trainees, and helpers described in paragraphs 4 and 5 above) shall require or permit any laborer, mechanic, watchman, or guard in any workweek in which he/she is employed on such work, to work in excess of 40 hours in such workweek unless such laborer, mechanic, watchman, or guard receives compensation at a rate not less than one-and-one-half times his/her basic rate of pay for all hours worked in excess of 40 hours in such workweek.

#### 8. Violation:

Liability for Unpaid Wages; Liquidated Damages: In the event of any violation of the clause set forth in paragraph 7 above, the contractor and any subcontractor responsible thereof shall be liable to the affected employee for his/her unpaid wages. In addition, such contractor and subcontractor shall be liable to the United States (in the case of work done under contract for the District of Columbia or a territory, to such District or to such territory) for liquidated damages. Such liquidated damages shall be computed with respect to each individual laborer, mechanic, watchman, or guard employed in violation of the clause set forth in paragraph 7, in the sum of \$10 for each calendar day on which such employee was required or permitted to work in excess of the standard work week of 40 hours without payment of the overtime wages required by the clause set forth in paragraph 7.

9. Withholding for Unpaid Wages and Liquidated Damages:

The SHA shall; upon its own action or upon written request of any authorized representative of the DOL withhold, or cause to be withheld, from any monies payable on account of work performed by the contractor or subcontractor under any such contract or any other Federal contract with the same prime contractor, or any other Federally-assisted contract subject to the Contract Work Hours and Safety Standards Act, which is held by the same prime contractor, such sums as may be determined to be necessary to satisfy any liabilities of such contractor or subcontractor for unpaid wages and liquidated damages as provided in the clause set forth in paragraph 8 above.

#### V. STATEMENTS AND PAYROLLS

(Applicable to all Federal-aid construction contracts exceeding \$2,000 and to all related subcontracts, except for projects located on roadways classified as local roads or rural collectors, which are exempt.)

1. Compliance with Copeland Regulations (29 CFR 3):

The contractor shall comply with the Copeland Regulations of the Secretary of Labor which are herein incorporated by reference.

- 2. Payrolls and Payroll Records:
  - a. Payrolls and basic records relating thereto shall be maintained by the contractor and each subcontractor during the course of the work and preserved for a period of 3 years from the date of completion of the contract for all laborers, mechanics, apprentices, trainees, watchmen, helpers, and guards working at the site of the work.
  - b. The payroll records shall contain the name, social security number, and address of each such employee; his or her correct classification; hourly rates of wages paid (including rates of contributions or costs anticipated for bona fide fringe benefits or cash equivalent thereof the types described in Section 1(b)(2)(B) of the Davis Bacon Act); daily and weekly number of hours worked; deductions made; and actual wages paid. In addition, for Appalachian contracts, the payroll records shall contain a notation indicating whether the employee does, or does not, normally reside in the labor area as defined in Attachment A, paragraph 1. Whenever the Secretary of Labor, pursuant to Section IV, paragraph 3b, has found that the wages of any laborer or mechanic include the amount of any costs reasonably anticipated in providing benefits under a plan

or program described in Section 1(b)(2)(B) of the Davis Bacon Act, the contractor and each subcontractor shall maintain records which show that the commitment to provide such benefits is enforceable, that the plan or program is financially responsible, that the plan or program has been communicated in writing to the laborers or mechanics affected, and show the cost anticipated or the actual cost incurred in providing benefits. Contractors or subcontractors employing apprentices or trainees under approved programs shall maintain written evidence of the registration of apprentices and trainees, and ratios and wage rates prescribed in the applicable programs.

c. Each contractor and subcontractor shall furnish, each week in which any contract work is performed, to the SHA resident engineer a payroll of wages paid each of its employees (including apprentices trainees, and helpers, described in Section IV, paragraphs 4 and 5, and watchmen and guards engaged on work during the preceding weekly payroll period).

The payroll submitted shall set out accurately and completely all of the information required to be maintained under paragraph 2b of this Section V.

This information may be submitted in any form desired. Optional Form WH-347 is available for this purpose and may be purchased from the Superintendent of Documents (Federal stock number 029-005-0014-1), U.S. Government Printing Office, Washington, D.C. 20402. The prime contractor is responsible for the submission of copies of payrolls by all suncontractors.

- d. Each payroll submitted shall be accompanied by a "Statement of Compliance," signed by the Contractor or subcontractor or his/her agent who pays or supervises the payment of the persons employed under the contract and shall certify the following:
- (1) that the payroll for the payroll period contains the information required to be maintained under paragraph 2b of this Section V and that such information is correct and complete;
- (2) that such laborer or mechanic (including each helper, apprentice, and trainee) employed on the contract during the payroll period has been paid the full weekly wages earned, without rebate, either directly or indirectly, and that no deductions have been made either directly or indirectly from the full wages earned, other than permissible deductions as set forth in the Regulations, 29 CFR 3;
- (3) that each laborer or mechanic has been paid not less that the applicable wage rate and fringe benefits or cash equivalent for the classification of worked performed, as specified in the applicable wage determination incorporated into the contract.
- e. The weekly submission of a properly executed certification set forth on the reverse side of Optional Form WH-347 shall satisfy the requirement for submission of the "Statement of Compliance" required by paragraph 2d of this Section V.
- f. The falsification of any of the above certifications may subject the contractor to civil or criminal prosecution under 18 U/S. C. 1001 and 31 U.S.C. 231.
- g. The contractor or subcontractor shall make the records required under paragraph 2b of this Section V available for

inspection, copying, or transcription by authorized representatives of the SHA, the FHWA, or the DOL, and shall permit such representatives to interview employees during working hours on the job. If the contractor or subcontractor fails to submit the required records or to make them available, the SHA, the FHWA, the DOL, or all may, after written notice to the contractor, sponsor, applicant, or owner, take such actions as may be necessary to cause the suspension of any further payment, advance, or guarantee of funds. Furthermore, failure to submit the required records upon request or to make such records available may be grounds for debarment action pursuant to 29 CFR 5.12.

#### VI. RECORD OF MATERIALS, SUPPLIES, AND LABOR

- 1. On all federal-aid contracts on the national highway system, except those which provide solely for the installation of protective devices at railroad grade crossings, those which are constructed on a force account or direct labor basis, highway beautification contracts, and contracts for which the total final construction cost for roadway and bridge is less than \$1,000,000 (23 CFR 635) the contractor shall:
  - a. Become familiar with the list of specific materials and supplies contained in Form FHWA-47, "Statement of Materials and Labor Used by Contractor of Highway Construction Involving Federal Funds," prior to the commencement of work under this contract.
  - b. Maintain a record of the total cost of all materials and supplies purchased for and incorporated in the work, and also of the quantities of those specific materials and supplies listed on Form FHWA-47, and in the units shown on Form FHWA-47.
  - c. Furnish, upon the completion of the contract, to the SHA resident engineer on /Form FHWA-47 together with the data required in paragraph 1b relative to materials and supplies, a final labor summary of all contract work indicating the total hours worked and the total amount earned.
- 2. At the prime contractor's option, either a single report covering all contract work or separate reports for the contractor and for each subcontract shall be submitted.

#### VII. SUBLETTING OR ASSIGNING THE CONTRACT

- 1. The contractor shall perform with its own organization contract work amounting to not less than 30 percent (or a greater percentage if specified elsewhere in the contract) of the total original contract price, excluding any specialty items designated by the State. Specialty items may be performed by subcontract and the amount of any such specialty items performed may be deducted from the total original contract price before computing the amount of work required to be performed by the contractors' own organization (23 CFR 635).
  - a. "Its own organization" shall be construed to include only workers employed and paid directly by the prime contractor and equipment owned or rented by the prime contractor, with or without operators. Such term does not include employees or equipment of a subcontractor, assignee, or agent of the prime contractor.
  - b. "Specialty Items" shall be construed to be limited to work that requires highly specialized knowledge, abilities, or equipment not ordinarily available in the type of contracting organizations qualified and expected to bid on the contract as a

whole and in general are to be limited to minor components of the overall contract.

- 2. The contract amount upon which the requirements set forth in paragraph 1 of Section VII is computed includes the cost of material and manufactured products which are to be purchased or produced by the contractor under the contract provisions.
- 3. The contractor shall furnish (a) a competent superintendent or supervisor who is employed by the firm, has full authority to direct performance of the work in accordance with the contract requirements, and is in charge of all construction operations (regardless of who performs the work) and (b) such other of its own organizational resources (supervision, management, and engineering services) as the SHA contracting officer determines is necessary to assure the performance of the contract.
- 4. No portion of the contract shall be sublet, assigned or otherwise disposed of except with the written consent of the SHA contracting officer, or authorized representative, and such consent when given shall not be construed to relieve the contractor of any responsibility for the fulfillment of the contract.

Written consent will be given only after the SHA has assured that each subcontract is evidenced in writing and that it contains all pertinent provisions and requirements of the prime contract.

#### VIII. SAFETY: ACCIDENT PREVENTION

- 1. In the performance of this contract the contractor shall comply with all applicable Federal, State, and local laws governing safety, health, and sanitation (23 CFR 635). The contractor shall provide all safeguards, safety devices and protective equipment and take any other needed actions as it determines, or as the SHA contracting officer may determine, to be reasonably necessary to protect the life and health of employees on the job and the safety of the public and to protect property in connection with the performance of the work covered by the contract.
- 2. It is a condition of this contract, and shall be made a condition of each subcontract, which the contractor enters into pursuant to this contract, that the contractor and any subcontractor shall not permit any employee, in performance of the contract, to work in surroundings or under conditions which are unsanitary, hazardous or dangerous to his/her health or safety, as determined under construction safety and health standards (29 CFR 1926) promulgated by the Secretary of Labor, in accordance with Section 107 of the Contract Work Hours and Safety Standards Act (40 U.S. C. 333).
- 3. Pursuant to 29 CFR 1926.3, it is a condition of this contract that the Secretary of Labor or authorized representative thereof, shall have right of entry to any site of contract performance to inspect or investigate the matter of compliance with the construction safety and health standards and to carry out the duties of the Secretary under Section 107 of the Contract Work Hours and Safety Standards Act (40 U.S.C. 333).

#### IX. FALSE STATEMENTS CONCERNING HIGHWAY PROJECTS

In order to assure high quality and durable construction in conformity with approved plans and specifications and a high degree of reliability on statements and representations made by engineers, contractors, suppliers, and workers on Federal-aid highway projects, it is essential that all persons concerned with the project perform their functions as carefully, thoroughly, and honestly as possible. Willful falsification,

distortion, or misrepresentation with respect to any facts related to the project is a violation of Federal law. To prevent any misunderstanding regarding the seriousness of these and similar acts, the following notice shall be posted on each Federal-aid highway project (23 CFR 635) in one or more places where it is readily available to all persons concerned with the project:

## NOTICE TO ALL PERSONNEL ENGAGED ON FEDERAL-AID HIGHWAY PROJECTS

18 U.S.C. 1020 reads as follows:

"Whoever, being an officer, agent or employee of the United States, or of any State or Territory, or whoever, whether a person, association, firm, or corporation, knowingly makes any false statement, false representation, or false report as to the character, quality, quantity, or cost of the material used or to be used, or the quantity or quality of the work performed or to be performed, or the cost thereof in connection with the submission of plans, maps, specifications, contracts, or costs of construction on any highway or related project submitted for approval to the Secretary of Transportation; or

Whoever knowingly makes any false statement, false representation, false report or false claim with respect to the character, quality, quantity, or cost of any work performed or to be performed, or materials furnished or to be furnished, in connection with the construction of any highway or related project approved by the Secretary of Transportation; or

Whoever knowingly makes any false statement or false representation as to material fact in any statement, certificate, or report submitted pursuant to provisions of the Federal-aid Roads Act approved July 1, 1916, (39 Stat. 355), as amended and supplemented;

Shall be fined not more than \$10,000 or imprisoned not more than 5 years or both."

## X. IMPLEMENTATION OF CLEAN AIR ACT AND FEDERAL WATER POLLUTION CONTROL ACT

(Applicable to all Federal-aid construction contracts and to all related subcontracts of \$100,000 or more).

By submission of this bid or the execution of this contract, or subcontract, as appropriate, the bidder, Federal-aid construction contractor, or subcontractor, as appropriate, will be deemed to have stipulated as follows:

- 1. That any facility that is or will be utilized in the performance of this contract, unless such contract is exempt under the Clean Air Act, as amended (42 U.S.C. 1857 et seq., as amended by Pub.L. 91-604), and under the Federal Water Pollution Control Act, as amended (33 U.S.C. 1251 et seq., as amended by Pub.L. 92-500), Executive Order 11738, and regulations in implementation thereof (40 CFR 15) is not listed, on the date of contract award, on the U.S. Environmental Protection Agency (EPA) List of Violating Facilities pursuant to 40 CFR 15.20.
- 2. That the firm agrees to comply and remain in compliance with all the requirements of Section 114 of the Clean Air Act and Section 308 of the Federal Water Pollution Control Act and all regulations and guidelines listed thereunder.
- 3. That the firm shall promptly notify the SHA of the receipt of

any communication from the Director, Office of Federal Activities, EPA indicating that a facility that is or will be utilized for the contract is under consideration to be listed on the EPA List of Violating Facilities.

4. That the firm agrees to include or cause to be included the requirements of paragraph 1 through 4 of this Section X in every nonexempt subcontract, and further agrees to take such action as the government may direct as a means of enforcing such requirements.

# XI. CERTIFICATION REGARDING DEBARMENT, SUSPENSION, INELIGIBILITY AND VOLUNTARY EXCLUSION

1. Instructions for Certification - Primary Covered Transactions:

(Applicable to all Federal-aid contracts - 49 CFR 29)

- a. By signing and submitting this proposal, the prospective primary participant is providing the certification set out below.
- b. The inability of a person to provide the certification set out below will not necessarily result in denial of participation in this covered transaction. The prospective participant shall submit an an explanation of why it cannot provide the certification set out below. The certification or explanation will be considered in connection with the department or agency's determination whether to enter into this transaction. However, failure of the prospective primary participant to furnish a certification or an explanation shall disqualify such a person from participation in this transaction.
- c. The certification in this clause is a material representation of fact upon which reliance was placed when the department or agency determined to enter into this transaction. If it is later determined that the prospective primary participant knowingly rendered an erroneous certification, in addition to other remedies available to the Federal Government, the department or agency may terminate this transaction for cause of default.
- d. The prospective primary participant shall provide immediate written notice to the department or agency to whom this proposal is submitted if any time the prospective primary participant learns that its certification was erroneous when submitted or has become erroneous by reason of changed circumstances.
- e. The terms "covered transaction," "debarred," "suspended," "ineligible,""lower tier covered transaction," "participant," "person," "primary covered transaction," "principal," "proposal," and "voluntarily excluded," as used in this clause, have the meanings set out in the Definitions and Coverage sections of rules implementing Executive Order 12549. You may contact the department or agency to which this proposal is submitted for assistance in obtaining a copy of those regulations.
- f. The prospective primary participant agrees by submitting this proposal that, should the proposed covered transaction be entered into, it shall not knowingly enter into any lower tier covered transaction with a person who is debarred, suspended, declared ineligible, or voluntarily excluded from participation in this covered transaction, unless authorized by the department or agency entering into this transaction.
- g. The prospective primary participant further agrees by submitting this proposal that it will include the clause titled

\*\*\*\*

"Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion-Lower Tier Covered Transaction," provided by the department or agency entering into this covered transaction, without modification in all lower tier covered transactions and in all solicitations for lower tier covered transactions.

- h. A participant in a covered transaction may rely upon a certification of a prospective participant in a lower tier covered transaction that is not debarred, suspended, ineligible, or voluntarily excluded from the covered transaction, unless it knows that the certification is erroneous. A participant may decide the method and frequency by which it determines the eligibility of its principals. Each participant may, but is not required to, check the nonprocurement portion of the "Lists of Parties Excluded from Federal Procurement or Nonprocurement Programs" (Nonprocurement List) which is compiled by the General Services Administration.
- i. Nothing contained in the foregoing shall be construed to require establishment of a system of records in order to render in good faith the certification required by this clause. The knowledge and information of participant is not required to exceed that which is normally possessed by a prudent person in the ordinary course of business dealings.
- j. Except for transactions authorized under paragraph f of these instructions, if a participant in a covered transaction knowingly enters into a lower tier covered transaction with a person who is suspended, debarred, ineligible, or voluntarily excluded from participation in this transaction, in addition to other remedies available to the Federal Government, the department or agency may terminate this transaction for cause or default.

\*\*\*\*\*

# Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion-Primary Covered Transactions

- 1. The prospective primary participant certifies to the best of its knowledge and belief, that it and its principals:
  - a. Are not presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from covered transactions by any Federal department or agency;
  - b. Have not within a 3-year period preceding this proposal been convicted of or had a civil judgment rendered against them for commission of fraud or a criminal offense in connection with obtaining, attempting to obtain, or performing a public (Federal, State or local) transaction or contract under a public transaction; violation of Federal or State antitrust statutes or commission of embezzlement, theft, forgery, bribery, falsification or destruction of records, making false statements, or receiving stolen property;
  - c. Are not presently indicted for or otherwise criminally or civilly charged by a governmental entity (Federal, State or local) with commission of any of the offenses enumerated in paragraph 1b of this certification; and
  - d. Have not within a 3-year period preceding this application/proposal had one or more public transactions (Federal, State or local) terminated for cause or default.
- 2. Where the prospective primary participant is unable to certify to any of the statements in this certification, such prospective participant shall attach an explanation to this proposal.

## 2. Instructions for Certification - Lower Tier Covered Transactions:

(Applicable to all subcontracts, purchase orders and other lower tier transactions of \$25,000 or more - 49 CFR 29)

- a. By signing and submitting this proposal, the prospective lower tier is providing the certification set out below.
- b. The certification in this clause is a material representation of fact upon which reliance was placed when this transaction was entered into. If it is later determined that the prospective lower tier participant knowingly rendered an erroneous certification, in addition to other remedies available to the Federal Government, the department, or agency with which this transaction originated may pursue available remedies, including suspension and/or debarment.
- c. The prospective lower tier participant shall provide immediate written notice to the person to which this proposal is submitted if at any time the prospective lower tier participant learns that its certification was erroneous by reason of changed circumstances.
- d. The terms "covered transaction," "debarred," "suspended," "ineligible," "primary covered transaction," "participant," "person," "principal," "proposal," and "voluntarily excluded," as used in this clause, have the meanings set out in the Definitions and Coverage sections of rules implementing Executive Order 12549. You may contact the person to which this proposal is submitted for assistance in obtaining a copy of those regulations.
- e. The prospective lower tie participant agrees by submitting this proposal that, should the proposed covered transaction be entered into, it shall not knowingly enter into any lower tier covered transaction with a person who is debarred, suspended, declared ineligible, or voluntarily excluded from participation in this covered transaction, unless authorized by the department or agency with which this transaction originated.
- f. The prospective lower tier participant further agrees by submitting this proposal that it will include this clause titled "Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion-Lower Tier Covered Transaction," without modification, in all lower tier covered transactions and in all solicitations for lower tier covered transactions.
- g. A participant in a covered transaction may rely upon a certification of a prospective participant in a lower tier covered transaction that is not debarred, suspended, ineligible, or voluntarily excluded from the covered transaction, unless it knows that the certification is erroneous. A participant may decide the method and frequency by which it determines the eligibility of its principals. Each participant may, but is not required to, check the Nonprocurement List.
- h. Nothing contained in the foregoing shall be construed to require establishment of a system of records in order to render in good faith the certification required by this clause. The knowledge and information of participant is not required to exceed that which is normally possessed by a prudent person in the ordinary course of business dealing.
- Except for transactions authorized under paragraph e of these instructions, if a participant in a covered transaction knowingly enters into a lower tier covered transaction with a person who is suspended, debarred, ineligible, or voluntarily

excluded from participation in this transaction, in addition to other remedies available to the Federal Government, the department or agency with which this transaction originated may pursue available remedies, including suspension and/or debarment.

\*\*\*\*

# Certification Regarding Debarment, Suspension, Ineligibility And Voluntary Exclusion-Lower Tier Covered Transactions:

- 1. The prospective lower tier participant certifies, by submission of this proposal, that neither it nor its principals is presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from participation in this transaction by any Federal department or agency.
- 2. Where the prospective lower tier participant is unable to certify to any of the statements in this certification, such prospective participant shall attach an explanation to this proposal.

\*\*\*\*

## XII. CERTIFICATION REGARDING USE OF CONTRACT FUNDS FOR LOBBYING

(Applicable to all Federal-aid construction contracts and to all related subcontracts which exceed \$100,000 - 49 CFR 20)

- 1. The prospective participant certifies, by signing and submitting this bid or proposal, to the best of his or her knowledge and belief. that:
  - a. No Federal appropriated funds have been paid or will be paid, by or on behalf of the undersigned, to any person for influencing or attempting to influence an officer or employee of any Federal agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress in connection with the awarding of any Federal contract, the making of any Federal grant, the making of any Federal loan, the entering into of any cooperative agreement, and the extension, continuation, renewal, amendment, or modification of any Federal contract, grant, loan, or cooperative agreement.
  - b. If any funds other than Federal appropriated funds have been paid or will be paid to any person for influencing or attempting to influence an officer or employee of any Federal agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress in connection with this Federal contract, grant, loan, or cooperative agreement, the undersigned shall complete and submit Standard Form-LLL, "Disclosure Form to Report Lobbying," in accordance with its instructions.
- 2. This certification is a material representation of fact upon which reliance was placed when this transaction was made or entered into. Submission of this certification is a prerequisite for making or entering into this transaction imposed by 31 U.S.C. 1352. Any person who fails to file the required certification shall be subject to a civil penalty of not less than \$10,000 and not more than \$100,000 for each such failure.
- 3. The prospective participant also agrees by submitting his or her bid or proposal that he or she shall require that the language of this certification be included in all lower tier subcontracts, which exceed \$100,000 and that all such recipients shall certify and disclose accordingly.

## MINIMUM WAGES FOR FEDERAL AND FEDERALLY ASSISTED CONSTRUCTION CONTRACTS

This project is funded, in part, with Federal-aid funds and, as such, is subject to the provisions of the Davis-Bacon Act of March 3, 1931, as amended (46 Sta. 1494, as amended, 40 U.S.C. 276a) and of other Federal statutes referred to in a 29 CFR Part 1, Appendix A, as well as such additional statutes as may from time to time be enacted containing provisions for the payment of wages determined to be prevailing by the Secretary of Labor in accordance with the Davis-Bacon Act and pursuant to the provisions of 29 CFR Part 1. The prevailing rates and fringe benefits shown in the General Wage Determination Decisions issued by the U.S. Department of Labor shall, in accordance with the provisions of the foregoing statutes, constitute the minimum wages payable on Federal and federally assisted construction projects to laborers and mechanics of the specified classes engaged on contract work of the character and in the localities described therein.

General Wage Determination Decisions, modifications and supersedes decisions thereto are to be used in accordance with the provisions of 29 CFR Parts 1 and 5. Accordingly, the applicable decision, together with any modifications issued, must be made a part of every contract for performance of the described work within the geographic area indicated as required by an applicable DBRA Federal prevailing wage law and 29 CFR Part 5. The wage rates and fringe benefits contained in the General Wage Determination Decision shall be the minimum paid by contractors and subcontractors to laborers and mechanics.

#### **NOTICE**

The most current **General Wage Determination Decisions** (wage rates) are available on the IDOT web site. They are located on the Letting and Bidding page at <a href="http://www.dot.state.il.us/desenv/delett.html">http://www.dot.state.il.us/desenv/delett.html</a>.

In addition, ten (10) days prior to the letting, the applicable Federal wage rates will be e-mailed to subscribers. It is recommended that all contractors subscribe to the Federal Wage Rates List or the Contractor's Packet through IDOT's subscription service.

PLEASE NOTE: if you have already subscribed to the Contractor's Packet you will automatically receive the Federal Wage Rates.

The instructions for subscribing are at <a href="http://www.dot.state.il.us/desenv/subsc.html">http://www.dot.state.il.us/desenv/subsc.html</a>.

If you have any questions concerning the wage rates, please contact IDOT's Chief Contract Official at 217-782-7806.