

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODES		
				L 160 / POPLAR		POPLAR
				STATE	CMAQ	STU
60261540	INLETS TO BE ADJUSTED WITH NEW TYPE 24 FRAME AND GRATE	EACH	1			1
60266600	VALVE BOXES TO BE ADJUSTED	EACH	14	3	2	9
60500040	REMOVING MANHOLES	EACH	3		3	
60500060	REMOVING INLETS	EACH	11	4	4	3
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	2		2	
60600605	CONCRETE CURB, TYPE B	FOOT	189		107	82
60602400	CONCRETE GUTTER (SPECIAL)	FOOT	45	15		30
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	5,197	1923	1643	1631
60605900	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-9.12	FOOT	276	149	127	
60606300	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-2.12	FOOT	383	207	176	
60606521	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-2.24	FOOT	118		118	
60611600	COMBINATION CONCRETE CURB AND GUTTER, (SPECIAL)	FOOT	715	488	227	
67100100	MOBILIZATION	L SUM	1	0.40	0.40	0.20
70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1	0.25	0.25	0.50
70101900	TRAFFIC CONTROL AND PROTECTION (DETOUR 1)	L SUM	1	0.50	0.50	
70102000	TRAFFIC CONTROL AND PROTECTION (DETOUR 2)	L SUM	1	0.50	0.50	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	2,088	910	806	372
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	81	51	30	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	570		570	
70300250	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1,672	898	774	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	689	300	266	123
72000100	SIGN PANEL - TYPE 1	SQ FT	401	254	96	51
72000105	SIGN PANEL - TYPE 1 (SPECIAL)	SQ FT	12		12	
72000205	SIGN PANEL - TYPE 2 (SPECIAL)	SQ FT	28	28		
72000305	SIGN PANEL - TYPE 3 (SPECIAL)	SQ FT	89	89		
72700200	TUBULAR STEEL SIGN SUPPORT - BREAKAWAY	POUND	751	751		
72900100	METAL POST - TYPE A	FOOT	63	12		51
72900200	METAL POST - TYPE B	FOOT	626	358	211	57
73000100	WOOD SIGN SUPPORT	FOOT	177	128	34	15
73400100	CONCRETE FOUNDATIONS	CU YD	4.2	4.2		
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	117	81	36	
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	4,835	1254	1133	2448
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2,963	191	694	2078
78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	1,672	898	774	
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	68	68		
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	796	384	160	252
78006100	PREFORMED THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	83	8	15	60
78200300	PRISMATIC CURB REFLECTOR	EACH	108	74	34	
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1	0.50	0.50	
89502380	REMOVE EXISTING HANDHOLE	EACH	4	2	2	
89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	5	3	2	
A2001120	TREE, ACER RUBRUM OCTOBER GLORY (OCTOBER GLORY RED MAPLE), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	4	1	3	
A2001220	TREE, ACER RUBRUM RED SUNSET (RED SUNSET RED MAPLE), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	4	2	1	1
A2003570	TREE, FRAXINUS AMERICANA AUTUMN PURPLE (AUTUMN PURPLE WHITE ASH), 8" HEIGHT, CLUMP FORM, BALLED AND BURLAPPED	EACH	2		1	1

CODE NO.	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODES		
				IL 160 / POPLAR		POPLAR
				STATE	CMAQ	STU
A2005420	TREE, LIRODENDRON TULIPIFERA (TULIP TREE), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	2		2	
A2007120	TREE, QUERCUS RUBRA (RED OAK), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	2		2	
B2001168	TREE, CERCIS CANADENSIS (EASTERN REDBUD) 7' HEIGHT, CLUMP FORM, BALLED AND BURLAPPED	EACH	8	2	5	1
B2001386	TREE, CORNUS FLORIDA (FLOWERING DOGWOOD), 6' HEIGHT, CLUMP FORM, BALLED AND BURLAPPED	EACH	10	1	5	4
C2C02618	SHRUB, EUONYMUS ALATA COMPACTA (DWARF WINGED EUONYMUS), 18" HEIGHT, CONTAINER	EACH	14			14
D2001872	EVERGREEN, PICEA GLAUCA (WHITE SPRUCE), 6' HEIGHT, BALLED AND BURLAPPED	EACH	2	1	1	
D2002088	EVERGREEN, PICEA OMORIKA (SERBIAN SPRUCE), 8' HEIGHT, BALLED AND BURLAPPED	EACH	2	1	1	
D2002288	EVERGREEN, PICEA PUNGENS GLAUCA (COLORADO BLUE SPRUCE), 8' HEIGHT, BALLED AND BURLAPPED	EACH	2	2		
LR430030	CONCRETE PAVER PAVEMENT	SQ YD	658	286	372	
X7800200	PAINT PAVEMENT MARKING CURB	FOOT	646	419	227	
XX000731	CASING PIPE	FOOT	182		182	
XX002176	CONCRETE STEP REMOVAL	L SUM	1			1
XX003470	SANITARY CLEANOUT 6"	EACH	2			2
XX005431	LOCATING UNDERGROUND UTILITY	EACH	20	1	12	7
XX146400	STORM SEWER REMOVAL	FOOT	516	45	395	76
Z0015000	CURB STOPS 1"	EACH	5	3	2	

• SPECIALITY ITEMS

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8852	D6-00056-01-WR	MADISON	81	4
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
SUMMARY OF QUANTITIES				

CONTRACT NO. 97324