

## EROSION CONTROL SCHEDULE

LOCATION IL 34	STONE RIPRAP CLASS A3	STONE RIPRAP CLASS A4	FILTER FABRIC	PERIMETER EROSION BARRIER	EROSION CONTROL BLANKET	DITCH CHECKS	INLET & PIPE PROTECTION
	SQ YD	SQ YD	SQ YD	FOOT	SQ YD	EACH	EACH
LT STA 172+50 TO 173+00				507	44		
LT STA 173+00 TO 177+25				444			
RT STA 173+00 TO 177+10					472		
RT STA 173+50 TO 176+20				534			
RT STA 177+10 TO 182+25				532			
LT STA 177+40 TO 182+50					280		
RT STA 177+96 TO 179+50						1	
RT STA 178+00						1	
RT STA 178+75							1
RT STA 177+90						1	
RT STA 181+00							1
RT STA 181+55							1
<b>RUNAROUND</b>							
LT STA 0+90 TO 4+70					924		
RT STA 2+40 TO 4+60					373		
LT STA 4+90 TO 8+40					372		
RT STA 4+80 TO 6+90					306		
LT STA 2+91.76		5	5				
RT STA 2+91.76							1
RT STA 3+25						1	
RT STA 4+90 TO 5+46		27	27				
RT STA 6+25						1	
<b>TOTALS</b>	<b>0</b>	<b>32</b>	<b>32</b>	<b>2017</b>	<b>2771</b>	<b>5</b>	<b>3</b>

## PAVEMENT MARKING SCHEDULE

LOCATION IL 34	SHORT-TERM PAVEMENT MARKING	TEMPORARY PAVEMENT MARKING LINE-4"	PAINT PAVEMENT MARKING LINE-4"
	FOOT	FOOT	FOOT
STA 174+45 TO 175+98.74	28	615	615
STA 175+98.74 TO 178+36.02	24	949	949
STA 178+36.02 TO 182+80	84	1,776	1,776
<b>TOTALS</b>	<b>136</b>	<b>3,340</b>	<b>3,340</b>

## TREE REMOVAL SCHEDULE

LOCATION IL 34	TREE REMOVAL 6 TO 15 UNITS DIAMETER	TREE REMOVAL OVER 15 UNITS DIAMETER	LOCATION IL 34	TREE REMOVAL 6 TO 15 UNITS DIAMETER	TREE REMOVAL OVER 15 UNITS DIAMETER
	UNITS	UNITS		UNITS	UNITS
<b>NORTHWEST QUADRANT</b>			<b>SOUTHEAST QUADRANT (CONT.)</b>		
STA. 172+70, 28' LT		30	STA. 180+70, 22' RT	7	
STA. 172+75, 27' LT	6		STA. 180+75, 23' RT	6	
STA. 172+85, 28' LT	9		STA. 180+85, 35' RT	9	
STA. 172+85, 28' LT	15		STA. 180+90, 28' RT	6	
STA. 174+25, 52' LT	6		STA. 181+00, 24' RT	6	
STA. 175+00, 63' LT	6		STA. 181+00, 24' RT	6	
STA. 175+70, 78' LT	6		STA. 181+00, 40' RT	6	
STA. 175+75, 73' LT	7		STA. 181+20, 23' RT	7	
STA. 176+00, 75' LT	6		STA. 181+20, 23' RT	7	
STA. 176+50, 82' LT	6		STA. 181+20, 36' RT	6	
STA. 176+60, 80' LT	6		STA. 181+30, 20' RT	6	
STA. 176+65, 82' LT	6		STA. 181+40, 21' RT		16 (DEAD)
STA. 176+65, 82' LT	7		STA. 181+40, 35' RT	6	
STA. 176+65, 82' LT	13		STA. 181+40, 35' RT	8	
<b>NORTHEAST QUADRANT</b>			STA. 181+45, 24' RT	6	
STA. 178+00, 61' LT	7		STA. 181+50, 26' RT	6	
STA. 178+05, 51' LT	11		STA. 181+60, 27' RT	7	
<b>SOUTHWEST QUADRANT</b>			STA. 181+60, 35' RT	8	
STA. 173+60, 31' RT	10		STA. 181+70, 37' RT	10	
STA. 173+60, 31' RT	10		STA. 181+75, 20' RT	15	
STA. 173+60, 31' RT	12		STA. 181+75, 34' RT	12	
STA. 174+15, 37' RT	6		STA. 181+80, 26' RT	8	
STA. 174+25, 33' RT	10		STA. 181+90, 35' RT	8	
STA. 174+35, 39' RT	6		STA. 182+00, 20' RT		19
STA. 174+50, 36' RT		18	STA. 182+00, 35' RT	7	
STA. 174+50, 37' RT		19	STA. 182+00, 35' RT	9	
STA. 175+10, 35' RT	7		STA. 182+10, 27' RT	6	
STA. 175+10, 35' RT	10		STA. 182+10, 33' RT	6	
STA. 175+10, 35' RT	12		STA. 182+15, 33' RT	6	
STA. 175+20, 29' RT	13		STA. 182+20, 26' RT	7	
STA. 176+25, 24' RT	6		STA. 182+20, 32' RT	15	
<b>SOUTHEAST QUADRANT</b>			STA. 182+25, 26' RT	8	
STA. 177+65, 29' RT	12		STA. 182+40, 34' RT	9	
STA. 177+85, 25' RT	8		STA. 182+46, 25' RT	6	
STA. 177+85, 25' RT	12		STA. 182+48, 30' RT	8	
STA. 178+00, 22' RT	8		STA. 182+50, 30' RT	7	
STA. 178+00, 22' RT	9		STA. 182+65, 35' RT	6	
STA. 178+25, 24' RT	7				
STA. 178+25, 24' RT		28	<b>TOTALS</b>	<b>541</b>	<b>130</b>

## FENCE SCHEDULE

LOCATION IL 34	TEMPORARY FENCE	FENCE REMOVAL
	FOOT	FOOT
LT STA 178+45 TO 182+25	400	
LT STA 178+30 TO 182+25		460
<b>TOTALS</b>	<b>400</b>	<b>460</b>

11/19/2007  
 50.0000 / JK  
 dse-ar-0191