



BILL OF MATERIAL

CHANNEL EXCAVATION	CU YD	48
CLASS C PATCHES, TYPE 4, 12 INCH	SQ YD	33
REMOVAL OF EXISTING STRUCTURES NO. 4	EACH	1
PIPE CULVERTS, CLASS A (RCCP), TYPE 2 48"	FOOT	77
TOPSOIL EXCAVATION AND PLACEMENT	CU YD	28
CONTROLLED LOW STRENGTH MATERIAL	CU YD	73
SEEDING, MULCHING AND FERTILIZING	ACRE	0.03
TEMPORARY EROSION CONTROL SEEDING	POUND	3
STONE RIPRAP, CLASS A5	SQ YD	220
FILTER FABRIC	SQ YD	220
NON-RESTRICTIVE FENCE	FOOT	44
TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	24

Note: The finished surface of the Class C Patch shall match the existing pavement surface

Designed By GMS checked By TMM
 Drawn By STN checked By TMM
 12/13/2012 5:35:20 PM
 C:\OwrProj\p\Projects\ASHLAND\Plan Sheets\sheet 14.dgn