	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE														
					A	B	C	D	E	F	G	H	I	J	K	L	M	N	O
					0003	0040	0040	0040	0040	0010	0010	0021	0021	0021	0021	0028	0028	0003	0003
					URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN
X	JS250318	SEEDING, CLASS 4F	ACRE	1.50															1.50
	JT420000	WHITEWASHING FOR CONCRETE PAVEMENT	SQ YD	12694															12694
	JI420005	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SQ YD	7420															7420
	JI420010	PORTLAND CEMENT CONCRETE PAVEMENT 12" (JOINTED)	SQ YD	5274															5274
	JI440010	CONCRETE MEDIAN BARRIER AND BASE REMOVAL	FOOT	208															208
	JI440022	SHOULDER RUMBLE STRIP REMOVAL	SQ YD	9967															9967
	JI481040	AGGREGATE SHOULDERS, TYPE B	TON	951	1													1	951
	JI481070	AGGREGATE SHOULDERS SPECIAL, TYPE C	TON	382															382
	JI482004	HOT-MIX ASPHALT SHOULDERS (6 IN.)	SQ YD	11471															11471
	JI602000	INLET, SLOPE DRAIN	EACH	1															1
	JI602031	CATCH BASIN, TYPE G-2 (MODIFIED)	EACH	2															2
	JI602115	CATCH BASINS, TYPE G-2, TYPE G-2 FRAME AND GRATE	EACH	13															13

X SPECIALTY ITEM

A ROADWAY AND DRAINAGE - 100% STATE
B RETAINING WALL SN 022-W063 - 100% STATE
C RETAINING WALL SN 022-W064 - 100% STATE
D RETAINING WALL SN 022-W065 - 100% STATE
E RETAINING WALL SN 022-W066 - 100% STATE
F BRIDGE SN 022-2029 - 100% STATE
G BRIDGE SN 022-2030 - 100% STATE
H LIGHTING - 100% STATE
I TRAFFIC SIGNALS, TRAFFIC SIGNAL INTERCONNECT, TEMPORARY TRAFFIC SIGNAL INTERCONNECT - 100% STATE
J TRAFFIC SIGNALS EVP EQUIPMENT - 100% NAPERVILLE
K NEW SIDEWALK - 80% STATE, 20% NAPERVILLE
L SHARED-USE PATH - 80% STATE, 20% NAPERVILLE
M SHARED-USE PATH - 100% NAPERVILLE
N ROADWAY ITEMS - 100% STATE
O ROADWAY, DRAINAGE, RETAINING WALLS, LIGHTING AND BRIDGE SUBSTRUCTURE - 100% TOLLWAY

1 Rev. 1-3-13

FILE NAME =	USER NAME = {USER}	DESIGNED PJO	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
{FILE}		DRAWN KES	REVISED -			338	(112 & 113) WRS-5	DUPAGE	963	39
	PLOT SCALE = {SCALE}	CHECKED JCM	REVISED -					CONTRACT NO. 60I31		
	PLOT DATE = {DATE}	DATE 10/15/2012	REVISED -		SCALE: SHEET NO. 34 OF 41 SHEETS STA. TO STA.		ILLINOIS FED. AID PROJECT			