

CONSTRUCTION CODE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O
				0003	0040	0040	0040	0040	0010	0010	0021	0021	0021	0021	0028	0028	0003	0003
				URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN
J1680121	SLOPED HEADWALL TYPE III, 12", 1:3	EACH	5															5
J1680123	SLOPED HEADWALL TYPE III, 18", 1:3	EACH	1															1
J1680125	SLOPED HEADWALL TYPE III, 24", 1:3	EACH	2															2
J1680130	SLOPED HEADWALL TYPE III, 6", 1:4	EACH	9															9
J1680135	SLOPED HEADWALL TYPE III, 24", 1:4	EACH	1															1
J1680140	SLOPED HEADWALL TYPE III, 6", 1:6	EACH	7															7
JS701010	MAINTENANCE OF TRAFFIC	L SUM	1															1
X JT720120	SIGN INSTALLATION, TYPE 3	SQ FT	700															700
X JS733070	OVERHEAD SIGN STRUCTURE, SPAN TYPE (ALUMINUM) (70 FT)	FOOT	71															71
X JS733080	OVERHEAD SIGN STRUCTURE, SPAN TYPE (ALUMINUM) (80 FT)	FOOT	81															81
X JS734A10	FOUNDATION FOR OVERHEAD SIGN STRUCTURE, SPAN TYPE	CU YD	29															29
X J1780245	POLYUREA PAVEMENT MARKING TYPE I - LINE 10"	FOOT	10,265	823														15,442

X SPECIALTY ITEM

- | | | |
|---|--|---|
| A ROADWAY AND DRAINAGE - 100% STATE | H LIGHTING - 100% STATE | M SHARED-USE PATH - 100% NAPERVILLE |
| B RETAINING WALL SN 022-W063 - 100% STATE | I TRAFFIC SIGNALS, TRAFFIC SIGNAL INTERCONNECT, TEMPORARY TRAFFIC SIGNAL INTERCONNECT - 100% STATE | N ROADWAY ITEMS - 100% STATE |
| C RETAINING WALL SN 022-W064 - 100% STATE | J TRAFFIC SIGNALS EVP EQUIPMENT - 100% NAPERVILLE | O ROADWAY, DRAINAGE, RETAINING WALLS, LIGHTING AND BRIDGE SUBSTRUCTURE - 100% TOLLWAY |
| D RETAINING WALL SN 022-W065 - 100% STATE | K NEW SIDEWALK - 80% STATE, 20% NAPERVILLE | |
| E RETAINING WALL SN 022-W066 - 100% STATE | L SHARED-USE PATH - 80% STATE, 20% NAPERVILLE | |
| F BRIDGE SN 022-2029 - 100% STATE | | |
| G BRIDGE SN 022-2030 - 100% STATE | | |

Rev. 1-3-13

FILE NAME	USER NAME - JUSHPH	DESIGNED PJO	REVISIONS	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
FILED	DRAWN KES	CHECKED JCM	DATE 10/15/2012					338	(112 & 113) WRS-5	DUPAGE	963	41
PLOT SCALE - 1"=400'	DATE	REVISIONS	SCALE:					SHEET NO. 36 OF 41 SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT	
PLOT DATE - 10/15/12	REVISIONS	CONTRACT NO. 60131										