

SEE NOTE 1

INTERCONNECT CONDUIT AND HANDHOLES TO BE INSTALLED WITH CONTRACT 60131

INTERCONNECT CONDUIT AND HANDHOLES TO BE INSTALLED WITH CONTRACT 60R31

1. THIS HANDHOLE TO BE INSTALLED WITH CONTRACT 60131. CONTRACTOR TO PROVIDE CONDUIT STUB IN HANDHOLE FOR CONNECTION OF 2" CONDUIT INSTALLED UNDER CONTRACT 60R31.
2. RESIDENT ENGINEER TO VERIFY THAT ALL FIBER OPTIC CABLE TERMINATIONS HAVE BEEN MADE PRIOR TO TRANSFER OF MAINTENANCE TO IDOT.


A

FIBER OPTIC AND TRACER CABLES BETWEEN I-88 SOUTH RAMPS COMMUNICATIONS CABINET AND FERRY RD CONTROLLER SHALL BE INSTALLED UNDER CONTRACT 60131.

FIBER OPTIC AND TRACER CABLES BETWEEN NORTH AURORA RD AND I-88 SOUTH RAMPS COMMUNICATIONS CABINET, SHALL BE INSTALLED UNDER CONTRACT 60R31.

THE TEMPORARY AERIAL FIBER OPTIC INTERCONNECT SHALL BE REMOVED UNDER CONTRACT 60R31 ONCE THE PERMANENT FIBER OPTIC CABLE AND TRACER CABLE ARE INSTALLED AND ACCEPTED BY THE ENGINEER.

THE TRAFFIC SIGNAL CONTROL EQUIPMENT FOR THIS PROJECT SHALL BE "ECONOLITE" TO MATCH THE EXISTING ADJACENT SYSTEM



| | | | | | | | | | | | | |
|-------------|--------------------|-------------------|---------------------------------|---|--|---------------------------|--------------|---------------|---------------------------|--------------------|------------------|---------------|
| FILE NAME * | USER NAME * #USER# | DESIGNED - DW | REVISED - ADDENDUM A 12/17/2012 | STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION | INTERCONNECT PLAN IL ROUTE 59 FROM DIEHL ROAD TO FERRY ROAD | | | F.A. RTE. 338 | SECTION (112 & 113) WRS-5 | COUNTY DUPAGE | TOTAL SHEETS 963 | SHEET NO. 463 |
| #FILE# | | DRAWN - JDH | REVISED - | | SCALE: 1"=50' | SHEET NO. 48 OF 53 SHEETS | STA. TO STA. | TS-47 | | CONTRACT NO. 60131 | | |
| | | CHECKED - KMM | REVISED - | | | | | | | | | |
| | | DATE - 10/15/2012 | REVISED - | | | | | | | | | |