

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE						
				<i>URBAN</i>						
				80% FED - 20% STATE	80% FED/ 15% STATE/ 5% LEMONT	80% FED/ 15% STATE/ 5% LEMONT	100% LEMONT	100% LEMONT	100% LEMONT	
ROADWAY	TRAFFIC SIGNALS	TRAFFIC SIGNAL INTERCONNECT	SAFETY	EMERGENCY VEHICLE PREEMPTION (EVP)	LOCAL					
0004	0021	0021	0021	0021	0021					
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	203	203						
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	203	203						
* 25100630	EROSION CONTROL BLANKET	SQ YD	9014	9014						
* 25200110	SODDING, SALT TOLERANT	SQ YD	804	804						
28000200	EARTH EXCAVATION FOR EROSION CONTROL	CU YD	195	195						
* 28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	200	200						
28000305	TEMPORARY DITCH CHECKS	FOOT	300	300						
28000400	PERIMETER EROSION BARRIER	FOOT	573	573						
28000510	INLET FILTERS	EACH	28	28						
28001000	AGGREGATE (EROSION CONTROL)	TON	3	3						
28100105	STONE RIPRAP, CLASS A3	SQ YD	8	8						
28100107	STONE RIPRAP, CLASS A4	SQ YD	5	5						
28200200	FILTER FABRIC	SQ YD	13	13						
30300001	AGGREGATE SUBGRADE IMPROVEMENT	CU YD	156	156						
30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SQ YD	5910	5910						
31101200	SUBBASE GRANULAR MATERIAL, TYPE B, 4 INCH	SQ YD	1549	175			1374			1374

Rev.
* - DENOTES SPECIALTY ITEM

FILE NAME:	USER NAME: vjgsl	DESIGNED - RG	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.U. RTE. 1587	SECTION 3099-R	COUNTY COOK	TOTAL SHEETS 95	SHEET NO. 1
PLANT SCALE: 1/8"=1'-0"	CHECKED - MGR	REVISIONS	SCALE:					SHEET NO. OF SHEETS	STA. TO STA.	ILLINOIS FED. AID PROJECT		
PLANT DATE: 10/24/2012	DATE - MARCH, 2012	REVISIONS					CONTRACT NO. 60L79					